



Remove exist'g handrails and install new painted galv. steel rails consisting of 1 1/2" O.D. schedule 40 pipe. Set rail at 34" off of nosings and attach to existing brick walls

WINTON SCOTT ARCHITECTS, PA
 5 Milk Street
 Portland, Maine 04101
 207 774 4811

Portland Community
 Health Clinic- Renovation
 Project

ASK 3

October. 23, 2012