

NOTES

1. SEE E000 FOR ELECTRICAL LEGEND, ABBREVIATIONS, AND GENERAL NOTES.
2. SEE SHEET A103 FOR ADDITIONAL PHASING INFORMATION.


3. CONNECT NEW EXIT/EMERGENCY LIGHTS TO LOCAL 120V LIGHTING CIRCUIT.
 4. CONNECT NEW FIRE ALARM DEVICES TO EXISTING FIRE ALARM SYSTEM
 FROM PANEL C-6. IN ELECTRICAL PANELS, PROVIDE NEW TO SUPPORT BATTERIES.
 SYSTEMS HAS THE CAPABILITY TO SUPPORT BATTERIES.
 ADDITIONAL DEVICES SHOWN. PROVIDE ALL AUXILIARY EQUIPMENT, EXISTING
 PROGRAMMING AND COMMISSIONING FOR A COMPLETE INSTALLATION. EXISTING
 FIRE ALARM CONTROL PANEL IS MANUFACTURED BY FARADAY MODEL #: MPC-6000. INSTALLATION OF ALL NEW FIRE ALARM COMPONENTS SHALL BE
 COORDINATED WITH PROTECTION PROFESSIONALS OF FALMOUTH, ME. PHONE
 NEW.

5. #. (207)-775-9755 TO ENSURE PROPER INTEGRATION FOR A COMPLETE AND OPERABLE SYSTEM.
 THE BUILDING DOES NOT CONTAIN A SPRINKLER SYSTEM FOR FIRE SUPPRESSION. NEW SMOKE DETECTORS AND NOTIFICATION DEVICES SHALL BE FURNISHED AND INSTALLED AS SHOWN. IN THE EVENT A DEVICE IS NOT SHOWN WHERE IT IS REQUIRED BY CODE, CONTRACTOR SHALL FURNISH AND INSTALL DEVICES AS NECESSARY TO COMPLY WITH CODE.
6. FIXTURES DENOTED AS "EX" ARE EXISTING FIXTURES THAT HAVE BEEN RE-INSTALLED IN NEW CEILING AND SERVICED AS REQUIRED BY NOTE 5 ON SHEET E200.
7. LIGHT SWITCHES, DEVICES, AND FIXTURES SHOWN IN BOLD DENOTED WITH LETTER DESIGNATIONS (I.E. "A") SHALL BE FURNISHED AND INSTALLED AS NEW.

KEYED NOTES:

- ① FURNISH TIME DELAY SWITCH FOR BATHROOM EXHAUST FANS. CONNECT EXHAUST FAN TO BATHROOM LIGHTING CIRCUIT. COORDINATE SWITCH WITH EQUIPMENT FURNISHED.
- ② VERIFY EXISTING SMOKE DETECTOR IN FACP ROOM. FURNISH AND INSTALL NEW SMOKE DETECTOR IF THEIR IS NO EXISTING DETECTOR IN ROOM.

① REVISIONS PER FIRE MARSHALL REVIEW COMMENTS. 10.15.12



Winton Scott Architects
 5 Milk Street
 Portland, Maine 04101
 207 774 4811
 www.wintonsscott.com

Architecture / Planning
 Preservation Architecture
 Interior Architecture



**Portland
 Community
 Health Center**

180 Park Avenue
 Portland, Maine

