

Daniel S. Chase, PE
Structural & Construction Engineering
26 Stonybrook Rd.
Cape Elizabeth, ME 04107
207.799.9087
dchasepe@gmail.com

February 22, 2017

Ian Taber
548 Stevens Ave.
Portland, ME 04103

Recommended exterior stairway modifications for 105 Sherman St., Portland, ME.

1. 9 in. long (minimum) vertical bearing blocks beneath carrying beams - 6 locations. Face nail/screw to support posts.
2. Sloped seat hangers for tops of stair stringers - 4 stringers. Face nail to carrying beam.
3. Double 2X bearing blocking for bottoms of stair stringers. Bolt through carrying beam with 1/2 in. bolt below each stringer.

I FREEMAN SCOTT, ADDRESSED ALL ITEMS
AND WENT ABOVE AND BEYOND WITH FASTENER
~~AND~~ SIZE AND AMOUNT PER LOCATION AT
105 SHERMAN ST. ON FEB 21ST.

FREEMAN SCOTT, 