

A 2 WALL & FLOOR FRAMING DETAILS

WINDOW SCHEDULE

All newly built exterior walls above new concrete foundation walls to be 2x4 construction, 16" o.c., same as existing, with R-21 spray foam insulation.

All newly built floors will be 2x8 construction, 16" o.c., same as existing, with R-21 spray foam insulation.

Window schedule:

One 24" W by 68" H double hung.

One 30" W by 30" H fixed pane.

One 28" W by 36" H double hung.

All are Alside Sheffield triple glazed double argon, double low-e, 0.23 U-factor.