



(207) 435-2171

101 Main St
 PO Box 623
 Ashland ME 04732

Estimate

Date	Estimate #
9/30/2015	802

Name / Address
Portland Sea Dogs PO Box 636 Portland ME 04104

Project

Description	Cost	Qty	Total
Materials	45,880.90		45,880.90T
Labor	26,750.00		26,750.00
<p>This quote will include material, labor, start up / testing required to install heat pumps in seventeen VIP boxes, 1st floor offices, and jumbotron room. A total of twenty evaporator heads, all heads will be cassette style and will fit in the drop ceiling T-bar grid. All condensate will be pumped into the building drain system. The existing a/c systems will not have to be removed before the new cassettes can be installed. All electrical power will be taken from the existing 30 amp a/c breaker. All condensing units will be mounted on the roof of VIP boxes.</p> <p>(4) Daikin 4MXS36NMVJU (1) Daikin 3MXS24NMVJU (2) Daikin 2MXS18NMVJU</p> <p>Luxury Boxes 4MXS36NMVJU with four FFQ09LVJU 4MXS36NMVJU with four FFQ09LVJU 4MXS36NMVJU with four FFQ09LVJU 3MXS24NMVJU with three FFQ09LVJU 2MXS18NMVJU with two FFQ09LVJU</p> <p>Office Unit 2MXS18NMVJU with one FFQ12LVJU</p> <p>Press Box & Jumbo Tron 4MXS36NMVJU with two FFQ18LVJU sales tax</p>			
	5.50%		2,523.45
Quote prices are good for 30 days.		Total	\$75,154.35

Customer Signature _____