

Page 7 = Fan Specs

EXHAUST FAN INFORMATION - Job#2468448

FAN UNIT NO.	TAG	FAN UNIT MODEL #	CFM	ESP	RPM	H.P.	3/4 H.P.	Ø	VOLT	FLA	DISCHARGE VELOCITY	WEIGHT (LBS.)/SONES
1	Area 1	CASRE20BD	2400	2.000	1288	3.000	2.0790	1	230	17.0	1115 FPM	451 19.7
2	Area 2	CASRE20BD	2400	2.000	1288	3.000	2.0790	1	230	17.0	1115 FPM	451 19.7

FAN OPTIONS

FAN UNIT NO.	TAG	OPTION (Qty. - Descr.)
1	Area 1	1 - Full Crating For Exhaust Fans
		1 - Utility Set Grease Cup
		1 - 3 Year Extended Motor Warranty
1	Area 1	1 - Extra Set of Belts
		1 - Fan Base Ceramic Seal - For Grease Ducts
		1 - RE20 - Rain Cap Assembly - Includes Hardware And Gasket.
2	Area 2	1 - Full Crating For Exhaust Fans
		1 - Utility Set Grease Cup
		1 - 3 Year Extended Motor Warranty
2	Area 2	1 - Extra Set of Belts
		1 - Fan Base Ceramic Seal - For Grease Ducts
2	Area 2	1 - RE20 - Rain Cap Assembly - Includes Hardware And Gasket.

FAN ACCESSORIES

FAN UNIT NO.	TAG	EXHAUST	SUPPLY
		GREASE CUP DAMPER	WALL MOUNT DISCHARGE DAMPER
1	Area 1	YES	
2	Area 2	YES	

URB ASSEMBLIES

NO.	DN FAN	WEIGHT	ITEM	SIZE
1	# 1	30 LBS	Curb	26.500"W x 26.500"L x 24.000"H 3.000x12.000 Pitch Vented
2	# 2	30 LBS	Curb	26.500"W x 26.500"L x 24.000"H 3.000x12.000 Pitch Vented

ROOF PITCH FOR CURBS) MUST BE SPECIFIED PRIOR TO RELEASING ORDER
 ---:12

CUSTOMER APPROVAL TO MANUFACTURE:

covered as Noted
 covered with ND Exception Taken
 see and Resubmit
 DATE _____ Date _____



CAPTIVEAIRE

JOB Portland Sea Dogs r1
 LOCATION LEWISTON, ME, JOB # 2468448
 DATE 11/3/2015
 DWG # 4 DRAWN BY BFC-21
 REV. SCALE 3/8" = 1'-0"