ROOM FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR	BASE	WALL				CEILING		ROOM NO.	REMARKS
				NORTH	EAST	SOUTH	WEST	MATL	HEIGHT		
101	PLAYERS LOUNGE	CARPET	*	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	ACT	8'-0"	101	
102	KITCHEN	EPOXY PAINT	*	-	GWB-1 / PT	GWB-1 / PT	-	ACT	8'-0"	102	
103	STAIRS	CARPET	*	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	GWB-1	*	103	CEILING HEIGHT SHALL BE TO UNDERSIDE OF COLLAR TIES
104	LOCKER ROOM	CARPET	*	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	GWB-1	*	104	CEILING HEIGHT SHALL BE TO UNDERSIDE OF JOISTS, SOFFIT SHALL BE ACT AT 8'-0"
105	PLAYER'S BATH	EPOXY PAINT	*	GWB-2 / PT	GWB-2 / PT	GWB-2 / PT	GWB-2 / PT	GWB-2	*	105	CEILING HEIGHT TO UNDERSIDE OF JOISTS
106	LAUNDRY	EPOXY PAINT	*	GWB-2 / PT	GWB-2 / PT	GWB-2 / PT	GWB-2 / PT	GWB-2	*	106	CEILING HEIGHT TO UNDERSIDE OF JOISTS
107	STORAGE	EPOXY PAINT	*	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	GWB-1		107	CEILING HEIGHT TO UNDERSIDE OF JOISTS
108	RESERVED										
109	SPRINKLER ROOM-EXISTING	EXISTING								109	EXISTING
110	MANAGER'S OFFICE	CARPET	*	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	ACT	8'-6"	110	
111	MANAGER'S BATH	EPOXY PAINT	*	GWB-2 / PT	GWB-2 / PT	GWB-2 / PT	GWB-2 / PT	GWB-2	8'-6"	111	
112	HALL	CARPET	*	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	ACT	8'-6"	112	
113	CLOSET	EPOXY PAINT	*	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	ACT	8'-0"	113	
114	CLOSET	EPOXY PAINT	*	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	ACT	8'-0"	114	
115	CLOSET	EPOXY PAINT	*	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	ACT	8'-0"	115	
116	COACH'S OFFICE	CARPET	*	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	ACT	8'-6"	116	
117	COACH'S BATH	EPOXY PAINT	*	GWB-2 / PT	GWB-2 / PT	GWB-2 / PT	GWB-2 / PT	GWB-2	8'-6"	117	
118	TRAINER'S ROOM	CARPET	*	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	ACT	8'-6"	118	
119	TRAINER'S OFFICE	CARPET	*	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	GWB-1 / PT	ACT	8'-6"	119	
120	WHIRLPOOL ROOM	EPOXY PAINT	*	GWB-2 / PT	GWB-2 / PT	GWB-2 / PT	GWB-2 / PT	GWB-2	8'-6"	120	
121	MECHANICAL ROOM	CONCRETE	*	GWB-1 / PT	GWB-1 / PT	*	GWB-1 / PT	GWB-1	*	121	CEILING HEIGHT TO UNDERSIDE OF JOISTS GWB-1 ON BOTH SIDES OF CHASE WALL
201	BATTING CAGE	CONCRETE	*	3/4" ADVANTECH	3/4" ADVANTECH	3/4" ADVANTECH	3/4" ADVANTECH	3/4" ADVANTECH	X'-X"	201	CEILING HEIGHT SHALL BE TO UNDERSIDE OF RAFTERS
202	WEIGHT ROOM	RUBBER MAT	*	GWB-1	GWB-1	GWB-1	GWB-1	GWB-1	*	202	CEILING HEIGHT SHALL BE TO UNDERSIDE OF RAFTERS
203	BULLPEN BENCH	CONCRETE	*						X'-X"	203	XXX
204	BULLPEN	CONCRETE	*	CHAINLINK FENCE	CHAINLINK FENCE	OPEN	HARDIPLANK	N/A	X'-X"	204	XXX

G1 / AE610 ROOM FINISH SCHEDULE

N/A

NOTES:

1. SEE SHEET T-1 FOR LEGEND, ABBREVIATIONS & GENERAL NOTES.
2. RE SPECIFICATIONS FOR ADDITIONAL INFORMATION REGARDING FINISH MATERIALS.
3. ALL GWB WALLS TO BE PAINTED UNO.
4. PROVIDE FLOORING TRANSITION STRIPS AT THE JUNCTURE OF ALL FLOORING MATERIALS, AND IN THE CENTERS OF ALL DOORS.
5. ALL COLUMNS, INCLUDING THOSE BURIED IN WALLS, SHALL BE WRAPPED WITH TYPE X GWB PER DETAIL E1/ AE421.

KEY

ACT-1	ACOUSTIC CEILING TILE 2x4
ACT-2	ACOUSTIC CEILING TILE 2x2
ACT-3	ACOUSTIC CEILING TILE 4x4
CPT	CARPET
CT	CERAMIC TILE
CONC	CONCRETE
EP	EPOXY PAINT
EXP	EXPOSED STRUCTURE
GWB-1	5/8" GYPSUM WALL BOARD - TYPE X
GWB-2	5/8" MOISTURE RESISTANT GYPSUM WALL BOARD - TYPE X
PT	PAINT
RB	RUBBER BASE
SWC	SEAMLESS WALL COVERING
SV	SHEET VINYL
VCT	VINLY COMPOSITION TILE

DOMUS ARCHITECTS

PO BOX 301
FREEPORT, MAINE
04032

CUYLER M. FEAGLES No.2529 LICENSED ARCHITECT STATE OF MAINE

TEL 207-865-1272
FAX 207-865-XXXX
WWW.DOMUSARCHITECTS.NET

NOTES/ REVISIONS

PORTLAND SEA DOGS CLUB HOUSE

HADLOCK FIELD
PORTLAND, ME

ISSUED FOR CONSTRUCTION
8/6/07

AE-610

ROOM FINISH SCHEDULE