



SPECIAL INSPECTIONS (REFERENCE IBC CHAPTER 17):

GENERAL: WHERE APPLICATION IS MADE FOR CONSTRUCTION, THE OWNER OR THE REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE ACTING AS THE OWNER'S AGENT SHALL EMPLOY ONE OR MORE APPROVED AGENCIES TO PERFORM INSPECTIONS DURING CONSTRUCTION ON THE TYPES OF WORK LISTED IN THE INSPECTION CHECKLIST ABOVE. THE REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE AND ENGINEERS OF RECORD INVOLVED IN THE DESIGN OF THE PROJECT ARE PERMITTED TO ACT AS THE APPROVED AGENCY AND THEIR PERSONNEL ARE PERMITTED TO ACT AS THE SPECIAL INSPECTOR FOR THE WORK DURING CONSTRUCTION.

STATEMENT OF SPECIAL INSPECTIONS: THE APPLICANT SHALL SUBMIT A STATEMENT OF SPECIAL INSPECTIONS PREPARED BY AN APPROVED AGENCY IN ACCORDANCE WITH SECTION 107.1 AS A CONDITION FOR ISSUANCE. THIS STATEMENT SHALL BE IN ACCORDANCE WITH SECTION 1705.

REPORT REQUIREMENT: SPECIAL INSPECTIONS SHALL KEEP RECORDS OF THE SPECIAL INSPECTIONS AND SUBMIT WRITTEN INSPECTION REPORTS TO THE BUILDING OFFICIAL AND TO THE REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE. REPORTS SHALL INDICATE THAT WORK INSPECTED WAS OR WAS NOT COMPLETED IN CONFORMANCE TO APPROVED CONSTRUCTION DOCUMENTS. DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTOR FOR CORRECTION. IF THEY ARE NOT CORRECTED, THE DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE BUILDING OFFICIAL AND TO THE REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE. A FINAL REPORT DOCUMENTING REQUIRED SPECIAL INSPECTIONS SHALL BE SUBMITTED.

SPECIAL INSPECTION CHECKLIST	
BEFORE CONSTRUCTION	
CONSTRUCTION/INSTALLATION TESTING REQUIRED (NUMBER OF RECORD)	REPORT ITEM
REQUIRED	ENGINEER OF RECORD APPROVED SHOP DRAWINGS
REQUIRED	MATERIAL SPECIFICATIONS REPORT
N/A	FABRICATOR WET INSPECTION
N/A	WET REPORT OR MONITORING TEST (TYP. AS TESTED)
REQUIRED	PACKING SLIPS*
ADDITIONAL TESTING AND INSPECTIONS:	
DURING CONSTRUCTION	
CONSTRUCTION/INSTALLATION INSPECTIONS AND TESTING REQUIRED (NUMBER OF RECORD)	REPORT ITEM
REQUIRED	STEEL INSPECTIONS
N/A	HIGH STRENGTH BOLT INSPECTIONS
N/A	HIGH WIND ZONE INSPECTIONS
N/A	FOUNDATION INSPECTIONS
N/A	CONCRETE COMP. STRENGTH, SLUMP TESTS AND PLACEMENT POST INSTALLED ANCHOR ROD VERIFICATION
N/A	BASE PLATE GROUT VERIFICATION
N/A	CERTIFIED WELD INSPECTION
N/A	DAMPENOR, LIFT AND DESIGN
N/A	ON SITE COLD GALVANIZING VERIFICATION
N/A	COR WIRE TENSION REPORT
ADDITIONAL TESTING AND INSPECTIONS:	
AFTER CONSTRUCTION	
CONSTRUCTION/INSTALLATION INSPECTIONS AND TESTING REQUIRED (NUMBER OF RECORD)	REPORT ITEM
REQUIRED	UPGRADATION INSPECTION REPORT OR RECORD DRAWINGS
REQUIRED	POST INSTALLED ANCHOR ROD PULL-OUT TESTING
ADDITIONAL TESTING AND INSPECTIONS:	PHOTOGRAPHS

SCALE: REFER TO STRUCTURAL ANALYSIS REPORT & RECOMMENDATIONS BY HUDSON DESIGN GROUP LLC, ALL DATED 02/20/2018. THE ANALYSIS OF THE EXISTING STRUCTURES TO SUPPORT THE PROPOSED CONSTRUCTION TO COMPLEMENT CONSTRUCTION.

NOTE: ALL VISIBLE PROPOSED JOINTS SHALL BE REINFORCED WITH EMBEDMENT SURROUNDINGS.

NOTE: REFER TO THE FINAL RF DATA SHEET FOR FINAL ANTENNA SETTINGS.

- NOTES:**
1. SHOP DRAWING ENGINEER REVIEW & APPROVAL REQUIRED BEFORE ORDERING/FABRICATING MATERIAL
 2. ALL FLASHING SHALL BE COMPLETED BY A ROOFING SUBCONTRACTOR APPROVED BY THE BUILDING OWNER & ROOFING CONTRACTOR. THIS SHALL NOT VOID THE ROOF WARRANTY
 3. ALL FLASHING SHALL BE DONE IN A WAY SO AS NOT TO IMPAIR THE INTEGRITY OF THE ROOF DRAINS

Hudson Design Group

1600 GORDON STREET
N. ANDOVER, MA 01862
TEL: (978) 525-5555

EMPIRE telecom

16 ESQUIRE ROAD
BILLERICA, MA 01862
TEL: (978) 608-8400

at&t

550 COCHITUAH ROAD
FRAMINGHAM, MA 01701

DATE	ISSUED FOR CONSTRUCTION	BY	DATE	ISSUED FOR REVISION	REVISIONS	DESIGNED BY	APPROVED BY
10/20/18	ISSUED FOR CONSTRUCTION	VP	10/20/18	ISSUED FOR REVISION	REVISIONS	DESIGNED BY	APPROVED BY



AT&T

STRUCTURAL MODIFICATION DESIGN	(LITE AC 2018)
DATE SUBMITTED	DRAWING NUMBER
DATE	SCALE
REV	1