

### **DRAWING INDEX**

## ARCHITECTURAL DRAWINGS

G000	COVER SHEET - PROJECT INFORMATION
G100	CODE COMPLIANCE PLAN

I	A100	DEMOLITION, NOTED, EQUIPMENT AND FINISHES FLOOR PLANS
	A101	INTERIOR ELEVATIONS AND MILLWORK DETAILS
	A102	MILLWORK DETAILS
	Λ103	MILLWORK DETAILS AND ELEVATIONS

## **GENERAL NOTES**

- 1- ALL WORK MUST MEET THE STANDARDS OF THE STATE OF MAINE BUILDING CODES, THE REQUIREMENTS OF PORTLAND AND THE UNIVERSITY OF SOUTHERN MAINE.
- 2- DO NOT SCALE DRAWINGS. DRAWINGS ARE FOR GENERAL PURPOSES ONLY. NO MEASUREMENTS SHALL BE SCALED OFF DRAWINGS. ALL MEASUREMENTS SHALL BE VERIFIED IN FIELD.
- 3- CONNOR ARCHITECTURE ACCEPTS NO RESPONSIBILITY FOR UNAUTHORIZED REPRODUCTION OR UNAUTHORIZED USE OF THIS DOCUMENT.
- 4- DUE TO THE NATURE OF THE WORK THE CONTRACTOR SHALL VERIFY EXISTING DIMENSIONS AND REPORT TO THE ARCHITECT ANY DIMENSIONAL CHANGES. FAILURE TO COMPLY WILL NOT ALLOW FOR ANY CHANGES BY THE CONTRACTOR.
- 5- INFORMATION REGARDING THE PROJECT CONDITIONS HAVE BEEN TAKEN FROM FIELD OBSERVATIONS. THE CONTRACTOR SHALL VERIFY EXISTING CONDITIONS BEFORE COMPLETION OF BID STAGE, INCLUDING ABOVE CEILING, BELOW SLAB, WALL COMPOSITION AND UTILITIES, AND SHALL NOTIFY THE ARCHITECT OF ANY DISCREPANCIES BETWEEN PLANS, SPECS, AND EXISTING CONDITIONS.
- 6- ALL MATERIALS AND WORKMANSHIP SHALL BE GUARANTEED FOR A PERIOD OF ONE YEAR FROM THE DATE OF FINAL ACCEPTANCE UNLESS SPECIFIED OTHERWISE FOR A LONGER PERIOD OF TIME ON A CERTAIN ITEM.
- 7- EQUIPMENT SUPPLIED BY OWNER AND INSTALLED BY THE CONTRACTOR. EQUIPMENT INFORMATION AND SPECIFICATIONS ARE THE MOST CURRENT AVAILABLE AT THE TIME OF PREPARATION OF THE DRAWINGS. CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING WITH OWNER THE EXACT DIMENSIONS AND EQUIPMENT CONNECTION REQUIREMENTS (INCLUDING ELECTRICAL CIRCUIT REQUIREMENTS) OF EQUIPMENT TO BE SUPPLIED. CONTRACTOR TO MAKE ALL FINAL CONNECTIONS AS NOTED ON THE DRAWINGS, INSTALL SET UP IN WORKING ORDER, CHECK WARRANTIES, TEST, AND NOT VOID WARRANTIES. CONTRACTOR SHALL COORDINATE WITH OWNER DELIVERY, STORAGE AND INSTALLATION OF ALL OWNER SUPPLIED EQUIPMENT. CONTRACTOR TO STORE EQUIPMENT IF REQUESTED UNTIL INSTALLATION.
- 8- SEE SPECIFICATIONS AND DRAWINGS FOR OTHER OWNER SUPPLIED/ CONTRACTOR INSTALLED ITEMS.
- 9- ALL MATERIALS USED FOR THE CONSTRUCTION OF THIS PROJECT, WHETHER BUILDING MATERIALS OR APPURTENANCES, SHALL BE NON-ASBESTOS CONTAINING MATERIALS.
- 10- ALL INTERIOR FINISHES TO COMPLY WITH FIRE RESISTANCE RATINGS REQUIRED BY INTERNATIONAL BUILDING CODE.
- 11- ALL SHOP DRAWINGS (MILLWORK, STEEL, SIGNAGE, ETC.) TO BE SUBMITTED TO ARCHITECT FOR APPROVAL. ALL SAMPLES (FLOORING, PAINT, STAINLESS STEEL, WALLCOVERING, LAMINATE, & SOLID SURFACE) SHALL BE SUBMITTED TO
- 12- GENERAL CONTRACTOR SHALL OBTAIN AND PAY FOR ANY BUILDING PERMITS REQUIRED AND CARRY INSURANCE COVERAGE REQUIRED.
- 13- CONTRACTOR MUST COORDINATE WITH OWNER ON ALL ACTIVITIES. INCLUDING UTILITIES SHUT DOWN OR MODIFIED. WORK MUST NOT INTERFERE WITH EXISTING SMOKE DETECTORS, AND ALARMS.
- 14- THE UNIVERSITY OF SOUTHERN MAINE AND THE GENERAL CONTRACTOR SHALL OBTAIN ANY BUILDING PERMIT REQUIRED. THE UNIVERSITY OF SOUTHERN MAINE IS TO PAY FEES ASSOCIATED WITH ALL REVIEWS AND PERMITS.



**SOUTHERN MAINE** 



# GARBECHT LAW CAFE RENOVATION

ARCHITECTURAL ABBREVIATIONS							
<u>A</u> &		_ /~\L J Jan	JANITOR				
@ ACT ALT ALUM AVG	AT ACOUSTICAL CEILING TILE ALTERNATE ALUMINUM AVERAGE ABOVE FINISH FLOOR	<u>L</u> LAV LB/# LGMF	LAVATORY POUND				
BD BLDG BOD BSMT	BOARD BUILDING BOTTOM OF DECK BASEMENT	MEP MEP MFR MAT MAX MEZZ MIN	MECHANICAL, ELECTRICAL, AND PLUMBIN MANUFACTURER MATERIAL MAXIMUM MEZZANINE MINIMUM				
<u>C</u> CBU CG	CEMENTITOUS BACKER UNIT CORNER GUARDS	MO MTL	MASONRY OPENING METAL				
CMU	CLEAR CONCRETE MASONRY UNIT	<u>N</u> NA NIC NR NTS	NOT APPLICABLE NOT IN CONTRACT NOT RATED NOT TO SCALE				
CONF CONT	CONCRETE CONFERENCE CONTINUOUS CORRIDOR CARPET	<u>o</u> OC OD OPNG OSB	ON CENTER OUTSIDE DIAMETER OPENING ORIENTER STRAND BOARD				
CT  D  DEMO  DF  DIA	DEMOLITION DRINKING FOUNTAIN DIAMETER	P +/- PSF PSI PT PLAM	PLUS OR MINUS POUNDS PER SQUARE FOOT POUNDS PER SQUARE INCH PRESSURE TREATED PLASTIC LAMINATE				
DIM DN DO DWG	DIMENSION DOWN DOOR OPENING DRAWING	<u>Q</u> QTY	QUANTITY				
<u>e</u> Ea EJ Elec Elev	EACH EXPANSION JOINT ELECTRIC ELEVATION/ ELEVATOR RUBBER ROOF MEMBRANE EQUAL EXISTING EXTERIOR	R R RD REF REQ REV RO RTU	RISER ROOF DRAIN REFRIGERATOR REQUIRED REVISION ROUGH OPENING ROOF TOP UNIT				
E FD FDN FEC FFE	FLOOR DRAIN FOUNDATION FIRE EXTINGUISHER CABINET FINISH FLOOR ELEVATION	SHTG SIM SF SS STL STD	SHEATHING SIMILAR SQUARE FOOT/ FEET STAINLESS STEEL STEEL STANDARD				
FRP FT FTG	FIBER REINFORCED POLYESTER FOOT/FEET FOOTING	<u>I</u> T T&G	TREAD TONGUE & GROOVE				

TEL TELEPHONE

TEMP TEMPERATURE

TOS TOP OF STEEL

VIF VERIFY IN FIELD

VCT VINYL COMPOSITION TILE

TV TELEVISION

TYP TYPICAL

W/O WITHOUT

WD WOOD

GAGE

GALV GALVANIZED

GEN GENERAL GLASS

GENERAL CONTRACTOR

GWB GYPSUM WALL BOARD

HANDICAPPED


**HOLLOW METAL** 

HVAC HEATING, VENTILATING & AC

HEIGHT

HOUR

## SYMBOLS LEGEND



ELEVATION FROM NOTED BENCHMARK



CONNOR ARCHITECTURE ACCEPTS NO RESPONSIBILITY FOR UNAUTHORIZED REPRODUCTION OR UNAUTHORIZED USE OF THIS

Drawings are for general purposes only. No MEASUREMENTS SHALL BE SCALED OFF DRAWINGS. ALL MEASUREMENTS SHALL BE VERIFIED IN FIELD.



Lexington, MA 02420 Tel: 781-652-0114

**REVISIONS** 

**ISSUED**: JANUARY 19, 2017

SHE

**DESCRIPTION:** 100% CONSTRUCTION **DOCUMENTS**