



**E8** DEMOLITION GENERAL NOTES

**95% REVIEW**  
25 FEB 2005

1. REFER TO FLOOR PLANS FOR SCOPE OF WORK AREA. REFER TO ARCHITECTURAL AND HVAC DRAWINGS FOR THE ADDITIONAL DEMOLITION SCOPE OF WORK. DEMOLITION SCOPE OF WORK SHALL INCLUDE ALL ELECTRICAL DEVICES IN WALLS SCHEDULED TO BE DEMOLISHED.
2. THE CONTRACTOR SHALL COMPLETELY DEMOLISH ALL ELECTRICAL DEVICES WITHIN DEMOLITION AREA SCOPE OF WORK, UNLESS NOTED OTHERWISE. DEMOLITION SHALL INCLUDE BUT NOT BE LIMITED TO WIRING DEVICES, OUTLET BOXES, PULL BOXES, LIGHTING FIXTURES AND SWITCHES, WIRING AND CONDUIT, FIRE ALARM DEVICES, ETC.
3. DEMOLITION SHALL EXCLUDE ALL DEVICES AND WIRING FOR EQUIPMENT IN SCOPE OF WORK AREA SCHEDULED TO REMAIN ON MECHANICAL DRAWINGS.
4. THE CONTRACTOR SHALL DISCONNECT, REMOVE AND MAKE SAFE ALL ELECTRICAL WIRING FOR EQUIPMENT TO BE REMOVED WITHIN THIS SPACE BACK TO THE POINT OF CONNECTION.
5. ALL SALVAGABLE ITEMS SHALL BE TURNED OVER TO THE OWNER.
6. CONTRACTOR SHALL VERIFY ALL EXISTING SOURCES OF POWER TO EQUIPMENT PRIOR TO FINAL REMOVAL.
7. THE CONTRACTOR SHALL COORDINATE ALL SHUTDOWN PROCEDURES WITH THE OWNER PRIOR TO DISCONNECTING ANY CIRCUITS.
8. PROVIDE BLANK COVER PLATES FOR REMOVED POWER AND COMMUNICATIONS OUTLETS IN EXISTING WALLS SCHEDULED TO REMAIN.