



- F8 DEMOLITION GENERAL NOTES**
1. ALL EXPOSED DOMESTIC HOT AND COLD WATER, WASTE, AND VENT PIPING SHALL BE REMOVED, WHERE NOT SELECTED FOR RE-USE.
 2. WHERE CONCEALED, PIPING SHALL BE REMOVED TO THE EXTENT NECESSARY TO ACCOMMODATE THE RENOVATIONS, WHERE PIPING REMAINS ABANDONED AND CONCEALED, CAP BELOW FLOOR OR WITHIN WALL CAVITY, CHASE, ETC. COORDINATE WITH OTHER TRADES FOR PATCHING EXISTING FINISH TO MATCH EXISTING. COORDINATE WITH DIVISION 13 FOR ASBESTOS ABAEMENT AND PARTIAL PIPE DEMOLITION REQUIREMENTS.
 3. REMOVAL OF PIPING SHALL INCLUDE REMOVAL OF ALL ASSOCIATED FITTINGS, HANGERS, NON-ASBESTOS INSULATION, ETC.
 4. UNDERFLOOR WASTE AND PIPING CONCEALED IN WALLS WHERE NOT SCHEDULED FOR REUSEMAY BE ABANDONED IN PLACE PROVIDED IT DOES NOT INTERFERE WITH RENOVATIONS OUTLINED HEREIN.

- E8 DEMOLITION KEY NOTES**
1. PLUMBING FIXTURE TO BE REMOVED COMPLETE, WITH HOT/COLD WATER FEED, WASTE AND VENT PIPING.
 2. WASTE AND VENT RISER TO BE REMOVED COMPLETE. CAP PIPING BELOW FLOOR CAP PIPING AND ABANDON IN PLACE