

LINTEL SCHEDULE

| MASONRY OPENING | LINTEL SIZE |
|-----------------|-----------------------------|
| UP TO 3'-0" | L3 1/2x3 1/2x5/16 |
| 3'-1" - 4'-6" | L4x3 1/2x5/16 (4" LEG VERT) |
| 4'-7" - 6'-0" | L5x3 1/2x5/16 (5" LEG VERT) |
| 6'-1" - 8'-0" | L6x3 1/2x5/16 (6" LEG VERT) |
| 8'-1" - 12'-0" | L6x3 1/2x3/8 (6" LEG VERT) |
| 12'-1" - 15'-9" | L8x4x7/16 (8" LEG VERT) |

NOTES:

1. PROVIDE ONE ANGLE FOR EACH 4" OF WALL THICKNESS. FOR 6" WALLS, PROVIDE WT OR BUILT-UP SECTION WITH PROPERTIES EQUAL TO OR GREATER THAN 1 1/2 TIMES THE ANGLE PROPERTIES FOR A 4" WALL THICKNESS.
2. PROVIDE A MINIMUM 8" OF BEARING @ EACH END OF ALL LINTELS.
3. ALL EXTERIOR LINTELS SHALL BE HOT-DIPPED GALVANIZED.

SKS-03

LINTEL SCHEDULE

IRIS NETWORK
PORTLAND, MAINE

Scale: NONE

Project No: 03066

Date: MARCH 28, 2005

CAD File: JGM-03066S.DWG

allied
engineering, inc.

One Westbrook Common, Westbrook, Maine 04092-2804
Telephone No: 207-854-8126 • Fax No: 207-854-0603
E-Mail: info@allied-eng.com • www.allied-eng.com

