

**SECTION 11452 – RESIDENTIAL APPLIANCES****PART 1 GENERAL****A. RELATED DOCUMENTS**

1. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

**B. SUMMARY**

1. This Section includes installation only of the following types of Owner Purchased residential and commercial appliances:
  - a. Ranges.
  - b. Recirculating Range hoods.
  - c. Refrigerator: minimum 12.5 cubic feet.
  - d. Dishwashers.
  - e. Clothes Washers in laundry room.
  - f. Clothes Dryers in laundry room.
  - g. All kitchen c110 equipment.
2. All appliances to be installed in barrier-free units will meet ADA requirements.
3. Furnish and install all required ductwork to vent and dryers.

**PART 2 PRODUCTS (not applicable)****PART 3 EXECUTION****A. INSTALLATION**

1. General: Comply with manufacturer's instructions and recommendations.
2. Built-In Equipment: Securely anchor units to supporting cabinets or countertops with concealed fasteners. Verify that clearances are adequate for proper functioning and rough openings are completely concealed.
  - a. All ranges supplied by the Owner are equipped with a forward tip-over preventer-bracket as required by Code. Installation of this bracket on back wall and connection of ranges thereto will be a required part of the Work of this installation.
3. Freestanding Equipment: Place units in final locations after finishes have been completed in each area. Verify that clearances are adequate to properly operate equipment.
4. Utilities: Refer to Divisions 15 and 16 for plumbing, mechanical and electrical requirements.

**B. ADJUST AND CLEAN**

1. Testing: Test each item of residential equipment to verify proper operation. Make necessary adjustments.
2. Accessories: Verify that accessory items required have been furnished and installed.
3. Cleaning: Remove packing material from residential equipment items and leave units in clean condition, ready for operation.

**END OF SECTION 11452**