

Lighting Fixture Schedule

Г

-	-				
	Mfr	Model No.	Mounting	Lamping	Remarks
Α	Hill-Rom	P696-IL	Surface	(2) F032T8/841	Up/Down Headwall Unit Furnished by transport from South Portland to MM
			(69" AFF)		Remove exist light. Provide blank co extend wiring to new fixture. Mounting
					Switch uplight from wall switch. Dov fixture pull chain
В	Alkco	ST8140-1G	Recessed	(3) F032T8/841	Ceiling 1x4 Exam Light
С	Alkco	No. 103	Recessed	(1) CF4W/841	Night Light
D	Columbia	4PS22-240TTG-FSA19-EBTT120	Recessed	(2) CF40TT/841 4-Pin	2x2 Prismatic Troffer
E	Prescolite	CFT632HEB-STF602H	Recessed	(1) CF26W/841 4-Pin	Downlight
F	Columbia	P422-240TTG-44-S-EBTT120	Recessed	(2) CF40TT/841 4-Pin	16 Cell Parabolic Troffer
G1	Columbia	Alera Lighted Corner	Recessed		
G2	Columbia	Alera L662-217G-FALD-EB8120	Recessed	(2) F017T8/841	6" x 24" Linear Parabolic Fluorescen
G4	Columbia	Alera L664-232G-FALD-EB8120	Recessed	(2) F032T8/841	6" x 48" Linear Parabolic Fluorescen
н	Lightolier	QVS2GPFOS2U4120SB	Recessed	(2) T5BT	Provide By Alternate #4/Wire to exs circuits/Verify continuity

Note:

A Fixtures not installed during normal phasing due to delivery lead time shall be installed in sub-phases of one patient room each. shed by Owner. E.C. shall to MMC and install.

blank cover plate and Mounting board by G.C. ch. Downlight switched by

rescent

e to exsiting lighting

Richards Wing

Fifth Floor

Renovations

Maine Medical Center Portland, Maine 04102

Architect

Winton Scott Architects Portland, Maine

Mechanical Engineering Mechanical Systems Engineers Yarmouth, Maine

Electrical Engineering

Bartlett Design Bath, Maine

Electrical Floor Plan



Scale: 1/8" = 1' - 0" April 10, 2002