



DEMOLITION NOTES:

- ① EXISTING LIGHT FIXTURE AND SWITCH TO BE REMOVED.
- ② EXISTING PROXIMITY CARD READER, MOTION DETECTOR AND DOOR STRIKE HARDWARE TO BE REMOVED, STORED AND RE-INSTALLED UNDER NEW WORK, OR TURNED OVER TO HOSPITAL.
- ③ EXISTING RECEPTACLE OR POWER OUTLET TO BE REMOVED.
- ④ EXISTING NURSE CALL, SPEAKER, TELEVISION, TELEPHONE, DATA DEVICE TO BE REMOVED.
- ⑤ EXISTING FIRE ALARM DEVICE OR EXIT SIGN TO BE REMOVED, STORED AND RE-INSTALLED UNDER NEW WORK.
- ⑥ EXISTING FIRE ALARM DEVICE, EXIT SIGN, CLOCK, SPEAKER, TELEPHONE, RECEPTACLE, LIGHT FIXTURE, SWITCH OR NURSE CALL DEVICE TO REMAIN.
- ⑦ EXISTING PANEL REMAINS.
- ⑧ REMOVE EXISTING LOAD CENTER. REMOVE FEEDER BACK TO PANEL "LP42". EXISTING 60A BREAKER IN PANEL "LP42" REMAINS FOR USE IN NEW WORK.
- ⑨ EXISTING "DUKANE" NURSE CALL CONTROL PANEL REMAINS.
- ⑩ LIGHT FIXTURE TO BE REMOVED, STORED AND RE-INSTALLED UNDER NEW WORK.
- ⑪ EXISTING SPEAKER TO BE REMOVED, STORED AND RE-INSTALLED UNDER NEW WORK.

L:\25468\Cadd\25468E001.dwg May 24, 2004 - 2:01 pm