



DOOR SCHEDULE					
NO.	SIZE	REMARKS	NO.	SIZE	REMARKS
A	4'-0" X 7'-0"		P	5'-0" X 7'-0"	PAIR
B	3'-0" X 7'-0"		Q	6'-0" X 7'-0"	PAIR
C	3'-0" X 7'-0"		R	7'-0" X 7'-0"	PAIR
D	3'-0" X 7'-0"		S	4'-0" X 7'-0"	PAIR - OPPOSITE SWING
E	3'-0" X 7'-0"		T	4'-0" X 7'-0"	PAIR
F	3'-0" X 7'-0"		U	6'-0" X 7'-0"	PAIR
G	3'-0" X 7'-0"		V	3'-0" X 7'-0"	PAIR
H	2'-10" X 7'-0"		W	4'-0" X 7'-0"	2 PANEL
J	2'-8" X 7'-0"		X	4'-0" X 7'-0"	2 PANEL
K	2'-8" X 7'-0"		Y	4'-0" X 7'-0"	3 PANEL
L	2'-2" X 7'-0"		Z	4'-0" X 7'-0"	4 PANEL
M	4'-8" X 7'-0"	PAIR			
N	3'-0" X 7'-0"	PAIR - UNEQUAL LEAF	FM		FIELD MEASURE

SCHEDULE OF MATERIAL DESIGNATIONS		EXAMPLE OF DOOR TAG ANNOTATION	
LETTER SIZE + 2	WOOD	DOOR SIZE	DOOR MATERIAL
LETTER SIZE + 3	HOLLOW METAL		
LETTER SIZE + 4	ALUM. FRAMED GLASS		
LETTER SIZE + 5	WOOD FOLDING		
LETTER SIZE + 6	FABRIC FOLDING		
LETTER SIZE + 7	AUTOMATIC SLIDING BREAK-OUT DOOR		
	MANUAL SLIDING BREAK-OUT DOOR		

DOOR TYPE SCHEDULE			
FLUSH PANEL	HALF GLAZED	NARROWLINE GLAZED	NARROWVIEW GLAZED
FULL GLAZED			FULL GLAZED

NOTE: GLASS DIMENSIONS ARE CLEAR OF STOPS.

SUBSCRIPT ABBREVIATIONS		GENERAL NOTES	
B	- INKURED KNOB OR PUSHBAR	1)	ALL DOORS TO BE AS FOLLOWS:
C.I.F.	- CHANNEL IRON FRAME	2)	INTERIOR WOOD DOORS TO BE 1 3/4" UNLESS OTHERWISE NOTED.
C.O.	- CASED OPENING	3)	EXTERIOR/INTERIOR HOLLOW METAL DOORS TO BE 1 3/4" THICKNESS.
D.A.	- DOUBLE ACTING	4)	DOORS TO STAIRWAYS TO BE CLASS 'B' LABEL (1 1/2" HOUR FIRE RATING)
E.H.	- ELECTRIC HOLD BACKS	5)	ACCESS DOORS IN SHAFTS TO BE CLASS 'B' LABEL (1 1/2" HOUR FIRE RATING)
F	- FOLDING DOOR	6)	CLASS 'A' LABEL DOORS TO BE 3 HOUR FIRE RATING.
FG	- FULL GLAZED	7)	CLASS 'C' LABEL DOORS TO BE 1/4 HOUR FIRE RATING.
G	- GROUND GASKET	8)	ALL GLASS IN SMOKE PARTITIONS TO BE CLEAR WIRE GLASS OR TEMPERED GLASS AND SECURED WITH STEEL FRAMES AND APPROVED STOPS. TOTAL GLASS AREA FOR EACH LIGHT SHALL NOT EXCEED 1296 SQ. IN. UNLESS OTHERWISE NOTED.
H	- HOLLOW METAL	9)	TOTAL CLEAR WIRE GLASS AREA IN 'B' LABEL DOORS SHALL NOT EXCEED 100 SQ. IN. PER LEAF.
I	- INSULATED	10)	PROVIDE INTEGRAL OR 1/8" X 1 1/2" FLAT BAR ASTRAGAL AT ALL DOUBLE LEAF WOOD GLASS 'B' LABEL & SMOKE DOORS.
L	- LOUVER	11)	ALL DOORS INDICATED TO BE CLASS 'A', 'B' OR 'C' SHALL BEAR THE UNDERWRITER'S LABORATORY LABEL.
M.T.	- METAL THRESHOLD	12)	IN ALL CASES WHERE DOORS HAVE A CLASS LABEL THE FRAME SHALL ALSO HAVE THE SAME LABEL.
N	- ROLL UP STEEL DOOR	13)	WHERE CARPET OCCURS ADJUST DOORS FOR SIZE.
O.W.	- ONE WAY GLASS	14)	ALL DOORS IN SMOKE PARTITIONS WHERE VISION PANELS ARE INDICATED SHALL HAVE APPROVED TRANSPARENT WIRE GLASS NOT TO EXCEED 1296 SQ. IN. TOTAL AREA PER LEAF AND TO BE SECURED WITH APPROVED STOPS.
P	- PARTITION	15)	DOOR PROTECTION PLATE SET NUMBER.
P.P.	- PARTITION (MATCH EXISTING LAB DOORS)		
R	- RAISED UP (UNDERCUT 3/4")		
S	- SMOKE DOORS		
SP	- SPECIAL GLASS DOOR		
T	- TYPICAL		
W.S.	- WEATHERSTRIP		
X	- ALUMINUM DOOR WITH GLASS		
Y	- LIGHT PROOF		
Z	- FLEXIBLE DOOR (SEE SPEC)		
RP	- RAISED PANELS W/ WOOD TRIM		
SP+	- DOOR PROTECTION PLATE		
NO.	- NONE		



MARK	ISSUE DATE	DESCRIPTION
	08/24/04	PERMIT SET - NOT FOR CONSTRUCTION

TRO ARCHITECTURAL PLANNING ENGINEERING INTERIOR DESIGN
The Ritchie Organization
80 Bridge Street
Newton, MA 02459-1564
617-550-0400

Maine Medical Center
Central Utility Plant
Portland, Maine

Drawing Title: **DOOR SCHEDULE, VIEW WINDOW SCHEDULE, AND MISC DETAILS**

Commission No. 4677 Date Issued
Scale AS NOTED Sheet Number
Drawn By LR
Approved By JML
Checked By 4677MSJ/04
Copyright © 2004 The Ritchie Organization

A530