ABBREVIATIONS

A	
ACC	AIR COOLED CONDENSER
ACD	AUTOMATIC CONTROL DAMPER
ACU	AIR CONDITIONING UNIT
ADD	ACCESS DOOR
AFC	AIR FLOW CONTROL VALVE
AFF	ABOVE FINISHED FLOOR
AHU	AIR HANDLING UNIT
AIR	AIRFOIL
AMB	AMBIENT
AMP	AMPERE
ANSI	AMERICAN NATIONAL STANDARDS INSTITUTE
APPROX	APPROXIMATE
AS	AIR SEPERATOR
ATC	AUTOMATIC TEMPERATURE CONTROL
AVG	AVERAGE
ASHE	AMERICAN SOCIETY OF MECHANICAL ENGINEERS
B	
BAS	BUILDING AUTOMATION SYSTEM
BHP	BRAKE HORSEPOWER
BTU	BRITISH THERMAL UNIT
BTUH	BRITISH THERMAL UNITS/HOUR
C	
CA	COMBUSTION AIR
CAP	CAPACITY
CFM	CUBIC FEET PER MINUTE
CHR	CHILLED WATER RETURN
CHS	CHILLED WATER SUPPLY
COMP	COMPRESSOR
COND	CONDENSATE
CP	CONDENSATE PUMP
CT	COOLING TOWER
CTR	CENTER
CU FT	CUBIC FEET
CUH	CABINET UNIT HEATER
CV	CONSTANT VOLUME
CV	COEFFICIENT, VALVE FLOW
CONN	CONNECTION
CO	CLEANOUT
CO	CLEANOUT
CW	COLD WATER (DOMESTIC)
CV	CONSTANT VOLUME
D	
D	DRAIN
DB	DRY BULB
DEG	DEGREE
DDC	DIRECT DIGITAL CONTROL
DIA	DIAMETER
DISCH	DISCHARGE
DN	DOWN
DIL	DYNAMIC INSERTION LOSS
DPT	DEWPOINT TEMPERATURE
DP	DAMPER
DP/DPX	DIFFERENTIAL PRESSURE
DWG	DRAWING
E	
E	EXHAUST AIR DEVICE
EA	EACH OR EXHAUST AIR
EAT	ENTERING AIR TEMPERATURE
EC	ELECTRICAL CONTRACTOR
EF	EXHAUST FAN
EFF	EFFICIENCY
EFT	EXHAUST FAN
ENT	ENTERING
EDP	EXTERNAL STATIC PRESSURE
EL	ELEVATION
ELL	EXPANSION ELBOWS
EUH	ELECTRIC UNIT HEATER
EWT	ENTERING WATER TEMPERATURE
EXP	EXPANSION
EDB	ENTERING DRY BULB TEMPERATURE
EDB	ENTERING DRY BULB TEMPERATURE
EXIST	EXISTING
EXH	EXHAUST
EXT	EXTERIOR
F	
F	FILTER
FD	FIRE DAMPER
FLA	FULL LOAD AMPS
FPM	FEET PER MINUTE
FPS	FEET PER SECOND
FT	FEET, FOOT
F&T	FLOAT & THERMOSTATIC TRAP
FTR	FIN TUBE RADIATION
FT	FINAL FILTER
FTR	FIN TUBE
FT	FLUSH Tank
°F	DEGREE FAHRENHEIT
G	
GA	GAUGE
GAL	GALLON
GC	GENERAL CONTRACTOR
GPH	GALLON PER HOUR
GPM	GALLON PER MINUTE
H	
HD	HEAD
HGT	HEIGHT
HP	HORSEPOWER
HP	HEAT PUMP
HPS	HIGH PRESSURE STEAM RETURN
HPR	HIGH PRESSURE STEAM RETURN
HR	HOUR
HUH	HORIZONTAL UNIT HEATER
HWR	HOT WATER RETURN
HWS	HOT WATER SUPPLY
HX	HEAT EXCHANGER
HZ	FREQUENCY
HVAC	HEATING, VENTILATING AND AIR CONDITIONING
I	
ID	INSIDE DIAMETER
IN	INCH
IN. W.G.	INCHES – WATER GAUGE
IPS	INTERNATIONAL PIPE STANDARD
K	
KW	KILOWATT
KWH	KILOWATT PER HOUR
L	
LAT	LEAVING AIR TEMPERATURE
LBS/HR	POUNDS PER HOUR
LBS	POUNDS
LF	LIGHT FIXTURE
LVT	LEAVING TIMER
LHG	LATENT HEAT GAIN
LPS	LOW PRESSURE STEAM RETURN
LPR	LOW PRESSURE STEAM SUPPLY
LVG	LEAVING
LWT	LEAVING WATER TEMPERATURE
LPSH	LOW PRESSURE STEAM SUPPLY TO HUMIDIFIERS
LDB	LEAVING DRY BULB TEMPERATURE
LWB	LEAVING WET BULB TEMPERATURE
LRA	LOCKED ROTOR AMPS
M	
MBH	MAXIMUM
MBH	BTU PER HOUR (THOUSAND)
MFGR	MANUFACTURER
MPH	MPHEIGHT
MPR	MEDIUM PRESSURE STEAM RETURN
MPS	MEDIUM PRESSURE STEAM SUPPLY
MHP	MOTOR HORSEPOWER
N	
NC	NOISE CRITERIA
NC	NORMALLY CLOSED
NC	NORMALLY CONTRACT
NO	NUMBER
NO	NORMALLY OPEN
NTS	NOT TO SCALE
NFPA	NATIONAL FIRE PROTECTION ASSOCIATION
O	
OA	OUTSIDE AIR
OD	OUTSIDE DIAMETER
OH	ON SENSER
OPER	OPERATING
P	
P	PUMP
PC	PLUMBING CONTRACTOR
PD	PRESSURE DROP
PF	PROPELLER FAN
PH	PHASE
PPM	PARTS PER MILLION
PRESS	PRESSURE
PRV	PRESSURE REDUCING VALVE
PSI	POUNDS PER SQUARE INCH
PSIG	POUNDS PER SQUARE INCH
PSIA	PSI ABSOLUTE
PSIG	PSI GAUGE
PV	PRE-FILTER
Q	
QTY	QUANTITY
R	
R	RETURN AIR DEVICE
RA	RETURN AIR
RCUHC	RECIRCULATE
RH	REHEAT
RH	RELATIVE HUMIDITY
RH	RIGHT HAND
RP	RADIANT PANEL
RPM	REVOLUTIONS PER MINUTE
RTU	ROOF TOP UNIT
RL	REFRIGERANT LIQUID
RD	REFRIGERANT DISCHARGE
RG	RETURN AIR GRILLE
RECT	RECTANGULAR
RLA	RUNNING LOAD AMPS
REFRIG	REFRIGERANT
RM	ROOM
S	
S	SUPPLY AIR DEVICE
SA	SUPPLY AIR
SCFM	CFM STANDARD CONDITIONS
SD	SMOKE DAMPER
SEC	SECOND
SENS	SENSIBLE
SH	STEAM HUMIDIFIER
SHG	SENSIBLE HEAT GAIN
SHG	SENSIBLE HEAT GAIN
SP	STATIC PRESSURE (INCHES OF WATER)
SPEC	SPECIFICATION
SQ FT	SQUARE FOOT
STD	STANDARD
STM	STEAM
STR	STRAINER
SS	STAINLESS STEEL
SAT	SATURATED
SA	SOUND ATTENUATOR
SMACNA	SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION
T	
T	TRANSFER AIR DEVICE
TB	TERMINAL BOX
TD	TEMPERATURE DIFFERENCE
TEMP	TEMPERATURE
TOP	TOP
TSTAT	THERMOSTAT
TYP	TYPICAL
U	
U	HEAT TRANSFER COEFFICIENT
UH	UNIT HEATER
USG	UNFIRED STEAM GENERATOR
V	
V	VOLTS
VAC	VACUUM
VC	VOLUME DAMPER
VD	VOLUME
VCD	VOLUME
VAMBT	VARIABLE TEMPERATURE HOT WATER SUPPLY
VAMBR	VARIABLE TEMPERATURE HOT WATER RETURN
VV	VARIABLE VOLUME
VEL	VELOCITY
W	
W	WATT
W	WIDTH
W/	WITH
WB	WET BULB
WC	WATER COLUMN
WR	WATER RETURN
WS	WATER SUPPLY
WD	WEDGE
WTR	WATER

DRAWING LIST

M001	MECHANICAL – LEGEND AND GENERAL NOTES
M401	MECHANICAL – CENTRAL UTILITY PLANT PLAN LEVEL 1
M401.M	MECHANICAL – CENTRAL UTILITY PLANT PLAN LEVEL 1 MEZZANINE
M402	MECHANICAL – CENTRAL UTILITY PLAN PLAN LEVEL 2
M403	MECHANICAL – CENTRAL UTILITY PLANT ROOF PLAN
M404	MECHANICAL – BEAN BUILDING SUB-BASEMENT PIPING PLAN
M405	MECHANICAL – EXISTING BOILER ROOM PIPING PLAN
M406	MECHANICAL – PUMPHOUSE FLOOR PLANS
M407	MECHANICAL – PART PLANS AND SECTIONS
M500	MECHANICAL – CENTRAL UTILITY PLANT CHILLED WATER SYSTEM SCHEMATIC
M501	MECHANICAL – CENTRAL UTILITY PLANT CHILLED WATER CONTROLS AND POINTS LIST
M502	MECHANICAL – CENTRAL UTILITY PLANT STEAM SYSTEM SCHEMATIC
M503	MECHANICAL – CENTRAL UTILITY PLANT STEAM SYSTEM CONTROLS AND POINTS LIST
M504	MECHANICAL – CENTRAL UTIL. PLANT EMER. GENERATOR CONTROLS AND POINTS LIST
M505	MECHANICAL – CENTRAL UTILITY PLANT AHU UNITS CONTROL SEQUENCE AND POINTS LIST
M506	MECHANICAL – PIPING DIAGRAM CHILLED WATER/STEAM DISTRIBUTION
M601	MECHANICAL – CENTRAL UTILITY PLANT TYPICAL DETAILS SHEET NO.1
M602	MECHANICAL – CENTRAL UTILITY PLANT TYPICAL DETAILS SHEET NO.2
M603	MECHANICAL – CENTRAL UTILITY PLANT TYPICAL DETAILS SHEET NO.3
M700	MECHANICAL – CENTRAL UTILITY PLANT EQUIPMENT SCHEDULE SHEET NO. 1
M701	MECHANICAL – CENTRAL UTILITY PLANT EQUIPMENT SCHEDULE SHEET NO. 2
M702	MECHANICAL – CENTRAL UTILITY PLANT EQUIPMENT SCHEDULE SHEET NO. 3
MEP1	MECHANICAL ELECTRICAL AND PLUMBING COORDINATION SHEET

General Notes:

SHEET METAL LEGEND

DUCTWORK

- RECTANGULAR SUPPLY AIR DUCT TURN TOWARDS
- RECTANGULAR SUPPLY AIR DUCT TURN AWAY
- ROUND SUPPLY AIR DUCT TURN TOWARDS
- ROUND SUPPLY AIR DUCT TURN AWAY
- OVAL SUPPLY AIR DUCT TURN TOWARDS
- OVAL SUPPLY AIR DUCT TURN AWAY
- RETURN/EXHAUST AIR DUCT TURN TOWARDS
- RETUN/EXHAUST AIR DUCT TURN AWAY
- W×H — RECTANGULAR DUCT W=WIDTH H=HEIGHT
- X"ø — ROUND DUCT X"ø=DIAMETER
- DN — DUCT OFFSET DOWN
- UP — DUCT OFFSET UP
- LINED DUCTWORK
- FLEXIBLE DUCTWORK

FITTINGS

- 90 DEGREE ELBOW WITH VANES
- 90 DEGREE ELBOW WITHOUT VANES
- 90 DEGREE ROUND ELBOW
- 45 DEGREE ELBOW WITH VANES
- 45 DEGREE ELBOW WITHOUT VANES
- 45 DEGREE ROUND ELBOW
- DUCT SECTION (SUPPLY)
- DUCT SECTION (RETURN)
- DUCT SECTION (EXHAUST)

AIR TERMINALS

- SUPPLY DIFFUSER
- RETURN GRILLE
- EXHAUST GRILLE
- SIDEWALL SUPPLY GRILLE
- SIDEWALL RETURN/EXHAUST GRILLE
- LINEAR SUPPLY DIFFUSER
- LINEAR RETURN GRILLE

EQUIPMENT

- TERMINAL BOX WITH REHEAT COIL
- UNIT HEATER
- REHEAT COIL
- FILTER
- ACCESS DOOR
- INLINE FAN
- ROOF EXHAUST FAN
- ROOF VENT

SINGLE LINE

- WYE BRANCH TAKE-OFF
- RADIUS DUCT ELBOW
- WYE DOVETAIL
- DN — DUCT OFFSET DOWN
- UP — DUCT OFFSET UP
- SIDEWALL SUPPLY GRILLE
- SIDEWALL RETURN GRILLE

DAMPERS

- SSD — DUCT MOUNTED SMOKE DETECTOR
- ACD — AIR CONTROL DAMPER
- AFS — AIR FLOW STATION
- FS — FLOW SWITCH
- SPS — STATIC PRESSURE SENSOR
- S — SMOKE DAMPER
- SD/FD — COMBINATION SMOKE FIRE DAMPER
- SD — SMOKE DAMPER
- FD — FIRE DAMPER
- VD — VOLUME DAMPER

PIPING SYMBOL LEGEND

- OPEN STRAIGHT GATE VALE
- OPEN ANGLED GATE VALVE
- O.S.& Y. GATE VALVE
- NEEDLE VALVE
- OPEN BALL VALVE
- OPEN STRAIGHT GLOBE VALVE
- OPEN ANGLED GLOBE VALVE
- STOP AND CHECK NON-RETURN VALVE
- QUICK OPENING VALVE
- 2-WAY AUTOMATIC CONTROL VALVE (PNEUMATIC)
- 3-WAY AUTOMATIC CONTROL VALVE (PNEUMATIC)
- MOTOR OPERATED 2-WAY VALVE
- MOTOR OPERATED 3-WAY VALVE
- SOLENOID VALVE
- PRESSURE REDUCING VALVE
- PRESSURE REDUCING VALVE
- CHECK VALVE
- CHECK VALVE
- OPEN PLUG VALVE
- BUTTERFLY VALVE (TYPE 1)
- PRESSURE RELIEF VALVE
- PRESSURE RELIEF VALVE
- SAFETY VALVE
- COMBINATION BALANCING/FLOW MEASURING DEVICE
- BALL VALVE WITH HOSE CONNECTION, CAP AND CHAIN
- GATE VALVE WITH HOSE CONNECTION, CAP AND CHAIN
- QUICK CLOSING VALVE 1
- QUICK CLOSING VALVE 2
- FLOAT VALVE
- DIAPHRAGM VALVE
- LOCK SHIELD VALVE
- DRAIN VALVE
- SELF CONTAINED
- EXTERNAL
- DIFFERENTIAL
- BALL & SHUT CHECK VALVE
- SWING GATE CHECK VALVE
- SPRING CHECK VALVE
- ANGLED CHECK VALVE
- OPEN THREE WAY VALVE
- OPEN FOUR WAY VALVE
- GATE VALVE W/ HOSE CONNECTION
- ANGLED GATE VALVE W/ HOSE CONNECTION
- GLOBE VALVE W/ HOSE CONNECTION
- ANGLED GLOBE VALVE W/ HOSE CONNECTION
- STRAINER
- STRAINER
- THERMOSTATIC TRAP
- INVERTED BUCKET TRAP
- FLOAT AND THERMOSTATIC TRAP
- UNION
- FLANGE
- REDUCER
- CONCENTRIC REDUCER
- ECCENTRIC REDUCER
- THERMOMETER
- PRESSURE GAUGE
- FS — FLOW SWITCH

- PIPE GUIDES
- PIPE ANCHOR
- CO — CONDENSATE DRAIN LINE W/CLEANOUT
- AUTOMATIC FLOW CONTROL VALVE
- PRESSURE TEMPERATURE MEASUREMENT PORT
- MANUAL AIR VENT
- AUTOMATIC AIR VENT
- HUMIDIFIER
- PIPE TURN TOWARDS
- PIPE TURN AWAY
- CAPPED PIPE

PIPING LEGEND

- HWS — HOT WATER SUPPLY PIPING
- HWR — HOT WATER RETURN PIPING
- BFW — BOILER FEED-WATER PIPING PIPING
- CW — DOMESTIC COLD WATER (MAKE-UP)
- VHWS — VARIABLE TEMPERATURE HOT WATER SUPPLY PIPING
- VHWR — VARIABLE TEMPERATURE HOT WATER RETURN PIPING
- CHWS — CHILLED WATER SUPPLY PIPING
- CHWR — CHILLED WATER RETURN PIPING
- CWS — CONDENSER WATER SUPPLY PIPING
- CWR — CONDENSER WATER RETURN PIPING
- LPS — LOW PRESSURE STEAM SUPPLY PIPING
- LPR — LOW PRESSURE STEAM RETURN PIPING
- MPS — MEDIUM PRESSURE STEAM SUPPLY PIPING
- MPR — MEDIUM PRESSURE STEAM RETURN PIPING
- HPS — HIGH PRESSURE STEAM SUPPLY PIPING
- HPR — HIGH PRESSURE STEAM RETURN PIPING
- PC — PUMPED CONDENSATE PIPING
- D — DRAIN PIPING
- FOS — FUEL OIL SUPPLY PIPING
- FOR — FUEL OIL RETURN PIPING
- FOV — FUEL OIL VENT LINE
- FOG — FUEL OIL GAUGE LINE
- FOF — FUEL OIL FILL LINE
- V — ATMOSPHERIC VENT
- PITCH PIPE–DIRECTION OF ARROW

SYMBOLS LEGEND

- A / XXXX — DRAWING NUMBER / SHEET NUMBER — DETAIL DESIGNATION
- A / XXXX — DRAWING NUMBER / SHEET NUMBER — SECTION DESIGNATION
- CONNECT TO EXISTING
- POINT BETWEEN EXISTING TO BE REMOVED AND EXISTING TO REMAIN
- UNIT ABBREVIATION / EQUIPMENT DESIGNATION / UNIT NUMBER
- X — DEMOLITION PLAN KEYED NOTE
- X — NEW PLAN KEYED NOTE
- X / X — EQUIPMENT TYPE DESIGNATION
- XX — REVISION DESIGNATION
- FLOW DIRECTION
- EXISTING EQUIPMENT
- EXISTING EQUIPMENT TO BE REMOVED
- T — THERMOSTAT
- H — HUMIDISTAT
- S — SWITCH
- P — ROOM PRESSURIZATION MONITOR

GENERAL NOTES

1. EXACT LOCATION OF CEILING DIFFUSERS, REGISTERS AND GRILLES TO BE DETERMINED BY ARCHITECTURAL REFLECTED CEILING PLAN.
2. DIMENSIONS SHOWN FOR ALL DUCTS ARE NET INSIDE DIMENSIONS.
3. COORDINATE ALL CEILING, WALL AND FLOOR PENETRATIONS WITH OPENING ON ARCHITECTURAL AND STRUCTURAL DRAWINGS.
4. PROVIDE INSTRUMENT TEST HOLES ON DUCTWORK WHEREVER VOLUME DAMPERS ARE INDICATED.
5. ALL WORK UNDER THIS SECTION SHALL BE COORDINATED WITH ALL TRADES BEFORE ANY INSTALLATION.
6. ALL SUPPLEMENTAL STEEL CONNECTIONS TO MAIN STRUCTURE FOR SUPPORT OF HVAC EQUIPMENT SHALL BE BY THE MECHANICAL CONTRACTOR UNLESS SPECIFICALLY NOTED OTHERWISE.
7. ALL OPENINGS IN BEAMS AND ROOF SHALL BE APPROVED BY THE GENERAL CONTRACTOR AND STRUCTURAL ENGINEER.
8. EXACT LOCATION OF THERMOSTATS, CONTROL PANELS, MOTOR CONTROL CENTERS, VFD DRIVES ISTO BE COORDINATED WITH FINAL LOCATION OF ALL MECHANICAL AND ELECTRICAL EQUIPMENT.
9. MECHANICAL SUBCONTRACTOR SHALL PROVIDE FOR ALL SHEETMETAL AND PIPING TRANSITIONS TO COILS AND OTHER MECHANICAL EQUIPMENT.
10. ALL EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S APPROVED PUBLISHED LITERATURE.
11. ALL EXPOSED EQUIPMENT (CABINET HEATERS, UNIT HEATERS, etc.) SHALL HAVE COLORS SELECTED BY THE ARCHITECT, UNLESS NOTED OTHERWISE.
12. ALL THERMOSTATS INSTALLED IN AREAS EXCEPT PRIVATE OFFICES SHALL HAVE HEAVY DUTY TAMPERPROOF GUARDS.
13. EXACT ELEVATIONS FOR SIDE WALL REGISTERS AND GRILLES SHALL BE APPROVED BY THE ARCHITECT BEFORE INSTALLATION.
14. REFER TO MECHANICAL DETAIL SHEET(S) FOR TYPICAL DUCTWORK, PIPING AND EQUIPMENT DETAILS.
15. ALL LOUVERS SHALL BE FURNISHED AND INSTALLED BY THE GENERAL CONTRACTOR.
16. MECHANICAL SUBCONTRACTOR SHALL BE RESPONSIBLE FOR BLANKING OFF ALL INACTIVE PORTIONS OF LOUVERS UTILIZED FOR INTAKE OR EXHAUST FOR HVAC EQUIPMENT.
17. THE MECHANICAL CONTRACTOR AND ALL SUB–CONTRACTORS SHALL COORDINATE , COOPERATE, AND PROVIDE ALL WORK ACCORDING TO THE GENERAL CONTRACTORS OWNER APPROVED PHASING SCHEDULE AND AS REQUIRED AS PROVIDE A COMPLETE AND PROPER OPERATING SYSTEMS.
18. ALL WORK UNDER THIS SECTION SHALL BE COORDINATED WITH ALL TRADES PRIOR TO ANY FABRICATION AND INSTALLATION OF ALL WORK. THE MECHANICAL CONTRACTOR, SUB–CONTRACTORS, ALL TRADE CONTRACTORS AND GENERAL CONTRACTOR SHALL PROVIDE COORDINATION DRAWINGS PLANS AND SECTIONS TO COORDINATE ALL WORK OF ALL TRADES AS SPECIFIED IN SECTION 01150 – SPECIAL PROVISIONS. ALL TRADE CONTRACTORS AND GENERAL CONTRACTOR SHALL PRODUCE AND BE RESPONSIBLE TO CLEARLY SHOW ON PLANS AND SECTIONS HOW THE WORK IS TO BE INSTALLED IN RELATION TO ALL NEW WORK AND EXISTING CONDITIONS; FOR ALL TRADES. ANY AND ALL WORK THAT IS INSTALLED PRIOR TO THE COORDINATION WITH OTHER TRADES OR THAT CAUSES INTERFERENCES WITH ANY NEW WORK OR EXISTING CONDITIONS SHALL BE CHANGED TO CORRECT THE CONDITION AT NO COST TO THE OWNER. THE CONTRACTORS SHALL PROVIDE COORDINATION AS SOON AS POSSIBLE PRIOR TO THE SHOP DRAWING SUBMISSION PROCESS IN ORDER TO AVOID DELAYS IN THE CONSTRUCTION SCHEDULE.
19. THE MECHANICAL CONTRACTOR AND ALL SUB– CONTRACTORS SHALL VISIT THE SITE PRIOR TO SUBMISSION OF BID PRICE FOR PROJECT WORK. THE CONTRACTORS SHALL FIELD VERIFY ALL EXISTING CONDITIONS WITH ALL NEW WORK AS SHOWN, NOTED, AND REQUIRED TO PROVIDE WORK OF THE CONTRACT DOCUMENTS. IN ORDER FOR THE CONTRACTORS TO FAMILIARIZE THEMSELVES WITH ALL WORK AND CARRY ALL ASSOCIATED COSTS. NO EXTRA COMPENSATION SHALL BE ACCEPTED OR PERMITTED AFTER SUBMISSION OF THE BID PRICE.
20. THE AUTOMATIC TEMPERATURE CONTROLS CONTRACTOR (ATC) SHALL PROVIDE ALL 120 VOLTS/1 PHASE /60 HZ ELECTRICAL WIRING REQUIRED TO POWER ALL CONTROLS, MECHANICAL EQUIPMENT, DDC/EMS CONTROLLERS, DDC/EMS CONTROL PANELS, AND ALL CONTROLS ON THIS PROJECT. THE ATC CONTRACTOR SHALL CONNECT TO THE JUNCTION BOXES PROVIDED UNDER DIVISION 16 AND ACCESSORIES AS REQUIRED. REFER TO ELECTRICAL DRAWINGS FOR LOCATIONS.

MARK	ISSUE DATE	DESCRIPTION
PERMIT	09/24/04	PERMIT SET – NOT FOR CONSTRUCTION

FOR PERMIT ONLY - NOT FOR CONSTRUCTION

Issue Log



Key Plan

TRO
Architecture
Planning
Engineering
Interior Design
The Fitzhile Organization
80 Bridge Street
Newton, MA 02465-1134
617-969-9480

Maine Medical Center
Central Utility Plant
Portland, Maine

Drawing Title
MECHANICAL LEGEND AND GENERAL NOTES

0" 0 0 0 0

Commission No.	4677	Date Issued	
Scale	NTS	Sheet Number	
Drawn By	MC		
Approved By	MC		
Filename	4677-M001		

Copyright © 2004 The Fitzhile Organization

M001