PART 1 - GENERAL

.1 GENERAL

The Provisions of Section 260500, General Requirements for Electrical Work, apply to the Work of this

1.2 CODES AND STANDARDS:

A. Products shall comply with the following codes and standards and shall be UL_listed and labeled where applicable.

UL 486A Wire Connectors and Soldering Lugs for use with Copper Conductors. UL 510 Electrical Insulating Tape

PART 2 - PRODUCTS

2.1 WIRE AND CABLE

A. Wire and cable are specified in other Sections of Division 26.

2.2 TERMINATIONS AND SPLICES

A. Power Wiring:

- 1. Terminal lugs, connectors and splices shall be tin plated, high conductivity copper compression type. 1.4 MANUFACTURERS They shall have chamfered barrels and be permanently identified with conductor sizes.
- 2. Terminal lugs for conductors No. 3/0 AWG and larger shall be long barrel NEMA two hole type.
- 3. Splices shall be long barrel butt type with a center stop in the splice barrel.
- 4. Hydraulic crimping tools with proper die sizes which require full closure before reopening shall be
- B. Lighting and branch circuits
 - 1. Splices and taps in lighting and branch circuit wiring shall be 3M Scotchlok spring connectors or
- C. Metal clad cable connectors.
 - 1. For non-jacketed metal clad cable in dry locations, cable terminations shall be 0.Z. Gedney Type PK for use with galvanized steel armor or Type PK-A for use with aluminum armor. Cable terminations shall be provided with locknuts and bushings.

PART 3 - EXECUTION

3.1 PREPARATION OF RACEWAYS

A. Raceways shall be substantially completed before any wiring is installed in them. Before any wiring is pulled into a conduit, the conduit shall be cleaned and tested for obstructions and cleared of foreign material that may be found.

3.2 PULLING INTO RACEWAYS

- A. All possible care shall be taken in pulling of wiring into conduits or other raceways. The cable reels or coils shall be set up in such a way that the conductor may be trained into the raceway as directly as possible with a minimum number of changes of direction or amount of bending. Where several cables are contained in one conduit, all such cables shall be pulled in together.
- B. The use of pulling lubricants shall be restricted to non-hardening type, approved by UL and the cable manufacturer.

3.3 SPLICES AND TERMINATIONS

- A. All power and control wiring shall be continuous and shall not be spliced unless otherwise indicated on the Drawings.
- B. Bolts, nuts and hardware used for terminations shall be silicone bronze. All terminations shall be properly torqued and provided with Belleville washers.
- C. Where terminations are made on insulated buses, the terminations shall be insulated using the proper tape(s) and fillers for the voltage level of the cable.
- D. Connections in motor terminal boxes shall be made by installing compression type lugs on the motor branch circuit conductors and the motor leads and bolting the lugs together then insulating with motor lead connection kits, Raychem, 3M or equal.

3.4 IDENTIFICATION

A. All power wiring conductors shall be color coded as follows:

Phase	208Y/120V	480Y/277V
Phase A	Black	Brown
Phase B	Red	Orange
Phase C	Blue	Yellow
Neutral	White	Gray
Ground	Green	Green

END OF SECTION 260560

SECTION 262416 PANELBOARDS

PART 1 - GENERAL

1.1 GENERAL

A. The provisions of Section 260500, General Requirements for Electrical Work, apply to the Work of this

1.2 CODES AND STANDARDS

A. Products shall comply with the following codes and standards and shall be UL_listed and labeled:

Molded Case Circuit Breakers NEMA PB-1 Panelboards

UL 50 **Enclosures for Electrical Equipment** UL 67

Molded Case Circuit Breakers and Circuit Breaker Enclosures UL 489

1.3 SUBMITTALS

- A. Manufacturer's product data sheets.
- B. Circuit breaker schedules.

C. Dimensioned plans, elevations, sections and details.

A. Subject to compliance with the requirements of this Section:

Sauare D Approved equal

PART 2 - PRODUCTS

2.1 GENERAL

- A. Panelboards shall be of the sizes, rating and arrangement shown on the Drawings.
- B. Panelboards shall be provided complete with all overcurrent devices, accessories and trim.
- C. All panelboards shall be provided with safety barriers for dead front construction.
- D. The required short circuit ratings of assembled panelboards are shown on the drawings. The short circuit rating of every overcurrent device in the panel shall meet or exceed the panel rating. Unless otherwise noted on the drawings, series rated combinations will not be permitted.
- E. Provide through—feed or sub—feed lugs as indicated on panel schedules.

2.2 CABINETS

- A. Boxes shall be code gauge galvanized sheet steel.
- B. Trim shall be code gauge steel, ANSI-61 gray finish with stainless steel flush type lock/latch handle. All locks shall be keyed alike.
- C. Trim for surface mounted panels shall be door-in-door construction such that the gutter space may be exposed by a hinged door.
- D. Directory frames shall be metal frame with plastic covers.

2.3 BUS

- A. All bus work shall be copper
- B. Neutral busses shall be 100% rated with adequate connections for all outgoing neutral conductors.
- C. Panelboards shall be provided with copper ground busses. Provide isolated ground buses where indicated on the drawings.
- D. Bus shall be designed for sequence phase connection to allow the installation of one, two or three pole branch circuit breakers in any position.

2.4 OVERCURRENT DEVICES

- A. Overcurrent devices shall be trip-free molded case, bolt-on, thermal-magnetic circuit breakers.
- B. Main circuit breakers shall be individually mounted and bolted to bus assembly. Back—fed branch mounted circuit breakers are prohibited.
- C. Front faces of all circuit breakers shall be flush. Trip indication shall be clearly shown by the handle position between the ON and OFF positions.
- D. Ground fault and arc fault circuit breakers shall require no more panel space than standard breakers.
- E. All connections shall be rated for 75° C copper conductors.

PART 3 - EXECUTION

3.1 PANELBOARDS

- A. Panelboards shall be labeled in accordance with Section 260500, General Requirements for Electrical
- B. Panelboard covers are required to have 2 labels. The first, an Arc flash warning label and the second, an OSHA label requiring 3 feet, (3 feet 6 inches or 4 feet as applicable), clearance in front of the

END OF SECTION 262416

SECTION 265100

LIGHTING FIXTURES

1.1 GENERAL

PART 1 - GENERAL

Provisions of Section 260500. General Requirements for Electrical Work and Section 260560, Installation of Wire and Cable apply to the work of this section.

1.2 CODES AND STANDARDS

A. Products shall comply with the following codes and standards and shall be UL-listed and labeled:

CBM Labels Certified Ballast Manufacturers Assoc. NEC Art. 410 National Electrical Code

FCC. Part 18 RFI and EMI ANSI C62.41 Line Transient Protection UL 1570 Fluorescent Lighting Fixtures

UL 924 **Emergency Lighting and Power Equipment** UL 1088 Temporary Lighting

1.3 SUBMITTALS

- Submit manufacturer's product data, photometrics, and installation instructions for each type of light fixture specified. Fixture submittals shall be in booklet form with separate sheet for each fixture assembled in "luminaire type" alphabetical order, with proposed fixture and accessories clearly indicated
- Submit on a separate sheet for each fluorescent fixture type specified, the ballast manufacturer, type and technical data for that ballast.
- Submit on a separate sheet for each light fixture specified, the proposed lamp and manufacturers data

1.4 MANUFACTURERS

A. Provide products of the manufacturers specified on the contract drawings and as listed under Part 2 of this section.

PART 2 - PRODUCTS

2.1 GENERAL

- Light fixtures shall be provided with housings, trims, ballasts, lamp holders, sockets, reflectors, wiring and other components required, as a factory—assembled unit for a complete installation.
- Provide electrical wiring within light fixtures suitable for connecting to branch circuit wiring in accordance with N.E.C. Article 410, Paragraph 52.
- C. Deliver interior lighting fixtures in factory fabricated containers and wrapping, which properly protect fixtures from damage.
- D. Store interior lighting fixtures in original packaging. Store inside well-ventilated area protected from weather, moisture, soiling, humidity, extreme temperatures, laid flat and on skids to keep off floors and ground.
- Fixtures installed in ceilings, suspended from ceilings or on walls shall have a plastic film covering protecting lens, louver and lamps from dust, dirt and debris. Plastic film shall not be removed until construction is completed.

2.2 FLUORESCENT FIXTURES

- A. General: Provide fluorescent fixtures of sizes, types and ratings indicated and specified in the Lighting Fixture Schedule on the Contract Drawings.
- Indoor fluorescent fixtures containing double-ended T8 or T5 lamps shall be provided with an internal disconnecting means to disconnect power to the fixture.
- C. Fluorescent-Lamp Ballasts: Provide low-energy solid state fluorescent lamp ballasts, operating lamps with a frequency of >20KHz and capable of operating lamp types indicated. Ballasts shall be high power factor >0.90, Class A sound rating. Ballasts shall have lamp current crest factor of 1.7 or less and total harmonic distortion less than 20%. Ballasts shall be UL listed, Class P, and meet FCC 47CFR Part 18 Non-Consumer and meet applicable ANSI standard.
- Ballasts that operate T8 lamps shall have the following requirements:
- a. Normal ballast factor (0.88-1.03)
- b. Ballast shall be Programmed Start type
- c. Ballast must be capable of 0°F starting d. Ballast shall be one of the following:
- 1. Sylvania Quicktronic PROStart PSN series. 2. General Electric Ultramax series.
- 3. Advance Optanium IOP series.
- Ballasts that operate T4 compact fluorescent lamps shall have the following requirements: a. Ballasts shall have an end of lamp life sensing circuit capable of shutting the lamp down to prevent lamp glass from cracking and lamp base sockets from melting.
- b. Ballast factor shall be 0.95 1.1. c. Ballast shall be Programmed Start type to operate lamps in series.
- d. Ballast must be capable of 0°F starting. e. Ballast shall be one of the following:
- Sylvania Quicktronic Prostart CF series.
- General Electric ProLine CFL series. Advance SmartMate ICF series.

2.3 LAMPS

- A. Provide fluorescent lamps of types as indicated on the contract drawings.
- B. T8 Lamp Type:
- 1. All lamps shall have a minimum 85 CRI and an average rated life of 30,000 hours based on 3hrs/start when used with a programmed rapid start ballast. A 17 Watt lamp shall be minimum 1350 lumens. A 32 Watt straight lamp shall be minimum 2950 lumens.
- 2. Lamp color temperature shall be cool white, 3500K unless otherwise noted.
- a. Lamps shall be one of the followina:
- b. Sylvania Octron 800XPS series. c. General Electric Ecolux Starcoat T8 series. d. Philips 800 Alto T8 series.
- C. Compact Fluorescent (T4) Lamp Type:
- 1. All lamps shall have an average rated life of 12,000 hours, and a minimum 82 CRI. A 32 Watt lamp shall be minimum 2200 lumens. A 42 Watt lamp shall be minimum 3200 lumens
- 2. All lamps shall have 4 pin bases for operation on electronic ballasts.
- 3. Lamp color temperature shall be cool white, 3500K unless otherwise noted.
 - a. Lamps shall be one of the following: b. Sylvania DULUX T/E/IN ECO series. c. General Electric Ecolux series.
- d. Philips Alto series. PL-T/PL-C.
- D. Lamps shall be manufactured by Osram Sylvania, General Electric, Philips Lighting Co. or approved equal.

PART 3 - EXECUTION

3.1 GENERAL

- A. Examine all areas and conditions under which lighting fixtures are to be installed and structure which will support lighting fixtures. Notify the General Contractor in writing of any conditions which are detrimental to proper installation and completion of the work. Do not proceed with work until unsatisfactory conditions have been corrected in a manner acceptable to the Installer.
- B. Coordinate light fixture installations with other trades. Fluorescent light fixtures should be installed a least two feet away from smoke detectors. Coordinate all lighting fixtures with mechanical piping and ductwork to allow for proper clearance.

3.2 INSTALLATION

- A. Install all lighting fixtures at locations and heights indicated, in accordance with the architectura reflected ceiling plans.
- B. Provide fixtures and/or fixture outlet boxes with hangers, channel or other method of fastening an supporting fixtures required for proper installation.
- C. Luminaires installed in suspended ceilings shall be independently supported, directly from the buildin structure. Each luminaire shall be supported at each end.
- D. Tighten connectors and terminals, including screws and bolts in accordance with equipment manufacturer's published torque tightening values for equipment connectors. All screws and bolts shall have washers.

3.3 SPLICES AND TERMINATIONS

A. Twist on wire connectors shall be installed which utilize square—wire spring grips and thermo plastic shells. Install connectors to meet the manufacturer's torquing requirements. Install wire connectors of size required as not to exceed the manufacturers UL-listed CSA recognized wire combinations.

3.4 FIELD QUALITY CONTROL

cost to the Owner.


- A. At date of substantial completion, all lamps that are not functioning, have color deficiencies, or are noticeably dimmed shall be replaced with new lamps as determined by the Engineer.
- B. All lamps used for temporary lighting in new light fixtures shall be replaced with new lamps.
- C. All light fixtures shall be cleaned of dirt and debris upon completion of construction. All finger prints and smudges shall be cleaned.
- D. All installed fixtures during remainder of construction shall be protected in accordance with Section 2.1 Paragraph E of this specification section.

E. All light fixtures shall be grounded in accordance with article 250 and 410 of the NEC. Tighte

connections to comply with tightening torques specified in UL 486A to assure permanent and effective

F. All light fixtures damaged in shipping or during installation shall be replaced with new fixtures at no

END OF SECTION 265100



蒸草

CONSTRUC .14.11 I Radiology I-PLANE RENOVATIONS S S Bramhi ANGIO

APHIC SCALE:

PROJECT MANAGER: IC/DRAWN BY: A/E OF RECORD: PROJECT NO:

SPECIFICATIONS SHEET 2

E-003