Maine Medical Center Bean 2 Roof Addition For Construction ADDENDUM No. 3 Issued for Permit PERKINS+WILL C140135461 (MMC) /152168.00 (P+W) June 14, 2013 January 17, 2014 February 07, 2014

SECTION 23 82 33 - CONVECTORS

PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following:
  - 1. Flat-pipe steel radiators.

### 1.3 SUBMITTALS

- A. Product Data: Include rated capacities, operating characteristics, furnished specialties, and accessories for each type of product indicated.
- B. Shop Drawings: Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
  - 1. Plans, elevations, sections, and details.
  - 2. Details of custom-fabricated enclosures indicating dimensions.
  - 3. Location and size of each field connection.
  - 4. Location and arrangement of piping valves and specialties.
  - 5. Location and arrangement of integral controls.
  - 6. Enclosure joints, corner pieces, access doors, and other accessories.
- C. Coordination Drawings: Floor plans and other details, drawn to scale, on which the following items are shown and coordinated with each other, based on input from installers of the items involved:
  - 1. Structural members, including wall construction, to which convection units will be attached.
  - 2. Method of attaching convection units to building structure.
  - 3. Penetrations of fire-rated wall and floor assemblies.
- D. Color Samples for Initial Selection: For units with factory-applied color finishes.
- E. Color Samples for Verification: For each type of exposed finish required.
- F. Field quality-control test reports.

Maine Medical Center Bean 2 Roof Addition For Construction ADDENDUM No. 3 Issued for Permit PERKINS+WILL C140135461 (MMC) /152168.00 (P+W) June 14, 2013 January 17, 2014 February 07, 2014

G. Operation and Maintenance Data: For convection heating units to include in operation, and maintenance manuals.

### PART 2 - PRODUCTS

### 2.1 FLAT-PIPE STEEL RADIATORS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Runtal North America, Inc.
- B. Heating Elements: Steel, welded and formed into flat, square, steel header with minimum thickness of 0.109 inches. Include threaded piping and air vent connections.
  - 1. Working Pressure 85 psig
- C. Mounting: Wall brackets or Floor pedestals (refer to drawings) on maximum spacing of 36 inches.
- D. Finish: Baked-enamel finish in manufacturer's optional color guide as selected by Architect.

### E. Accessories:

- 1. Steel piping covers finished to match radiator finish.
- 2. Flexible Expansion Compensation Hoses: Minimum 400-psig working pressure, and operating temperatures from 33 to 211 deg F.

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine areas to receive convection heating units for compliance with requirements for installation tolerances and other conditions affecting performance.
- B. Examine roughing-in for hydronic-piping connections to verify actual locations before convection heating unit installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

# 3.2 FLAT-PIPE STEEL RADIATOR INSTALLATION

- A. Install units level and plumb.
- B. Install expansion compensation hoses.

Maine Medical Center Bean 2 Roof Addition For Construction ADDENDUM No. 3 Issued for Permit PERKINS+WILL C140135461 (MMC) /152168.00 (P+W) June 14, 2013 January 17, 2014 February 07, 2014

C. Install piping covers.

## 3.3 CONNECTIONS

- A. Piping installation requirements are specified in Division 23 Section "Hydronic Piping." Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Connect hot-water units and components to piping according to Division 23 Section "Hydronic Piping."
  - 1. Install shutoff valves on inlet and outlet, and balancing valve on outlet.
- C. Install control valves as required by Division 23 Section "Instrumentation and Control for HVAC."
- D. Install piping adjacent to convection heating units to allow service and maintenance.

# 3.4 FIELD QUALITY CONTROL

- A. Perform the following field tests and inspections and prepare test reports:
  - 1. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
  - 2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- B. Remove and replace convection heating units that do not pass tests and inspections and retest as specified above.

**END OF SECTION**