

## SECTION 12 64 16 - BANQUETTES

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. This Section includes upholstered banquettes.
- B. Basis of Design: Design of Banquette is based on design by MARGAN, LTD

#### 1.2 SUBMITTALS

- A. Shop Drawings: Show fabrication and installation details for banquettes. Include plans, elevations, sections, details of components, and anchorage type and location. Indicate dimensions taken from field measurements.
- B. Samples: Show full range of color, texture, and pattern variations expected. Prepare Samples in sizes indicated below from same material to be used in the Work.
  - 1. Banquette Unit: Full size, unit. See drawing A04-02B
  - 2. Upholstery Material: 4 yards (1830 mm) of fabric from dye lot to be used for the Work, with specified treatments applied. Show complete pattern repeat. Mark top and face of material.
  - 3. Welt Cord: Not less than 12 inches (300 mm) long, wrapped in upholstery material.
  - 4. Tuft Button: Full size and upholstered.
  - 5. Exposed Finishes: Manufacturer's standard-size unit, not less than 3 inches(80 mm) square.
  - 6. Spring System: Full-size unit.
  - 7. Attached Seat Cushion Fastener: Full-size unit.
- C. Product Schedule: Use same designation indicated on Drawings when preparing schedule for banquettes. See drawing A04-02B

#### 1.3 QUALITY ASSURANCE

- A. Mockups: Before installing banquettes, construct mockups for each form of seating and finish required to verify selections made under sample Submittals and to demonstrate aesthetic effects and execution. Install mockups to comply with the following requirements, using materials indicated for the completed Work:
  - 1. Install mockups in location and of size indicated or, if not indicated, as directed by Architect.
  - 2. Notify Architect seven days in advance of dates and times when mockups will be installed.
  - 3. Demonstrate the proposed range of aesthetic effects and workmanship.

4. Obtain Architect's approval of mockups before starting work.
5. Keep mockups undisturbed during installation as a standard for judging the completed Work.
6. Remove mockups when directed.
7. Approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

- B. Pre-installation Conference: Conduct conference at Project site to comply with requirements in Division 1 Section "Project Management and Coordination."

#### 1.4 PROJECT CONDITIONS

- A. Field Measurements: Verify existing dimensions by field measurements before fabrication and indicate measurements on Shop Drawings.

#### 1.5 COORDINATION

- A. Coordinate layout and installation of banquettes with other work supported by or penetrating through adjacent partitions.

#### 1.6 EXTRA MATERIALS

- A. Furnish extra materials described below, before installation begins, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Upholstery Material: Full-width quantity to reupholster seating units equal to 5 percent of amount installed, but not less than 6 yards banquette units.
2. Covered Welt Cord: 2 yard (914 mm) of continuous cord.
3. Tuft Buttons: Quantity equal to 5 percent of amount installed.

### PART 2 - PRODUCTS

#### 2.1 BANQUETTES

- A. Products: Subject to compliance with requirements, provide the product indicated for each designation in the Banquette Schedule at the end of Part 3.

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance.

1. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. Install banquettes level and plumb, with fasteners and shims concealed, according to manufacturer's written instructions. Tighten threaded connections so threads are concealed.

### 3.3 BANQUETTE SCHEDULE

- A. Banquette BQ- 1 : See drawing A04-02B

1. Manufacturer: Custom built.
2. Overall Seating Unit Height:
3. Overall Single-Seating Unit Depth:
4. Seat Height: Over all height to align with adjacent curtain wall sill height mullion.
5. Finish Designation: F-3
6. Seat Cushion: Attached.
7. Seat and Back Cushions: Reinforce seams and conceal them in intersecting surfaces or channels.
8. Sources:

MARGAN LTD  
KC BOOTH Company  
HCF Contract Furniture  
New England Seating Company

END OF SECTION