

## SECTION 22 14 23 - STORM DRAINAGE PIPING SPECIALTIES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following storm drainage piping specialties:
  - 1. Cleanouts.
  - 2. Through-penetration firestop assemblies.
  - 3. Roof drains.
  - 4. Miscellaneous storm drainage piping specialties.
  - 5. Flashing materials.
- B. Related Sections include the following:
  - 1. Division 22 Section "Sanitary Waste Piping Specialties" for backwater valves, floor drains, trench drains and channel drainage systems connected to sanitary sewer, air admittance valves, FOG disposal systems, grease interceptors and removal devices, oil interceptors, and solid interceptors.

#### 1.3 DEFINITIONS

- A. ABS: Acrylonitrile-butadiene-styrene plastic.
- B. FOG: Fats, oils, and greases.
- C. FRP: Fiberglass-reinforced plastic.
- D. HDPE: High-density polyethylene plastic.
- E. PE: Polyethylene plastic.
- F. PP: Polypropylene plastic.
- G. PUR: Polyurethane plastic.
- H. PVC: Polyvinyl chloride plastic.

1.4 SUBMITTALS

- A. Product Data: For each type of product indicated.

1.5 QUALITY ASSURANCE

- A. Drainage piping specialties shall bear label, stamp, or other markings of specified testing agency.

1.6 COORDINATION

- A. Coordinate size and location of roof penetrations.

PART 2 - PRODUCTS

2.1 CLEANOUTS

- A. Exposed Metal Cleanouts:

1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
2. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
3. Basis-of-Design Product: Subject to compliance with requirements, provide the product indicated on Drawings or a comparable product by one of the following:
  - a. Josam Company; Josam Div.
  - b. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
  - c. Tyler Pipe; Wade Div.
  - d. Zurn Plumbing Products Group; Specification Drainage Operation.
4. Standard: ASME A112.36.2M for cast iron for cleanout test tee.
5. Size: Same as connected drainage piping
6. Body Material: Hub-and-spigot, cast-iron soil pipe T-branch and Hubless, cast-iron soil pipe test tee as required to match connected piping.
7. Closure: Countersunk Raised-head, brass plug.
8. Closure Plug Size: Same as or not more than one size smaller than cleanout size.
9. Closure: Stainless-steel plug with seal.

- B. Cast-Iron Wall Cleanouts:

1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

2. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
3. Basis-of-Design Product: Subject to compliance with requirements, provide the product indicated on Drawings or a comparable product by one of the following:
  - a. Josam Company; Josam Div.
  - b. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
  - c. Tyler Pipe; Wade Div.
  - d. Zurn Plumbing Products Group; Specification Drainage Operation.
4. Standard: ASME A112.36.2M. Include wall access.
5. Size: Same as connected drainage piping.
6. Body: Hub-and-spigot, cast-iron soil pipe T-branch, Hubless, cast-iron soil pipe test tee as required to match connected piping.
7. Closure: Countersunk, brass plug.
8. Closure Plug Size: Same as or not more than one size smaller than cleanout size.
9. Wall Access: Round, flat, chrome-plated brass or stainless-steel cover plate with screw.
10. Wall Access: Round, stainless-steel wall-installation frame and cover.

## 2.2 THROUGH-PENETRATION FIRESTOP ASSEMBLIES

### A. Through-Penetration Firestop Assemblies:

1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
2. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. ProSet Systems Inc.
3. Standard: UL 1479 assembly of sleeve and stack fitting with firestopping plug.
4. Size: Same as connected pipe.
5. Stack Fitting: ASTM A 48/A 48M, gray-iron, hubless-pattern, wye branch with neoprene O-ring at base and gray-iron plug in thermal-release harness. Include PVC protective cap for plug.
6. Special Coating: Corrosion resistant on interior of fittings.

## 2.3 ROOF DRAINS

### A. Metal Roof Drains:

1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

2. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
3. Basis-of-Design Product: Subject to compliance with requirements, provide the product indicated on Drawings or a comparable product by one of the following:
  - a. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
  - b. Tyler Pipe; Wade Div.
4. Standard: ASME A112.21.2M.
5. Pattern: Roof drain.
6. Body Material: Cast iron.
7. Dimensions of Body: As noted on the drawings.
8. Combination Flashing Ring and Gravel Stop: Required.
9. Flow-Control Weirs: Not required.
10. Outlet: Bottom.
11. Dome Material: Cast iron.
12. Extension Collars: Required.
13. Underdeck Clamp: Required.
14. Sump Receiver: Required.

#### 2.4 MISCELLANEOUS STORM DRAINAGE PIPING SPECIALTIES

##### A. Expansion Joints:

1. Standard: ASME A112.21.2M.
2. Body: Cast iron with bronze sleeve, packing, and gland.
3. End Connections: Matching connected piping.
4. Size: Same as connected piping.

##### B. Conductor Nozzles (Overflow Outlets):

1. Description: Bronze body with threaded inlet and bronze wall flange with mounting holes.
2. Size: Same as connected conductor.

#### 2.5 FLASHING MATERIALS

- A. Copper Sheet: ASTM B 152/B 152M, 12 oz./sq. ft. (3.7 kg/sq. m or 0.41-mm) thickness.
- B. Zinc-Coated Steel Sheet: ASTM A 653/A 653M, with 0.20 percent copper content and 0.04-inch (1.01-mm) minimum thickness, unless otherwise indicated. Include G90 (Z275) hot-dip galvanized, mill-phosphatized finish for painting if indicated.
- C. Elastic Membrane Sheet: ASTM D 4068, flexible, chlorinated polyethylene, 40-mil (1.01-mm) minimum thickness.
- D. Fasteners: Metal compatible with material and substrate being fastened.

#### STORM DRAINAGE PIPING SPECIALTIES

- E. Metal Accessories: Sheet metal strips, clamps, anchoring devices, and similar accessory units required for installation; matching or compatible with material being installed.
- F. Solder: ASTM B 32, lead-free alloy.
- G. Bituminous Coating: SSPC-Paint 12, solvent-type, bituminous mastic.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Refer to Division 22 Section "Common Work Results for Plumbing" for piping joining materials, joint construction, and basic installation requirements.
- B. Install cleanouts in aboveground piping and building drain piping according to the following, unless otherwise indicated:
  - 1. Size same as drainage piping up to NPS 4 (DN 100). Use NPS 4 (DN 100) for larger drainage piping unless larger cleanout is indicated.
  - 2. Locate at each change in direction of piping greater than 45 degrees.
  - 3. Locate at minimum intervals of 50 feet (15 m) for piping NPS 4 (DN 100) and smaller and 100 feet (30 m) for larger piping.
  - 4. Locate at base of each vertical soil and waste stack.
- C. For cleanouts located in concealed piping, install cleanout wall access covers with frame and cover flush with finished wall.
- D. Install through-penetration firestop assemblies in plastic conductors and stacks at floor penetrations.
- E. Install roof drains at low points of roof areas according to roof membrane manufacturer's written installation instructions. Roofing materials are specified in Division 07.
  - 1. Install roof-drain flashing collar or flange so that there will be no leakage between drain and adjoining roofing. Maintain integrity of waterproof membranes where penetrated.
  - 2. Position roof drains for easy access and maintenance.
- F. Install sleeve flashing device with each riser and stack passing through floors with waterproof membrane.
- G. Install expansion joints on vertical stacks and conductors. Position expansion joints for easy access and maintenance.
- H. Install conductor nozzles at exposed bottom of conductors where they spill onto grade.

- I. Install escutcheons at wall, floor, and ceiling penetrations in exposed finished locations and within cabinets and millwork. Use deep-pattern escutcheons if required to conceal protruding pipe fittings.

### 3.2 CONNECTIONS

- A. Piping installation requirements are specified in other Division 22 Sections. Drawings indicate general arrangement of piping, fittings, and specialties.

### 3.3 FLASHING INSTALLATION

- A. Fabricate flashing from single piece unless large pans, sumps, or other drainage shapes are required. Join flashing according to the following if required:
  1. Lead Sheets: Burn joints of lead sheets 6.0-lb/sq. ft. (30-kg/sq. m), 0.0938-inch (2.4-mm) thickness or thicker. Solder joints of lead sheets 4.0-lb/sq. ft. (20-kg/sq. m), 0.0625-inch (1.6-mm) thickness or thinner.
  2. Copper Sheets: Solder joints of copper sheets.
- B. Install sheet flashing on pipes, sleeves, and specialties passing through or embedded in floors and roofs with waterproof membrane.
  1. Pipe Flashing: Sleeve type, matching pipe size, with minimum length of 10 inches (250 mm), and skirt or flange extending at least 8 inches (200 mm) around pipe.
  2. Sleeve Flashing: Flat sheet, with skirt or flange extending at least 8 inches (200 mm) around sleeve.
  3. Embedded Specialty Flashing: Flat sheet, with skirt or flange extending at least 8 inches (200 mm) around specialty.
- C. Set flashing on floors and roofs in solid coating of bituminous cement.
- D. Secure flashing into sleeve and specialty clamping ring or device.
- E. Fabricate and install flashing and pans, sumps, and other drainage shapes.

### 3.4 PROTECTION

- A. Protect drains during remainder of construction period to avoid clogging with dirt or debris and to prevent damage from traffic or construction work.
- B. Place plugs in ends of uncompleted piping at end of each day or when work stops.

END OF SECTION