

SECTION 26 09 43 - NETWORK LIGHTING CONTROLS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes manually operated, PC-based, digital lighting controls with external signal source, relays , electrically operated circuit breakers, and control module.
- B. Related Sections include the following:
 - 1. Division 26 Section "Lighting Control Devices" for time switches, photoelectric switches, occupancy sensors, and multiple contactors.

1.3 DEFINITIONS

- A. BACnet: A networking communication protocol that complies with ASHRAE 135.
- B. BAS: Building automation system.
- C. LonWorks: A control network technology platform for designing and implementing interoperable control devices and networks.
- D. Low Voltage: As defined in NFPA 70 for circuits and equipment operating at less than 50 V or for remote-control, signaling and power-limited circuits.
- E. Monitoring: Acquisition, processing, communication, and display of equipment status data, metered electrical parameter values, power quality evaluation data, event and alarm signals, tabulated reports, and event logs.
- F. PC: Personal computer; sometimes plural as "PCs."
- G. Power Line Carrier: Use of radio-frequency energy to transmit information over transmission lines whose primary purpose is the transmission of power.
- H. RS-485: A serial network protocol, similar to RS-232, complying with TIA/EIA-485-A.

1.4 SUBMITTALS

- A. Product Data: For control modules, power distribution components, manual switches and plates, and conductors and cables.
- B. Shop Drawings: Detail assemblies of standard components, custom assembled for specific application on this Project.
 - 1. Outline Drawings: Indicate dimensions, weights, arrangement of components, and clearance and access requirements.
 - 2. Block Diagram: Show interconnections between components specified in this Section and devices furnished with power distribution system components. Indicate data communication paths and identify networks, data buses, data gateways, concentrators, and other devices to be used. Describe characteristics of network and other data communication lines.
 - 3. Wiring Diagrams: Power, signal, and control wiring. Coordinate nomenclature and presentation with a block diagram.
- C. Coordination Drawings: Submit evidence that lighting controls are compatible with connected monitoring and control devices and systems specified in other Sections.
 - 1. Show interconnecting signal and control wiring and interfacing devices that prove compatibility of inputs and outputs.
 - 2. For networked controls, list network protocols and provide statements from manufacturers that input and output devices meet interoperability requirements of the network protocol.
- D. Software and Firmware Operational Documentation:
 - 1. Software operating and upgrade manuals.
 - 2. Program Software Backup: On a magnetic media or compact disc, complete with data files.
 - 3. Device address list.
 - 4. Printout of software application and graphic screens.
- E. Field quality-control test reports.
- F. Software licenses and upgrades required by and installed for operation and programming of digital and analog devices.
- G. Operation and Maintenance Data: For lighting controls to include in emergency, operation, and maintenance manuals.
- H. Warranty: Special warranty specified in this Section.

1.5 QUALITY ASSURANCE

- A. Source Limitations: Obtain lighting control module and power distribution components through one source from a single manufacturer.

- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- C. Comply with 47 CFR, Subparts A and B, for Class A digital devices.
- D. Comply with NFPA 70.

1.6 COORDINATION

- A. Coordinate lighting control components to form an integrated interconnection of compatible components.
 - 1. Match components and interconnections for optimum performance of lighting control functions.
 - 2. Coordinate lighting controls with BAS-HVAC controls. Design display graphics showing building areas controlled; include the status of lighting controls in each area.
 - 3. Coordinate lighting controls with that in Sections specifying distribution components that are monitored or controlled by power monitoring and control equipment.
- B. Coordinate lighting control components specified in this Section with components specified in Division 26 Section "Panelboards."

1.7 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of lighting controls that fail in materials or workmanship or from transient voltage surges within specified warranty period.
 - 1. Failures include, but are not limited to, the following:
 - a. Failure of software input/output to execute switching or dimming commands.
 - b. Failure of modular relays to operate under manual or software commands.
 - c. Damage of electronic components due to transient voltage surges.
 - 2. Warranty Period: Two years from date of Substantial Completion.
 - 3. Extended Warranty Period Failure Due to Transient Voltage Surges: Eight years.
 - 4. Extended Warranty Period for Electrically Held Relays: 10 years from date of Substantial Completion.

1.8 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Electrically Held Relays: Equal to 5 percent of amount installed for each size indicated, but no fewer than ten relays.
 - 2. Electrically Operated, Molded-Case Circuit Breakers: Equal to 5 percent of amount installed for each size indicated, but no fewer than 10 circuit breakers.

1.9 SOFTWARE SERVICE AGREEMENT

- A. Technical Support: Beginning with Substantial Completion, provide software support for two years.
- B. Upgrade Service: Update software to latest version at Project completion. Install and program software upgrades that become available within two years from date of Substantial Completion. Upgrading software shall include operating system. Upgrade shall include new or revise licenses for use of the software.
 - 1. Provide 30-day notice to Owner to allow scheduling and access to system and to allow Owner to upgrade computer equipment, if necessary.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Intelligent Lighting Controls, Inc.
 - 2. Leviton Mfg. Company Inc.
 - 3. Lighting Control & Design, Inc.
 - 4. Lithonia Lighting; Acuity Lighting Group, Inc.
 - 5. Lutron Electronics Company, Inc.
 - 6. Watt Stopper (The).

2.2 SYSTEM REQUIREMENTS

- A. Expandability: System shall be capable of increasing the number of control functions in the future by 25 percent of current capacity; to include equipment ratings, housing capacities, spare relays, terminals, number of conductors in control cables, and control software.

- B. Performance Requirements: Manual switches, an internal timing and control unit, and external sensors or other control signal sources send a signal to a PC-based programmable-system control module that processes the signal according to its programming and routes an open or close command to one or more relays and electrically operated circuit breakers in the power-supply circuits, or routes variable commands to one or more dimmers, for groups of lighting fixtures or other loads.

2.3 CONTROL MODULE

- A. Control Module Description: Comply with UL 508 (CSA C22.2, No. 14); microprocessor-based, programmable, control unit; mounted in preassembled, modular relay panel. Low-voltage-controlled, latching-type, single-pole lighting circuit relays shall be prime output circuit devices. Where indicated, a limited number of digital or analog, low-voltage control-circuit outputs shall be supported by control unit and circuit boards associated with relays. Control units shall be capable of receiving inputs from sensors and other sources. Line-voltage components and wiring shall be separated from low-voltage components and wiring by barriers. Control module shall be locally programmable.

2.4 POWER DISTRIBUTION COMPONENTS

- A. Modular Relay Panel: Comply with UL 508 (CSA C22.2, No. 14) and UL 916 (CSA C22.2, No. 205); factory assembled with modular single-pole relays, power supplies, and accessory components required for specified performance.
 - 1. Panel shall consist of relays, system time clock, panel intelligence, power supply, DIN Rails, tub and cover.
 - 2. Cabinet: Steel with hinged, locking door.
 - a. Barriers separate low-voltage and line-voltage components.
 - b. Directory: Mounted on back of door. Identifies each relay as to load groups controlled and each programmed pilot device if any.
 - c. Control Power Supply: Transformer and full-wave rectifier with filtered dc output.
 - 3. Single-Pole Relays: Mechanically held unless otherwise indicated; split-coil, momentary-pulsed type.
 - a. Low-Voltage Leads: Plug connector to the connector strip in cabinet and pilot light power where indicated.
 - b. Rated Capacity (Mounted in Relay Panel): 20 A, 125-V ac for tungsten filaments; 20 A, 277-V ac for ballasts.
 - c. Endurance: 50,000 cycles at rated capacity.
 - d. Mounting: Provision for easy removal and installation in relay cabinet.
- B. Line-Voltage Surge Suppression: Factory installed as an integral part of 120- and 277-V ac, solid-state control panels or field-mounting surge suppressors that

comply with Division 26 Section "Transient-Voltage Suppression for Low-Voltage Electrical Power Circuits" for Category A locations.

2.5 MANUAL SWITCHES AND PLATES

- A. Push-Button Switches: Modular, momentary-contact, low-voltage type.
 - 1. Match color specified in Division 26 Section "Wiring Devices."
 - 2. Integral green LED pilot light to indicate when circuit is on.
 - 3. Internal white LED locator light to illuminate when circuit is off.
- B. Manual, Maintained Contact, Full- or Low-Voltage Switch: Comply with Division 26 Section "Wiring Devices."
- C. Wall-Box Dimmers: Comply with Division 26 Section "Wiring Devices."
- D. Wall Plates: Single and multigang plates as specified in Division 26 Section "Wiring Devices."
- E. Legend: Engraved or permanently silk-screened on wall plate where indicated. Use designations indicated on Drawings.

2.6 CONDUCTORS AND CABLES

- A. Power Wiring to Supply Side of Class 2 Power Source: Not smaller than No. 12 AWG, complying with Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."
- B. Classes 2 and 3 Control Cables: Multiconductor cable with copper conductors not smaller than No. 18 AWG, complying with Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."
- C. Class 1 Control Cables: Multiconductor cable with copper conductors not smaller than No. 14 AWG, complying with Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."
- D. Digital and Multiplexed Signal Cables: Unshielded, twisted-pair cable with copper conductors, complying with TIA/EIA-568-B.2, Category 5e for horizontal copper cable and with Division 27 Section "Communications Horizontal Cabling."

PART 3 - EXECUTION

3.1 WIRING INSTALLATION

- A. Comply with NECA 1.

- B. Wiring Method: Install wiring in raceways except where installed in accessible ceilings and gypsum board partitions. Comply with Division 26 Section "Low-Voltage Electrical Power Conductors and Cables." Minimum conduit size shall be $\frac{3}{4}$ inch.
- C. Wiring within Enclosures: Bundle, lace, and train conductors to terminal points. Separate power-limited and non-power-limited conductors according to conductor manufacturer's written instructions.
- D. Install field-mounting transient voltage suppressors for lighting control devices in Category A locations that do not have integral line-voltage surge protection.
- E. Size conductors according to lighting control device manufacturer's written instructions, unless otherwise indicated.
- F. Splices, Taps, and Terminations: Make connections only on numbered terminal strips in terminal cabinets, equipment enclosures, and in junction, pull, and outlet boxes.
- G. Identify components and power and control wiring according to Division 26 Section "Identification for Electrical Systems."

3.2 FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust field-assembled components and equipment installation, including connections, and assist in field testing. Report results in writing.
- B. Perform the following field tests and inspections and prepare test reports:
 - 1. Test for circuit continuity.
 - 2. Verify that the control module features are operational.
 - 3. Check operation of local override controls.
 - 4. Test system diagnostics by simulating improper operation of several components selected by Architect.

3.3 SOFTWARE INSTALLATION

- A. Install and program software with initial settings of adjustable values. Make backup copies of software and user-supplied values. Provide current licenses for software.

3.4 ADJUSTING

- A. Occupancy Adjustments: When requested within 12 months of date of Substantial Completion, provide on-site assistance in adjusting sensors and to assist Owner's personnel in making program changes to suit actual occupied conditions. Provide

Maine Medical Center
Bean 2 Roof Addition
For Construction
ADDENDUM No. 3
Issued for Permit

PERKINS+WILL
C140135461 (MMC) /152168.00 (P+W)
June 14, 2013
January 17, 2014
February 07, 2014

up to two visits to Project during other than normal occupancy hours for this purpose.

3.5 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain lighting controls and software training for PC-based control systems. Refer to Division 01 Section "Demonstration and Training."

END OF SECTION