GENERAL NOTES:

1. RE-BALANCE EXISTING DIFFUSERS AND REGISTERS AFFECTED BY NEW WORK TO ORIGINAL AIRFLOWS PRIOR TO DEMOLITION.
2. MAINTAIN ACCESS TO ALL NEW AND EXISTING VALVES, FIRE DAMPERS AND VAV BOXES.
3. LOCATE ALL NEW VAV CONTROL AND ISOLATION VALVES IN SAME ROOM CEILING AS VAV BOX.

DRAWING KEY NOTES:

① RE-BALANCE EXISTING SA VAV BOX AS INDICATED BELOW.

② PROVIDE LD W/ 2'-0" ACTIVE SECTION. BLANK-OFF REMAINDER OF LD. REFER TO ARCH. RCP FOR ACTUAL LD LENGTH.

SUPPLY TERMINAL BOXES:

①	②	③	④
001	002	003	004
210	500	680	800
105	250	455	530
0.3	0.6	1.2	1.0
VAV-1	(E)VAV	(E)VAV	E(VAV)
(NEW)			

PERKINS + WILL

225 Franklin St., Suite 1100
Boston, MA 02110
t 617.478.0300
f 617.478.0021
www.perkinswill.com

Maine Medical Center
MaineHealth

RETAIL PHARMACY

22 Bramhall Street, Portland, ME

MEP ENGINEER
AKF ENGINEERS
99 Bedford Street, 2nd Floor
Boston, MA 02111
t 617.737.1111
f 617.737.4311

STRUCTURAL ENGINEER
SIMPSON GUMPERTZ & HEGER
41 Seyon Street, Building 1, Suite 500
Waltham, MA 02453
t 781.907.9000
f 781.907.9009

STATE OF MAINE
DAVID B ROBERTS
No. 11646
LICENSED PROFESSIONAL ENGINEER

Revisions

NO	ISSUE	DATE
4	ISSUED FOR PERMIT	08.11.14
1	ADDENDUM #1	07.28.14
	ISSUE FOR BID	07.11.14

Sheet Information

Date	JULY 11, 2014
Job #	152168.010
Drawn	TU
Checked	DPR
Approved	DPR

Title

MECHANICAL DUCTWORK PLAN

Sheet

M-200

Copyright © 2011 Perkins+Will

AKF Job # B140153-000