


PIPE SLEEVE THRU EXPOSED FLOOR SLAB

FLOOR SLAB -


PIPE SLEEVE \_













HANGER ROD SCHEDULE			HANGER ROD SPACING	
PIPE SIZE	ROD SIZE	PIPE SIZE	MAX. ALLOWABLE SPACING	
UP TO 2"	3/8" DIA.	1"	7'	
2 1/2" THRU 3"	1/2" DIA.	1 1/4"	8'	
4" AND 5"	5/8"	1 1/2"	9'	
6" THRU 8"	3/4"	2"	10'	
12"	7/8"	2 1/2"	11'	
		3" THRU 8"	12'	
		10" & 12"	15'	

PLUMBING PIPE HANGER INSTALLATION DETAIL SCALE: N.T.S.


> 1. FIRESTOP SEALANTS AND PIPING PENETRATIONS THROUGH FIRE RATED ASSEMBLIES SHALL COMPLY WITH THE UL FIRE RESISTANCE DIRECTORY.












7	PIPE PENETRATION WITHOUT INSULATION
	SCALE: N.T.S.



PERKINS

Maine Medical Center

**HYBRID OR &** 

22 Bramhall Street, Portland,

+WILL

225 Franklin St., Suite 1100 Boston, MA 02110

t 617.478.0300 f 617.478.0321 www.perkinswill.com

MaineHealth

OR #6

Maine 04102

AKF GROUP, LLC

99 Bedford Street, 2nd Floor

Boston, MA 02111 t 617.737.1111

STRUCTURAL ENGINEER

SIMPSON GUMPERTZ &

41 Seyon Street, Building 1, Suite 500 Waltham, MA 02453 t 781.907.9000

f 617.737.4311

HEGER

f 781.907.9009


MEP ENGINEER

Аррі	roved	JR	
Ched	cked	JR	
Drav	vn	DC	
Job :	#	B150155-000	
Date	ate JULY 31, 201		
	Sheet In	formation	
NO	ISSUE	DATE	
	ISSUED FOR PERMIT	08.21.2015	

**PLUMBING DETAILS** 

P03-00

Copyright © 2014 Perkins+Will





SLEEVES IN MECHANICAL

MIN. 6" ABOVE FINISH FLOOR.

→ PENETRATIONS & SEALANT SHALL BE IN ACCORDANCE WITH LOCAL

— SEALANT (SEE SPEC.)

ROOMS SHALL EXTEND

— ESCUTCHEON

BUILDING CODE

