ABBREVIATIONS LEGEND

ABBREVIATIONS WHEN USED IN COMPOSITION MAY INCLUDE PERIODS FOR CLARIFICATION

A	AIR
A/C	AIR CONDITION(ING)(ED)
AB	ANCHOR BOLT
ACC	ACCESSIBLE
ACID RES	ACID RESISTANT
ACS FLR	ACCESS FLOOR
ACS PNL	ACCESS PANEL
ACST	ACOUSTICAL)
ACT	ACOUSTICAL CEILING TILE
AD	AREA DRAIN
ADA	AMERICANS WITH DISABILITIES ACT
ADH	ADHESIVE
ADJ	ADJACENT
ADJ	ADJUSTABLE
ADMIN	ADMINISTRATION
ADMIT	ADMITTING
AFF	ABOVE FINISHED FLOOR
AGGR	AGGREGATE
AHR	ANCHOR
AHU	AIR HANDLING UNIT
ALT	ALTERNATE
ALUM	ALUMINUM
ANESTH	ANESTHESIOLOGY
ANGIO	ANGIOGRAPHY
ANN	ANNUNCIATOR
ANOD	ANODIZE(D)
APC	ACOUSTICAL PANEL CEILING
APPROX	APPROXIMATE
ARCH	ARCHITECT(URAL)
ASPH	ASPHALT
ATC	ACOUSTICAL TILE CEILING
AUTO	AUTOMATIC
AWT	ACOUSTICAL WALL TREATMENT
B/B	BACK TO BACK
BB	BASE BOARD
BB	BULLETIN BOARD
BD	BOARD
BG	BUMPER GUARD
BITUM	BITUMINOUS
BL	BED LOCATOR
BLDG	BUILDING
BM	BEAM
BM	BENCHMARK
BOT	BOTTOM
BOT	BOTOM OF
BP	BED PAN HOLDER
BPRF	BULLETPROOF (BULLET-RESISTANT)
BR	BUMPER RAIL
BRG	BEARING
BRZ	BRONZE
BSMT	BASEMENT
BTWN	BETWEEN
BUR	BUILT-UP ROOFING
BW	BLANKET WARMER
C TO C	CENTER TO CENTER
CO2	CARBON DIOXIDE
CAB	CABINET
CARDIO	CARDIOLOGY
CATH	CATHETERIZATION
CB	CATCH BASIN
CBB	CEMENTITIOUS BACKER BOARD
CC	CUBICAL CURTAIN TRACK
EXIST	EXISTING
EXP	EXPANSION JOINT
EXP	EXPOSED
EXT	EXTERIOR
EXT	EXTERNAL
EXT	EXTINGUISHER
EXT LT	EXIT LIGHT
F/F	FACE TO FACE
FA	FIRE ALARM
FAAP	FIRE ALARM ANNUNCIATOR PANEL
FAB	FABRIC
FACP	FIRE ALARM CONTROL PANEL
FC	FILE CABINET
FC BRK	FACE BRICK
FD	FLOOR DRAIN
FDC	FIRE DEPARTMENT CONNECTION
FDCC	FIRE DEPT. CONNECTION CABINET
FDTN	FOUNDATION
FE	FIRE EXTINGUISHER
FEC	FIRE EXTINGUISHER CABINET
FGL	FIBERGLASS
FH	FIRE HYDRANT
FHC	FIRE HOSE CABINET
FHR	FIRE HOUSE RACK
FIN	FINISH(ED)
FIN FLR	FINISHED FLOOR
FIXT	FIXTURE
FLASH	FLASHING
FLEX	FLEXIBLE
FLG	FLOORING
FLR	FLOOR
FLOUR	FLUORESCENT
FO	FINISHED OPENING
FOC	FACE OF CONCRETE
FOC	FACE OF CURB
FOF	FACE OF FINISH
FOM	FACE OF MASONRY
FOS	FACE OF SLAB
FOS	FACE OF STUD
FOW	FACE OF WALL
FP	FIRE PROTECTION
FR	FIRE RATING
FR	FIRE RESISTANT
FR	FRAME
FRG	FIBER REINFORCED GYPSUM
FRMG	FRAMING
FRTW	FIRE RETARDANT TREATED WOOD
FRZ	FREEZER
FT	FEET
FT	FIRE TREATED
FT	FOOT
FT	FULLY TEMPERED (GLASS)
FTG	FOOTING
FTR	FINNED TUBE RADIATION
FURG	FURRING
FURN	FURNISH, FURNITURE
FUT	FUTURE
G	GROUND
GA	GAGE
GALC	GALVANIZED
GB	GRAB BAR
GDR	GUARD RAIL
STOR	STORAGE
STRUCT	STRUCTURE, STRUCTURAL
SU	SOILED UTILITY
SUCT	SUCTION
SUPVR	SUPERVISOR
SURF	SURFACE
SURG	SURGICAL INTENSIVE CARE UNIT
SUSP	SUSPENDED
SV	SHEET VINYL
SWBD	SWITCHBOARD
SYMM	SYMMETRICAL
SYS	SYSTEM
T	TREAD
T&B	TOP & BOTTOM
T&G	TONGUE & GROOVE
TCA	TILE COUNCIL OF AMERICA
TD	TOWEL DISPENSER
TDR	TOWEL DISPENSER AND RECEPTACLE
TEL	TELEPHONE
TELEM	TELEMETRY
TEMP	TEMPORARY
TER	TERRAZZO
TFF	TOP OF FINISH FLOOR
THK	THICK(NESS)
THRES	THRESHOLD
TK BD	TACK BOARD
TL	TASK LIGHT
TLT	TOILET
TEMP	TEMPERED
TO	TOP OF
TOB	TOP OF BEAM
TOC	TOP OF CONCRETE
TOF	TOP OF FLOOR
TOF	TOP OF FOOTING
TOJ	TOP OF JOIST
TOM	TOP OF MASONRY
TOP	TOP OF PARAPET
TOPO	TOPOGRAPHY, TOPOGRAPHIC
TOS	TOP OF SLAB
TOS	TOP OF STEEL
TOW	TOP OF WALL
TPD	TOILET PAPER DISPENSER
TPH	TOILET PAPER HOLDER
TREAT	TREATMENT
TRTD	TREATED
TS	TUBE STEEL
TV	TELEVISION
TV BRK	TELEVISION MOUNTING BRACKET
TYP	TYPICAL
U	HEAT TRANSFER COEFFICIENT
UGND	UNDER GROUND
UH	UNIT HEATER
UL	UNDERWRITER'S LABORATORIES
UNEX	UNEXCAVATED
UNFIN	UNFINISHED
UNO	UNLESS NOTED OTHERWISE
UR	URINAL
UTIL	UTILITY
VAC	VACUUM LINE
VAC CTR	VACUUM CONTAINER
VAC SL	VACUUM SLIDE
VAR	VARIES
MOD	MODULE
MOD BIT	MODIFIED BITUMEN
MON	MONITOR
MON	MONUMENT
MRI	MAGNETIC RESONANCE IMAGING
MS	MOP SINK
MTD	MOUNTED
MTG	MEETING
MTL	METAL CORNER BEAD
MULL	MULLION
MVBL	MOVABLE
MW	MICROWAVE
N	NORTH
N2	NITROGEN
N20	NITROUS OZIDE
NA	NOT APPLICABLE
NAR	NARROW
NARC	NARCOTICS
NC	NURSE CALL
NEURO	NEUROLOGY
NIC	NOT IN CONTRACT
NL	NIGHT LIGHT
NO	NUMBER
NOM	NOMINAL
NS	NURSE STATION
NTS	NOT TO SCALE
NUC	NUCLEAR
NUR	NURSE(RY)
O	OXYGEN
O/O	OUT TO OUT
OA	OVERALL
OB	OBSTETRICS
OC	ON CENTER
OCC	OCCUPY, OCCUPANT
OD	OUTSIDE DIAMETER
OF/CI	OWNER FURNISHED, CONTR INSTALLED
OF/OI	OWNER FURNISHED, OWNER INSTALLED
OFF	OFFICE
OP	OUT PATIENT
OPH	OPPOSITE HAND
OPNG	OPENING
OPP	OPERABLE
OPR	OPTIONAL
OPT	OPTIONAL
OR	OPERATING ROOM
ORD	OVERFLOW ROOF DRAIN
ORN	ORNAMENTAL
ORTHO	ORTHOPEDICS
OTO	OPTHALMOSCOPE
OTO	OTOSCOPE
PA	PUBLIC ADDRESS
PACU	POST ANESTHESIA CARE UNIT
PAR	PARALLEL
PAR	PARAPET
PAT	PATIENT
PATH	PATHOLOGY
PBD	PARTICLEBOARD
PCC	PRE-CAST CONCRETE
PED	PEDESTAL
PEDS	PEDIATRIC(S)
PEND	PENDANT
PERF	PERFORATED

SYMBOLS

&	AND
@	AT
x	BY
[	CHANNEL
°	DEGREE
Ø	DIAMETER
∆	DOUBLE ANGLE
"	INCHES
#	NUMBER, POUNDS
d	PENNY (NAIL)
%	PERCENT
±	PLUS OR MINUS
□	TUBE

MATERIALS

- COMPACTED SOIL
- UNDISTURBED SOIL
- COURSE POROUS FILL
- SAND
- BITUMINOUS PAVING
- CONCRETE
- TERRAZZO
- CUT STONE
- BRICK MASONRY
- CONCRETE MASONRY UNIT
- STRUCTURAL CLAY TILE UNIT MASONRY
- STEEL
- ALUMINUM
- ORNAMENTAL METAL
- CONTINUOUS WOOD FRAMING
- WOOD BLOCKING
- FINISH WOODWORK
- PLYWOOD
- PARTICLE BOARD
- GYPSUM WALLBOARD
- WATERPROOFING
- MINERAL WOOL INSULATION
- BATT INSULATION
- CARPETING
- RESILIENT FLOORING
- PLASTIC LAMINATE
- LEAD-LINED GYPSUM WALLBOARD
- GLAZING
- GLASS BLOCK
- ACOUSTICAL CEILING BOARD
- SEALANT AND BACKER ROD
- SPRAY-ON FIREPROOFING

SYMBOLS LEGEND

SHEET NUMBER

A-521

SHEET NUMBER
CATEGORY NUMBER
DISCIPLINE LETTER

NORTH ARROW

TRUE NORTH

GRAPHIC SCALE

0 2' 4' 8'
SCALE: 1" = 4'-0"

COLUMN SYMBOL & CENTER LINES

A AA 1 1

VERTICAL ELEVATION

LEVEL 2
FRE 18'-6"

SPOT ELEVATION

SECOND FLOOR
EL. 18'-6"

DATUM POINT

MATCH LINE

MATCH LINE
SEE XX/X-XXX
SHEET NUMBER ON WHICH CONTIUNATION IS FOUND

PROPERTY LINE

FENCING (WITH POSTS)

BREAK LINE

DRAWING TITLE

A5 DRAWING
1/4" = 1'-0"

NOTE, SHEET NOTE

X

KEY NOTE

00 00 00.00

ROOM NAME AND NUMBER

ROOM NAME
4-3096

DOOR NUMBER

NEW DOOR IN NEW OR EXISTING FRAME
OR
DOOR NO. USE ROOM NO WITH DOOR MARK OR DOOR MARK ONLY
EXISTING DOOR & FRAME

WINDOW TYPE SYMBOL

WINDOW TYPE

PARTITION TAG

A41

BUILDING SECTION TAG

SECTION DESIGNATION
SHEET NUMBER

DETAIL/WALL SECTION TAG

SECTION DESIGNATION
SHEET NUMBER

PARTIAL PLAN AND DETAIL TAG

PLAN OR DETAIL DESIGNATION
SHEET NUMBER

EXTERIOR ELEVATION TAG

ELEVATION DESIGNATION
SHEET NUMBER

INTERIOR ELEVATION TAG

ELEVATION DESIGNATION
SHEET NUMBER

DRAWING REVISION

FIRE HOSE CABINET
(RECESSED AND SURFACE MOUNTED)

FHC FHC

FIRE EXTINGUISHER CABINET
(RECESSED AND SURFACE MOUNTED)

FEC FEC

EQUIPMENT AND FURNITURE TAG

45925C

TOILET ROOM ACCESSORY TAG

TA1

SHOWER HEAD

FLOOR SINK

F.S.

FLOOR DRAIN

F.D.

OVERFLOW DRAIN AND ROOF DRAIN

OVERFLOW DRAIN
ROOF DRAIN

ROOF TOP UNIT
REFER TO MECHANICAL FOR TYPE

RTU

GENERAL NOTES

1. NOTES APPEAR ON VARIOUS DRAWINGS FOR DIFFERENT SYSTEMS AND MATERIALS. REVIEW ALL SHEETS AND APPLY NOTES TO RELATED BUILDING COMPONENTS.

2. REFER TO COMPLETE SET OF ISSUED CONTRACT DOCUMENTS FOR OTHER APPLICABLE NOTES, ABBREVIATIONS, AND SYMBOLS.

3. WHERE MATERIALS ARE APPLIED TO, OR ARE IN DIRECT CONTACT WITH WORK INSTALLED BY ANOTHER SUBCONTRACTOR, COMMENCEMENT OF WORK IMPLIES ACCEPTANCE OF THE SUBSTRATE AS SUITABLE FOR THE APPLICATION INTENDED.

4. ISOLATE DISSIMILAR METALS TO PREVENT GALVANIC CORROSION.

5. PARTITION TYPES AND FIRE RESISTIVE RATINGS INDICATED ON A WALL ARE TO BE CONTINUOUS FOR THE LENGTH AND HEIGHT OF A PARTITION.

6. OPENINGS IN RATED WALL, FLOOR, CEILING AND ROOF ASSEMBLIES SHALL BE SEALED WITH PENETRATION SEALANT SYSTEMS MEETING OR EXCEEDING THE REQUIRED FIRE RESISTIVE RATINGS.

7. MAINTAIN THE FIRE RATING OF CONSTRUCTION AROUND CABINETS, PANELS, AND BOXES RECESSED IN FIRE RATED WALL, FLOOR, AND CEILING ASSEMBLIES.

8. PROVIDE CONTINUOUS PERIMETER FIRE SAFING BETWEEN FLOORS AND COORDINATE THE INSTALLATION WITH THE EXTERIOR WALL. FIRE RATING OF SAFING SHALL MATCH FIRE RATING OF FLOOR CONSTRUCTION.

9. DO NOT SCALE THE DRAWINGS.

10. FIELD MEASURE AND CONFIRM DIMENSIONS FOR OWNER PROVIDED EQUIPMENT AND FURNISHINGS.

11. PROVIDE STIFFENERS, BRACING, BACKING PLATES AND BLOCKING REQUIRED FOR SECURE INSTALLATION OF TOILET PARTITIONS, DOORS AND DOOR HARDWARE INCLUDING WALL-MOUNTED DOOR STOPS, HANDRAILS, WALL-MOUNTED SHELVES, OPERABLE PARTITIONS, MISCELLANEOUS EQUIPMENT, AND SUSPENDED MECHANICAL AND ELECTRICAL EQUIPMENT.

12. COORDINATE ALL BASE AND HOUSEKEEPING PADS WITH MECHANICAL, PLUMBING AND ELECTRICAL EQUIPMENT.

13. LOCATE ACCESS PANELS AS INDICATED ON DRAWINGS. FOR ACCESS PANELS NOT SHOWN BUT REQUIRED BY PROVISIONS OF THE CONTRACT DOCUMENTS, LOCATED IN ACCORDANCE WITH APPLICABLE CODES. SUBMIT PROPOSED LOCATIONS TO THE ARCHITECT FOR REVIEW AND ACCEPTANCE PRIOR TO INSTALLATION.

PARTITION & DOOR NOTES

1. PARTITIONS LOCATED BY DIMENSION STRING ARE DIMENSIONED TO THE UNFINISHED FACE OF THE WALL UNLESS NOTED OTHERWISE.

2. PARTITIONS NOT DIMENSIONED ARE GENERALLY LOCATED BY ONE OF THE FOLLOWING CRITERIA:

- CENTERLINE - CENTER OF PARTITION ALIGNS WITH THE CENTER OF GRIDLINE OR OBJECT CENTERLINE (SUCH AS A COLUMN OR WINDOW MULLION). CENTER THE OVERALL PARTITION WIDTH, RATHER THAN STUD WIDTH ON THE LINE.

- ALIGN - LOCATE PARTITION FLUSH WITH FACE OF GYPSUM BOARD, OR OTHER SURFACE INDICATED.

- MAINTAIN DIMENSIONS NOTED AS "MINIMUM" OR "CLEAR".

1. DOOR OPENINGS ARE DIMENSIONED TO CENTERLINE OF OPENING. IF NOT DIMENSIONED, THE HINGE SIDE OF DOOR JAMBS SHALL BE SPACED 4" FROM THE ADJACENT WALL.

POWER/DATA LEGEND

WIRING DEVICES

WALL MTD CONVENIENCE OUTLETS @ 18" AFF (UNO)

SINGLE DUPLEX "QUAD" SPECIAL PURPOSE

FLOOR MTD CONVENIENCE OUTLETS

SINGLE DUPLEX "QUAD" SPECIAL PURPOSE

TELECOMM (VOICE/DATA) DEVICES

WALL MTD VOICE/DATA OUTLETS @ 18" AFF (UNO)

VOICE (TEL) DATA VOICE & DATA

FLOOR MTD VOICE/DATA OUTLETS

VOICE (TEL) DATA VOICE & DATA

LOUDSPEAKERS

LOUDSPEAKER DENOTES CEILING MOUNTED

JUNCTION/PULL BOXES

JUNCTION/PULL BOX

DENOTES FLOOR MOUNTED

DENOTES CEILING MOUNTED

LETTER(S) IN SYMBOL DENOTE(S) SYSTEM FOR WHICH JUNCTION/PULL BOX IS INTENDED

FLOOR CORE DRILL

OUTLET BOX(S) MOUNTED ON CONDUITS THRU CORE DRILLS. POWER (QUAD) / VOICE & DATA SHOWN. MODIFY DEVICES AS NECESSARY

CARD READER

MOUNTED AT 48" AFF (UNO)

REFLECTED CEILING LEGEND

ACOUSTIC CEILING TILE AND GRID

GYP. BOARD CEILING

CEILING MATERIAL AND HEIGHT

MATERIAL
9'-0" AFF

CEILING LIGHT FIXTURES

FLUORESCENT LTS FLUOR & INCAND DOWN LTS WALL WASHER

2 x 4 2 x 2

C1 C2 D1 D2

UPPER CASE LETTERS ADJACENT TO FIXTURE SYMBOL INDICATE FIXTURE TYPE, SEE FIXTURE LIST

ACCESS PANEL

DIFFUSER **RETURN**

SMOKE AND HEAT DETECTORS

S AND H

EXIT SIGN

CEILING MOUNTED OR WALL MOUNTED OR

SPRINKLER HEAD

FLUSH PENDENT UPRIGHT

Reviewed for Code Compliance
Portland Permit Services Division
Approved with Conditions

Date: 10/16/15

PERKINS + WILL

225 Franklin St., Suite 1100
Boston, MA 02110
t 617.478.0300
f 617.478.0321
www.perkinswill.com

Maine Medical Center
MaineHealth

HYBRID OR & OR #6

22 Bramhall Street, Portland, Maine 04102

MEP ENGINEER

AKF ENGINEERS

41 Farnsworth Street, 3rd Floor
Boston, MA 02210
t 617.737.1111
f 617.737.4311

STRUCTURAL ENGINEER

SIMPSON GUMPERTZ & HEGER

41 Seyon Street, Building 1, Suite 500
Waltham, MA 02453
t 781.907.9000
f 781.907.9009

LICENSED ARCHITECT DENNIS L. KAISER No. 2714 STATE OF MAINE

Revisions

	ISSUED FOR PERMIT	08.21.2015
	ISSUED FOR BID	07.31.2015
NO	ISSUE	DATE

Sheet Information

Date	AUGUST 21, 2015
Job #	152168.023
Drawn	Author
Checked	Checker
Approved	Approver

Title

GENERAL NOTES & ABBREVIATIONS

Sheet

A00-01

Copyright © 2015 Perkins+Will

8/24/2015 1:37:23 PM
c:\temp\MMC_NEW_HYBRID OR_allinsan.eskeves@perkinswill.com.rvt