DRAWING NOTES:

1. REFER TO DRAWING E00-01 FOR LEGEND, SYMBOLS, ABBREVIATIONS, AND ADDITIONAL GENERAL NOTES.

KEY NOTES:

1. PROVIDE WALL MOUNTED OCCUPANCY SENSOR FOR OCCUPIED/UNOCCUPIED CONTROL OF HVAC SYSTEM. OCCUPANCY SENSOR SHALL BE MOUNTED 8'-0" A.F.F. COORDINATE MOUNTING LOCATION WITH ARCHITECTURAL ELEVATIONS, DETAILS, AND FIELD CONDITIONS.
2. WIRE NEW FIXTURES TO NEAREST EXISTING 277V CRITICAL LIGHTING PANEL/CIRCUIT SERVING THE AREA. ELECTRICAL CONTRACTOR SHALL CONFIRM LOAD DOES NOT EXCEED CIRCUIT CAPACITY. PROVIDE NEW 277V CRITICAL LIGHTING CIRCUIT IF REQUIRED.
3. INDICATES FIXTURE TO BE DISCONNECTED, RELOCATED, AND RE-WIRED TO EXISTING CIRCUIT AND LIGHTING CONTROL TO ACCOMMODATE NEW OPERATING ROOM EXPANSION.
4. PROVIDE 1-POLE TOGGLE SWITCH INDICATED FOR MONTHLY EMERGENCY TESTING. SWITCH SHALL BE MOUNTED 6" BELOW FINISHED CEILING AND WIRED AHEAD OF LOCAL LIGHTING CONTROLS.

HYBRID OR SCOPE OF WORK

OR #6 SCOPE OF WORK

ADD ALTERNATE #1 SCOPE OF WORK

PLAN NORTH / TRUE NORTH

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 10/16/15

225 Franklin St., Suite 1100
Boston, MA 02110
t 617.478.0300
f 617.478.0321
www.perkinswill.com

Maine Medical Center
MaineHealth

HYBRID OR & OR #6

22 Bramhall Street, Portland, Maine 04102

MEP ENGINEER

AKF GROUP, LLC

99 Bedford Street, 2nd Floor
Boston, MA 02111
t 617.737.1111
f 617.737.4311

STRUCTURAL ENGINEER

SIMPSON GUMPERTZ & HEGER

41 Seyon Street, Building 1, Suite 500
Waltham, MA 02453
t 781.907.9000
f 781.907.9009

STATE OF MAINE
MARK F. RATTENBURY
No. 9122
ELECTRICAL
LICENSED PROFESSIONAL ENGINEER

Revisions

	ISSUED FOR PERMIT	08.21.2015
1	ADDENDUM 1	08.21.2015
	ISSUED FOR BID	07.31.2015
NO	ISSUE	DATE

Sheet Information

Date	JULY 31, 2015
Job #	B150155-000
Drawn	GN
Checked	MR
Approved	MR

Title

ELECTRICAL BASEMENT LIGHTING PLAN

Sheet

E03-0B

Copyright © 2014 Perkins+Will

8/21/2015 10:54:27 AM
C:\Revit Local Files\B150155-000 - MMC NEW HYBRID OR - MEP14_Central_anoy.rvt