MECHANICAL SYMBOL LIST

HVAC DUCTWORK

- SINGLE LINE DUCTWORK OR EQUIPMENT - NEW
- SINGLE LINE DUCTWORK OR EQUIPMENT - EXISTING
- EXISTING DUCTWORK TO BE REMOVED
- DUCTWORK WITH ACOUSTIC LINING
- DUCTWORK POSITIVE PRESSURE (SUPPLY AIR OR FAN DISCHARGE)
- DUCTWORK NEGATIVE PRESSURE (RETURN, EXHAUST OR OUTSIDE AIR)
- VD — VOLUME DAMPER
- FD — FIRE DAMPER AND ACCESS DOOR
- BDD — BACKDRAFT DAMPER
- M — AUTOMATIC DAMPER
- SD M — AUTOMATIC SMOKE DAMPER
- FSD M — COMBINATION SMOKE AND FIRE DAMPER WITH ACCESS DOOR
- R — RISE IN DUCTWORK (IN DIRECTION OF AIR FLOW)
- D — DROP IN DUCTWORK (IN DIRECTION OF AIR FLOW)
- CENTERLINE
- OR CFM — CUBIC FEET PER MINUTE
- Ø — DIAMETER
- SQUARE FEET
- OVAL DUCTWORK
- TYPE A CEILING DIFFUSER 400 CFM SUPPLY AIR
- 12x12 CD 400 — RECTANGULAR CEILING DIFFUSER WITH 12"x12" NECK 400 CFM SUPPLY AIR
- 10x8 CR(CG) 300 — 10" BY 8" CEILING REGISTER (CEILING GRILLE) 300 CFM RETURN AIR
- RECTANGULAR DIFFUSER WITH BLANKING PLATE
- 10x8 TR 150 — 10" BY 6" TOP REGISTER, 150 CFM SUPPLY AIR
- 10x8 TR(TG) 150 — 10" BY 6" TOP REGISTER (TOP GRILLE) 150 CFM RETURN AIR
- 10x8 BR(BG) 150 — 10" BY 6" BOTTOM REGISTER (BOTTOM GRILLE) 150 CFM RETURN AIR
- VANED ELBOW (SEE DETAIL)
- VANED ELBOW (SEE DETAIL) OR RADIUS ELBOW
- FLEXIBLE DUCT
- SLOTTED LINEAR DIFFUSER WITH PLENUM
- DUCT FLEXIBLE CONNECTION
- VERTICAL DUCT DROP (IN DIRECTION OF AIR FLOW)
- VERTICAL DUCT RISE (IN DIRECTION OF AIR FLOW)
- VAV-A — VARIABLE AIR VOLUME BOX TYPE A
- VAV-A — VARIABLE AIR VOLUME BOX, TYPE A, WITH REHEAT COIL
- VAV-A — VARIABLE AIR VOLUME BOX, TYPE A, WITH SOUND ATTENUATOR AND REHEAT COIL
- T — THERMOSTAT
- H — HUMIDISTAT
- SD — SMOKE DETECTOR
- H — HUMIDIFIER
- UC — RISE IN DUCTWORK (IN DIRECTION OF AIR FLOW)

HVAC PIPING

- NEW PIPE WITH DIRECTION OF FLOW
- EXISTING PIPING
- EXISTING PIPING TO BE REMOVED
- EXISTING PIPING TO BE ABANDONED
- PIPE DROP
- PIPE RISE
- U — PITCH UP IN DIRECTION OF FLOW
- D — PITCH DOWN IN DIRECTION OF FLOW
- UNION
- CONCENTRIC REDUCER
- ECCENTRIC REDUCER - FLAT BOTTOM
- ECCENTRIC REDUCER - FLAT TOP
- FLANGED CONNECTION
- FLANGED END - BLIND FLANGE
- EXPANSION LOOP
- PIPE EXPANSION JOINT
- BALL JOINT
- PIPE ALIGNMENT GUIDE
- PIPE ANCHOR
- GATE VALVE
- ANGLE GATE VALVE
- GLOBE VALVE
- ANGLE GLOBE VALVE
- NEEDLE VALVE COCK
- DRAIN VALVE
- LOCK SHIELD VALVE
- CHECK VALVE, SWING OR LIFT
- SILENT CHECK (NON-SLAM) VALVE
- FLEXIBLE CONNECTOR
- BUTTERFLY VALVE
- BALL VALVE
- SQUARE HEAD COCK
- BALANCING VALVE
- PLUG VALVE (TYPE AS NOTED)
- AUTOMATIC CONTROL VALVE
- THREE-WAY AUTOMATIC CONTROL VALVE
- "Y" TYPE STRAINER WITH BLOWOFF VALVE AND CAP
- THERMOMETER AND WELL
- PRESSURE GAUGE WITH SYPHON
- PUMP
- CWR — CONDENSER WATER RETURN
- CWS — CONDENSER WATER SUPPLY
- CHWR — CHILLED WATER RETURN
- CHWS — CHILLED WATER SUPPLY
- HWR — HOT WATER RETURN
- HWS — HOT WATER SUPPLY
- DW — DOMESTIC WATER
- D — DRAIN

HVAC GENERAL

- POINT OF CONNECTION
- POINT OF DISCONNECTION
- DDCP — DIRECT DIGITAL CONTROL PANEL
- NEW STEEL CUT
- EXISTING STEEL CUT
- SECTION DESIGNATION — SHEET No. WHERE SECTION IS SHOWN
- SECTION DESIGNATION — SHEET No. WHERE SECTION IS SHOWN

HVAC EQUIPMENT DESIGNATIONS

XXX-XX-XX
- EQUIPMENT TAG NUMBER
- FLOOR DESIGNATION
- EQUIPMENT DESIGNATION

ACU-2-3
- UNIT NUMBER 3
- SECOND FLOOR
- AIR CONDITIONING UNIT

1
- TERMINAL UNIT EQUIPMENT TAG

BOX ID
- UNIT ID

MAX CFM
- MAXIMUM AIRFLOW SETPOINT

MIN CFM
- MINIMUM AIRFLOW SETPOINT

GPM
- REHEAT COIL FLOW

SIZE
- UNIT DESIGNATION (SEE SCHEDULE)

MECHANICAL ABBREVIATIONS

A	AMPERES
AAV	AUTOMATIC AIR VENT
AC	AIR CONDITIONING
ACCU	AIR COOLED CONDENSING UNIT
ACS	AUTOMATIC CONTROL SYSTEM
ACU	AIR CONDITIONING UNIT
AD	ACCESS DOOR
AF	AFTER FILTER
AFDW	AIR FOIL DOUBLE WIDTH
AFF	ABOVE FINISHED FLOOR
AFMS	AIR FLOW MONITORING STATION
AFSW	AIR FOIL SINGLE WIDTH
AHU	AIR HANDLING UNIT
AL	ALUMINUM
AMCS	AUTOMATED MONITORING AND CONTROL SYSTEM
AP	ACCESS PANEL
BAD	BOTTOM ANGULAR DISCHARGE
BD	BLOWDOWN
BF	BOOSTER FAN
BFP	BOTTOM GRILLE
BG	BOILER FEED PUMP
BHD	BOTTOM HORIZONTAL DISCHARGE
BHP	BRAKE HORSEPOWER
BIDW	BACKWARD INCLINE DOUBLE WIDTH
BISW	BACKWARD INCLUDE SINGLE WIDTH
BMS	BUILDING MANAGEMENT SYSTEM
BR	BOTTOM REGISTER
BT	BOTTOM THROAT
BTU	BRITISH THERMAL UNIT
BTUH	BTU PER HOUR
C	CONVERTOR
CAC	CONTROL AIR COMPRESSOR
CC	COOLING COIL
CCP	CENTRAL CONTROL PANEL
CCW	COUNTER CLOCKWISE
CD	CEILING DIFFUSER
CFFC	CAP FOR FUTURE CONNECTION
CFM	CUBIC FEET PER MINUTE
CFP	CHEMICAL FEED PUMP
CG	CEILING GRILLE
CH	CHILLER
CHWP	CHILLED WATER PUMP
CLG	CEILING
COD	CLEAN-OUT DOOR
COMPR	COMPRESSOR
COND	CONDENSATE
COV	CHAIR OPERATED VALVE
CP	CONDENSATE PUMP
CPA	CONTROL POINT ADJUSTMENT
CPU	CONDENSATE PUMP UNIT
CR	CEILING REGISTER
CT	COOLING TOWER
CU FT	CUBIC FEET
CU IN	CUBIC INCHES
CUH	CABINET UNIT HEATER
CV	CONSTANT VOLUME
CW	CLOCKWISE
CWP	CONDENSER WATER PUMP
°C	DEGREES CENTIGRADE (CELSIUS)
D	DROP
DB	DRY BULB
DBD	DOWN BLAST DISCHARGE
DF	DUCT FURNACE UNIT
DFWP	DEARATOR FEED WATER PUMP
DG	DIESEL GENERATOR
DHW	DOMESTIC HOTER WATER
DMPR	DAMPER
DN	DOWN
DOP	DIESEL OIL PUMP
DWG	DRAWING
DX	DIRECT EXPANSION
ø,DIAM	DIAMETER
(E)	EXISTING TO REMAIN
(ER)	EXISTING TO BE REMOVED
(ERR)	EXISTING TO BE REMOVED & RELOCATED
EA	EACH
EAT	ENTERING AIR TEMPERATURE
EDB	ENTERING DRY BULB TEMPERATURE
EDH	ELECTRIC DUCT HEATER
EDR	EQUIVALENT DIRECT RADIATION
EF	EXHAUST FAN
EL	ELEVATION
ELEC	ELECTRIC
ELEV	ELEVATOR
EQ	EQUAL
ET	EXPANSION TANK
EUH	ELECTRIC UNIT HEATER
EWB	ENTERING WET BULB
EWT	ENTERING WET TEMPERATURE
EXH	EXHUAST
EXIST	EXISTING
EXP	EXPANSION
F	FILTER
F&T	FLOAT AND THERMOSTATIC
FA	FREE AREA (SQ.FT.)
FC	FLEXIBLE CONNECTION
FCDW	FORWARD CURVED DOUBLE WIDTH
FCSW	FORWARD CURVED SINGLE WIDTH
FCU	FAN COIL UNIT
FD	FIRE DAMPER
FF	FINAL FILTER
FG	FINISHED GRADE
FIN FL	FINISHED FLOOR
FLA	FULL LOAD AMPERES
FOP	FUEL OIL PUMP
FOT	FUEL COIL TANK
FPI	FINS PER INCH
FPM	FEET PER MINUTE
FPS	FEET PER SECOND
FR	FLOOR REGISTER
FT	FEET
FTR	FINNED TUBE RADIATION
FV	FACE VELOCITY
FX	FUME HOOD EXHAUST
°F	DEGREES FAHRENHEIT
G	GAUGE
GAL	GALLON
GPH	GALLONS PER HOUR
GPM	GALLONS PER MINUTE
GX	GENERAL EXHUAST
H	HUMIDIFIER
HALX	HALON EXHAUST
HC	HEATING COIL
HD	HEAD
HR	HOUR
HRC	HEAT RECOVERY COIL
HT	HEIGHT
HTWP	HIGH TEMPERATURE WATER PUMP
HV	HEATING AND VENTILATING
HWP	HOT WATER PUMP
HX	HEAT EXCHANGER
HZ	FREQUENCE
IN	INCH OR INCHES
IPS	IRON PIPE SIZE
KW	KILOWATT
KX	KITCHEN RANGE HOOD EXHAUST
L	LENGTH
LAT	LEAVING AIRE TEMPERATURE
LBS	POUNDS
LCP	LOCAL CONTROL PANEL
LD	LINEAR DIFFUSER
LDB	LEAVING DRY BULB TEMPERATURE
LF, LIN.FT.	LINEAR FEET
LR	LINEAR RETURN
LRA	LOCKED ROTOR AMPS
LV	LOW VELOCITY
LWB	LEAVING WET BULB TEMPERATURE
LWT	LEAVING WATER TEMPERATURE
MAV	MANUAL AIR VENT
MAX	MAXIMUM
MB	MIXING BOX
MBH	THOUSAND BTU PER HOUR
MCC	MOTOR CONTROL CENTER
MER	MECHANICAL EQUIPMENT ROOM
MHP	MOTOR HORSEPOWER
MIN	MINIMUM
MM	MILLIMETER
MOT	MOTOR
MOV	MOTOR OPERATED VALVE
MX	MECHANICAL ROOM EXHAUST
N.O.	NORMALLY OPEN
NC	NORMALLY CLOSED
NIC	NOT IN CONTRACT
NO.	NUMBER
NPSH	NET POSITIVE SUCTION HEAD
NTS	NOT TO SCALE
OA	OUTSIDE AIR
OAI	OUTSIDE AIR INTAKE
OD	OUTSIDE DIAMETER
OED	OPEN END DUCT
OV	OUTLET VELOCITY
P	PUMP
PCC	PRE-COOLING COIL
PD	PRESSURE DROP
PF	PRE-FILTER
PHC	PREHEAT COIL
PRV	PRESSURE REDUCING VALVE
PSI	POUNDS PER SQUARE INCH
PSIA	PSI ABSOLUTE
PSIG	PSI GAUGE
(RE)	RELOCATED EXISTING
(RRO)	EXISTING TO REMOVED AND RETURN TO OWNER
R	RISE
RA	RETURN AIR
RAD	RADIATION
RCC	RECOOLING COIL
REFR	REFRIGERANT
RF	RETURN FAN
RH	RELATIVE HUMIDITY
RHC	REHEAT COIL
RHWP	REHEAT WATER PUMP
RLA	RUNNING LOAD AMPS
RM	ROOM
ROT	ROTATION
RPM	REVOLUTIONS PER MINUTE
SA	SUPPLY AIR
SAU	SOUND ATTENUATION UNIT
SCHWP	SECONDARY CHILLED WATER PUMP
SD	SMOKE DETECTOR
SF	SUPPLY FAN
SHWP	SECONDARY HOT WATER PUMP
SLD	STRIPLINE DIFFUSER
SMK.CTL.	SMOKE CONTROL OPERATION
SP	STATIC PRESSURE
SPEC	SPECIFICATION
SQ.FT.	SQUARE FEET
SS	STAINLESS STEEL
SX	SMOKE EXHAUST
T	THROAT
TAD	TOP ANGULAR DISCHARGE
TDH	TOTAL DYNAMIC HEAD
TEMP	TEMPERATURE
TF	TERMINAL FILTER
TG	TOP GRILLE
THD	TOP HORIZONTAL DISCHARGE
TR	TOP REGISTER
TRD	TRANSFER DUCT
TRF	TRANSFER FAN
TRG	TRANSFER GRILLE
TS	TIP SPEED
TT	TOP THROAT
TV	TURNING VANES
TX	TOILET EXHAUST
TYP	TYPICAL
UBD	UPBLAST DISCHARGE
UH	UNIT HEATER
UON	UNLESS OTHERWISE NOTED
V	VOLTS
VA	VENTILATION AIR
VAC	VACUUM
VAV	VARIABLE AIR VOLUME UNIT
VF	VENTILATION FAN
VFD	VARIABLE FREQUENCY DRIVE
VIV	VARIABLE INLET VANES
VP	VACUUM PUMP
W	WIDTH
W/	WITH
W/O	WITHOUT
WB	WET BULB
WC	WATER COLUMN
WG	WATER GAUGE
WMS	WIRE MESH SCREEN
WP	WORKING PRESSURE
WSP	WORKING STEAM PRESSURE

MECHANICAL DEMOLITION NOTES

1. ALL PIPING IN WALLS AND FLOORS NOT TO BE REUSED WILL BE PLUGGED OR CAPPED AND CUTTING AND PATCHING WILL BE PERFORMED TO RESTORE SURFACE TO ORIGINAL CONDITION BY THIS CONTRACTOR.
2. AFTER REMOVING PIPE THROUGH THE FLOOR SLABS, PACK OPENING WITH APPROVED FIRE-RATED PACKING.
3. THE CONTRACTOR SHALL INCLUDE IN HIS PRICE ALL COSTS ASSOCIATED WITH REMOVALS AND RELOCATIONS OF HVAC WORK AS DESCRIBED ON THE DRAWINGS AND IN THE SPECIFICATIONS WITH ALLOWANCES FOR EXPECTED OR UNFORESEEN DIFFICULTIES WHEN CONCEALED WORK HAS BEEN OPENED. NO CLAIMS FOR ADDITIONAL WORK ASSOCIATED WITH DEMOLITION WILL BE ACCEPTED, EXCEPT IN CERTAIN CASES CONSIDERED JUSTIFIABLE BY THE OWNER/ENGINEER.
4. THE CONTRACTOR SHALL PERFORM DEMOLITION AND REMOVAL WORK WITH MINIMUM INTERFERENCE WITH FUNCTIONING HVAC SYSTEMS. ALL AFFECTED SYSTEMS SHALL BE RECONNECTED AND RESTORED.
5. DEMOLITION AND REMOVAL WORK SHALL BE PERFORMED IN A NEAT AND WORKMANLIKE MANNER. THE CONTRACTOR SHALL PATCH, REPAIR OR OTHERWISE RESTORE ANY DAMAGED INTERIOR OR EXTERIOR BUILDING SURFACE TO ITS ORIGINAL CONDITION.
6. THE CONTRACTOR SHALL REMOVE ALL DUCT & PIPING SUPPORTS, ETC. FROM PARTITIONS THAT ARE TO BE REMOVED. WHERE THE REMOVAL OF THESE ITEMS DISRUPTS EXISTING PIPING THAT IS TO REMAIN, THE CONTRACTOR SHALL INSTALL AND PROVIDE BYPASS CONNECTIONS NECESSARY.
7. ALL PIPING WHICH BECOMES EXPOSED DURING THE ALTERATION WORK SHALL BE REMOVED AND REROUTED CONCEALED BEHIND FINISHED SURFACES.
8. PORTIONS OF PIPING & DUCTWORK TO BE REMOVED OR ABANDONED AS A RESULT OF DEMOLITION WORK, BUT WHICH ARE REQUIRED TO REMAIN ACTIVE, SHALL BE CUT AT CONVENIENT LOCATIONS, REROUTED AND RECONNECTED.
9. THE CONTRACTOR SHALL NOTIFY THE OWNER AT THE APPROPRIATE TIME OF THE PROJECTED DEMOLITION AND PHASING SCHEDULE SO THAT REMOVAL OR RELOCATION OF AFFECTED UTILITIES MAY BE CARRIED OUT IN COORDINATION WITH THE PROJECT REQUIREMENTS.
10. ALL EXISTING MATERIAL AND EQUIPMENT IN USABLE CONDITION, WHICH IS TO BE REMOVED UNDER THIS CONTRACT, SHALL REMAIN THE PROPERTY OF THE OWNER OR SHALL BE DISPOSED OF BY THE HVAC CONTRACTOR, AS DIRECTED BY THE OWNER.
11. ARRANGE TO WORK CONTINUOUSLY, INCLUDING OVER TIME, IF REQUIRED, TO ASSURE THAT SYSTEMS WILL BE SHUT DOWN ONLY DURING THE TIME ACTUALLY REQUIRED TO MAKE THE NECESSARY CONNECTIONS TO THE EXISTING SYSTEMS.
12. THE SHUTDOWN OF EXISTING BUILDING HVAC SERVICES SHALL BE COORDINATED WITH THE OWNER. MAKE ARRANGEMENTS AT LEAST 5 BUSINESS DAYS PRIOR TO A SHUTDOWN.

1.3 CONTRACTOR SHALL COMPLY WITH ALL FEDERAL STATE & LOCAL REQUIREMENTS REGARDING DISPOSAL OF REFRIGERANTS.

MECHANICAL GENERAL NOTES

1. GENERAL NOTES, SYMBOL LIST AND DETAILS ARE APPLICABLE TO ALL HVAC/MECHANICAL DRAWINGS.
2. ALL WORK IS NEW UNLESS OTHERWISE NOTED.
3. DRAWINGS ARE DIAGRAMMATIC. DETERMINE LOCATIONS OF SYSTEMS AND COMPONENTS IN FIELD. RELOCATE EXISTING WORK THAT INTERFERES WITH WORK OF THIS CONTRACT.
4. COORDINATE THIS WORK WITH THAT OF OTHER TRADES.
5. DIMENSIONS SHOWN ON PLAN ARE HORIZONTAL. DIMENSIONS SHOWN IN ELEVATION ARE VERTICAL EXCEPT IN WAY OF STRUCTURAL STEEL, DIMENSIONS ARE MEASURED PERPENDICULAR TO FLANGE.
6. NEITHER ACCURACY NOR COMPLETION OF SERVICES AND UTILITY LOCATIONS SHOWN ON DRAWINGS IS GUARANTEED. DETERMINE EXACT LOCATIONS OF EXISTING SERVICES AND UTILITIES IN FIELD, WHETHER OR NOT SHOWN ON DRAWINGS. EXERCISE CAUTION AND IDENTIFY LOCATIONS OF UNMARKED UTILITY LINES AS NECESSARY TO PERFORM WORK OF THIS SECTION.
7. MANUFACTURERS MODEL NUMBERS ARE SPECIFIED SOLELY TO ESTABLISH STANDARDS OF QUALITY FOR PERFORMANCE AND MATERIALS.
8. PRODUCT INSTALLATION SHALL ADHERE TO MANUFACTURERS RECOMMENDATIONS.
9. PROVIDE ACCESS PANELS FOR EQUIPMENT THAT REQUIRES PERIODIC SERVICE.
10. PROVIDE HANGERS, INSERTS, ANCHORS, SUPPLEMENTAL STEEL & SUPPORTS AS REQUIRED TO SUPPORT DUCTWORK, PIPING AND EQUIPMENT FROM STRUCTURE.
11. SCHEDULE WORK OF THIS SECTION TO AVOID INTERFERING WITH EXISTING OPERATIONS IN THE FACILITY.
12. COORDINATE ROOF PENETRATIONS WITH WORK OF OTHER SECTIONS AND WITH FLASHING REQUIREMENTS. MECHANICAL CONTRACTOR TO NOTIFY OWNER PRIOR TO STARTING WORK TO VERIFY COMPLIANCE WITH BOND AND WARRANTY OF EXISTING ROOF.
13. RUN DUCTS AND PIPING CONCEALED, UNLESS OTHERWISE SPECIFIED AND CLEAR OF CEILING INSERTS.
14. INSTALL THERMOSTATS 4'-6" ABOVE FINISHED FLOOR OR AS DIRECTED OTHERWISE BY ARCHITECT.
15. STRUCTURAL WELDING SHALL BE CONTINUOUS 1/4" FILLET UNLESS REQUIRED OTHERWISE.

AIR SYSTEMS

16. AIR SYSTEMS REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR EXACT LOCATIONS OF AIR DEVICES.
17. INTERNAL AIRFLOW DIMENSIONS ARE SHOWN FOR DUCTS. INCREASE DUCT SIZE AS NECESSARY TO MAINTAIN FREE FLOW AREA INDICATED.
18. USE FLAT TRANSVERSE SEAM FOR DUCTWORK WHERE SPACE AVAILABLE DICTATES.
19. DIFFUSER SIZES SHOWN ARE NECK SIZES. REGISTERS AND GRILLE SIZES ARE NOMINAL.
20. PROVIDE VOLUME DAMPERS OR OTHER APPROVED BALANCING DEVICES AT DUCT BRANCHES AND RUN OUTS, AND AT REGISTER GRILLE AND DIFFUSER NECKS IN SUPPLY, RETURN AND EXHAUST DUCTWORK WHETHER SHOWN OR NOT.
21. PROVIDE 36" CLEARANCE IN FRONT OF ALL ELECTRIC CONTROL PANELS PER N.E.C. AND MFG. REQUIREMENTS.
22. PROVIDE DUCT TRANSITIONS FROM VAV BOX INLET/OUTLET DUCT WORK AT SIZES INDICATED TO VAV BOX INLET/OUTLET UNIT CONNECTIONS.
23. VAV DUCT INLET SIZE SHALL BE AS SCHEDULED OR AS INDICATED ON THE FLOOR PLANS. PROVIDE TRANSITION FROM DUCT SIZE INDICATED ON THE FLOOR PLANS TO SCHEDULED SIZE MINIMUM 2'-0" FROM VAV BOX INLETS.

PIPING SYSTEMS

24. PITCH PIPING 1" IN 20' IN DIRECTION OF FLOW.
25. PROVIDE TRAPS IN CONDENSATE LINES THAT EXTEND OVER 2".

MECHANICAL DRAWING LIST

DRAWING No.	DRAWING TITLE
M00-01	MECHANICAL COVER SHEET
M01-0B	MECHANICAL BASEMENT DUCTWORK DEMOLITION PLAN
M02-0B	MECHANICAL BASEMENT PIPING DEMOLITION PLAN
M03-0B	MECHANICAL BASEMENT DUCTWORK PLAN
M04-0B	MECHANICAL BASEMENT PIPING PLAN
M04-02	MECHANICAL LEVEL 2 PIPING PLAN
M05-00	MECHANICAL DETAILS
M06-00	MECHANICAL SCHEDULES

Reviewed for Code Compliance
Portland Fire Prevention Division
Approved with Conditions
Date: 10/16/15

Perkins+Will
225 Franklin St., Suite 1100
Boston, MA 02110
t 617.478.0300
f 617.478.0321
www.perkinswill.com

Maine Medical Center
MaineHealth

HYBRID OR & OR #6

22 Bramhall Street, Portland, Maine 04102

MEP ENGINEER

AKF GROUP, LLC

99 Bedford Street, 2nd Floor
Boston, MA 02111
t 617.737.1111
f 617.737.4311

STRUCTURAL ENGINEER

SIMPSON GUMPERTZ & HEGER

41 Seyon Street, Building 1, Suite 500
Waltham, MA 02453
t 781.907.9000
f 781.907.9009

D C A B

STATE OF MAINE — DAVID P. RAMEY — No. 7858 — LICENSED PROFESSIONAL ENGINEER

Revisions

	ISSUED FOR PERMIT	08.21.2015
1	ADDENDUM 1	08.21.2015
NO	ISSUE	DATE

Sheet Information

Date	JULY 31, 2015
Job #	B150155-000
Drawn	TU
Checked	DPR
Approved	DPR

Title

MECHANICAL COVER SHEET

Sheet

M00-01

Copyright © 2014 Perkins+Will

8/21/2015 1:02:34 PM
C:\Revit Local Files\B150155-000 - MMC NEW HYBRID OR - MEP14_Central_tusatin.rvt