



GROUND FLOOR PART PLAN
1/2"=1'-0"




KEY PLAN GROUND FLOOR



SECTION
3/4"=1'-0" AA S1

CONSTRUCTION SEQUENCE NOTES

1. INSTALL TEMPORARY JACKING/SHORING TO UNDERSIDE OF EXISTING W BEAM. (ENGAGE JACKS TIGHT TO BEAM).
2. REMOVE EXISTING BOLTS AT COLUMN SUPPORT.
3. INCREASE JACKING/SHORING SUCH THAT BEAM ENDS ARE 1/8" ABOVE COLUMN. MANIFOLD JACKS TOGETHER TO ENSURE JACKS ARE LIFTING WITH EQUAL LOAD & PISTON PRESSURE. APPROXIMATE LOAD PER JACK= 7,500 LBS. OVERSIZE JACKS BY A MINIMUM FACTOR OF 2.0 TO ENSURE JACKS HAVE SUFFICIENT CAPACITY.
4. LOCK JACKS OR SHIM EXISTING STEEL BEAMS TIGHT TO SHORING.
5. REMOVE EXISTING COLUMN AND WEB CONNECTION.
6. INSTALL REINFORCING STEEL PER STRUCTURAL DRAWINGS.
7. REMOVE JACKING/SHORING.



TYP CHANNEL SPLICE DETAIL
N.T.S.

NOT FOR CONSTRUCTION
PRELIMINARY PRICING 01-13-17
THESE DWGS ARE NOT COMPLETE.
DESIGN IS STILL IN PROGRESS.
CONTRACTOR SHALL CARRY
APPROPRIATE CONTINGENCY.

THIS DRAWING IS AN INSTRUMENT OF SERVICE AND SHALL REMAIN THE PROPERTY OF BECKER STRUCTURAL ENGINEERS INC. IT SHALL NOT BE REPRODUCED, COPIED, LENT, OR DISPOSED OF DIRECTLY OR INDIRECTLY FOR ANY PURPOSE OTHER THAN FOR WHICH IT IS SPECIFICALLY FURNISHED AND MUST BE RETURNED TO BECKER STRUCTURAL ENGINEERS INC. ON COMPLETION OF WORK, IF REQUESTED.

BECKER
STRUCTURAL ENGINEERS
75 Nash Street, Portland, Maine 04101
207.875.8538 • beckerstructural.com

Appr'd	
Issued For	
Date	
Rev. No	

MAINE MEDICAL CENTER MORGUE
22 BRAMHALL STREET, PORTLAND, ME
COLUMN REMOVAL PLANS & DETAILS

Designed	MDP	Scale	AS NOTED
Drawn	WBH	Date	01-13-17
Checked	MDP	Becker Job Number	3989

S1