

The Contractor shall replace the existing interior wooden entrance door to the Security Dispatch Center with a new commercial grade steel entrance door.
The entrance door shall be a minimum of 1.75" thick inclusive of steel cladding and interior filling and have a minimum of three (3) 4" hinges. The door frame shall be securely bolted or screwed to the wall at least every 24" around the entire frame. The door shall have an integral security lip to overlap the gap between the leading edge of the door and the door frame. The door shall be equipped with an internal auto door closer. **The door shall have an integrated bullet resistant transaction type window equipped with a talk thru speaker. The door is 3/0 x 7/0**

1. The existing window that was originally in the narrative to be removed will remain in place per MMC. MMC will apply a ballistic film on the interior of the existing windows in the Security Dispatch Office as opposed to infilling it.

