

WATERTIGHT BOXES WITH CURBS - 5' X 5' BOXES, CURB EPDM TO OVERLAP TOP OF ROOF BLOCKING ONTO VERTICAL INSIDE FACE AND TIE INTO EPDM ROOFING ON OUTSIDE OF BOX




ALL BOXES TO BE FIGURED AS 5'X5' CLEAR OPEN TO CONCRETE SLAB

SCOPE NARRATIVE - TEMPORARY ROOF WORK:

- 1.) LOAD ROOF WITH MATERIAL AND MAKE SAFE WITH FLAGGING SYSTEM AND FALL PROTECTION SYSTEMS.
- 2.) ROOFER REMOVES ROOFING (APPROX. 6' X 6' SQUARES) DOWN TO CONCRETE SLAB.
- 3.) CARPENTERS FASTEN DOWN PRE-FABRICATED WOOD CURBS TO SLAB AS SHOWN ON DETAIL IN BLUE ON THIS PAGE.
- 4.) ROOFER TO USE EXISTING EPDM AS WELL AS NEW STRIP SHEETS TO FLASH WOOD CURBS AND TERMINATE EPDM ON INSIDE OF CURBS.
- 5.) ROOFER TO WRAP BOX OUT WOOD CAPS (2x4 LUMBER FRAME WITH PLYWOOD TOP) WITH EPDM.
- 6.) CARPENTER TO PLACE WATERTIGHT CAPS OVER WATERTIGHT CURBS - CAP COVERS COMES DOWN AROUND CURB AND WILL GET MECHANICALLY FASTENED TO CURB HORIZONTALLY THROUGH CAP BORDER FRAME.
- 7.) ITEMS REMAIN COVERED AS SHOWN ON PICTURE ON LEFT UNTIL EAST TOWER STRUCTURAL STEEL STARTS ON-SITE.

Turner temp. fieldwork sketch TPSK-001



SIMILAR TO RED / BLUE DETAIL, BUT ROOF EDGE CONDITION ON 2 SIDES INSTEAD OF JUST 1

SIMILAR TO RED / BLUE DETAIL, BUT ROOF EDGE CONDITION ON 2 SIDES INSTEAD OF JUST 1


SIMILAR TO RED / BLUE DETAIL, BUT ROOF EDGE CONDITION ON 2 SIDES INSTEAD OF JUST 1

WILLIAM A. BERRY & SON, INC.
REVIEWED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
THE SUBCONTRACTOR / VENDOR IS RESPONSIBLE FOR ALL DIMENSIONS, CORRECT FIT AND COORDINATION OF ALL ITEMS TO BE FURNISHED & INSTALLED.
BY: *WAB* DATE: 12/20/06
JOB # 04-310-0 JOB NAME: MAC-CHARLES ST.
SUBMISSION # 05121-018-2
SPEC. OR REF. REF.
REVIEWED FOR CONSTRUCTABILITY

RECEIVED
DEC 28 2006
Simpson Gumpertz & Heger Consulting Engineers Inc.
REVISED ERECTION
FOR APPROVAL DEC 13 2006
DEC 15 2006

NOVEL IRON WORKS
250 Ocean Road
Greenland, NH 03840

No.	Date	Description	Revised	By	Checked
1	31-07-06	UPDATED TO SUIT APPROVAL			
2	12-10-06	ROOF FRAMES LOCATED			



SIMILAR TO RED / BLUE DETAIL, BUT ROOF EDGE CONDITION ON 2 SIDES INSTEAD OF JUST 1

SIMILAR TO RED / BLUE DETAIL, BUT ROOF EDGE CONDITION ON 2 SIDES INSTEAD OF JUST 1