



6th Floor/Roof Framing Plan

- Top Of Steel EL 227'-11 3/4 u/n
- ◀ Indicates Seismic Moment Connection - 1" Dia A490C Bolts
- Indicates Non Seismic Moment Connection - 3/4" Dia A325SC Bolts
- ⊗ Indicates 1" Dia A490 Bolts

APPROVED NOT APPROVED
 REVISE AND RESUBMIT
 RESUBMIT FOR RECORD COPY
 Checking is only for conformance with the design concept of the project and compliance with the information given in the Contract Documents. Contractor is responsible for dimensions to be confirmed and correlated at the job site; for information that pertains solely to the fabrication processes or to techniques of construction; and for coordination of the work of all trades.
 BY: *M. J. B. [Signature]*
 DATE: **30 Oct 06**
 SIMPSON GUMPERTZ & HEGER INC
 41 SEYON ST., BUILDING 1, SUITE 500
 WALTHAM, MA 02453

WILLIAM A. BERRY & SON, INC.
 REVIEWED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
 THE SUBCONTRACTOR/VENDOR IS RESPONSIBLE FOR ALL DIMENSIONS, CORRECT FIT AND COORDINATION OF ALL ITEMS TO BE FURNISHED & INSTALLED.
 BY: *W.A.B. [Signature]* DATE: **9/28/06**
 JOB # **04-310-0** JOB NAME: **MHC-CHARLES ST.**
 SUBMISSION # **PS 120-01470**
 SPEC/DRAWING REF:
 REVIEWED FOR CONSTRUCTION

THIS DRAWING TO BE REVIEWED FOR PIECE MARKS ONLY
 Date: **SEP 21 2006**

RECEIVED

OCT 02 2006
 Simpson Gumpertz & Heger
 Consulting Engineers, Inc.

See Dwg. EB For Notes
NOVEL IRON WORKS
 250 Ocean Road
 Greenland, NH 03840

Revisions		Notes	By (uno)	Date	Checked	Category
3	31-09-06	UPDATED TO SUIT APPROVAL				III

Project	Maine Medical Center	Drawn By	AD
Description	6th Floor/Roof Framing Plan	Checked By	H.J.L.
Architect	TRD	Engineer	Simpson Gumpertz & Heger Inc.
Job No.	316	Customer	William Berry & Son Inc.
Sheet No.	E13		