

### CRITICAL ENVIRONMENT DIFFUSER

TAG	LOCATION	NOMINAL SIZE	SYSTEM TOTAL CFM	DIM(FT)	CFM	# OF SLOTS	# OF INLETS	INLET SIZE	CFM/FT	INLET LOCATION	MANUF & MODEL	QTY	CENTER DIFFUSER			NOTES:			
													W X L (IN)	CFM/180°F DIFFUSER	INLET DIA (IN)		TOTAL CFM	THROW TO 30 FPM	MANUF & MODEL
CE0-1	OR #21	8'X8'	2500	8'X8	1600	2	2	36'X8	25	4.8	TITUS STERITEC-SS	4	48X24	225	8	900	8	TITUS, TLF-SS	*

### REGISTER, DIFFUSER & GRILL SCHEDULE - GENERAL

TAG	CFM	NECK SIZE (DIA)	TYPE	ΔP	MAX NC	TYPICAL UNIT MFG & MODEL NO.	NOTES
R-1	<130	9x9 (8)	LOUVERED DIRECTIONAL RETURN DIFFUSER	0.08	15	TITUS 24X24 LAY-IN MODULE	DP 1,2
R-2	130-280	9x9 (8)	LOUVERED DIRECTIONAL RETURN DIFFUSER	0.10	20	TITUS 24X24 LAY-IN MODULE	TDCA 1,2
R-3	280-490	12X12 (10)	LOUVERED DIRECTIONAL RETURN DIFFUSER	0.13	21	TITUS 24X24 LAY-IN MODULE	TDCA 1,2
R-4	491-620	15X15	LOUVERED DIRECTIONAL RETURN DIFFUSER	0.10	25	TITUS 24X24 LAY-IN MODULE	TDCA 1,2
R-1	<140	6	PERFORATED RETURN GRILLE	0.18	18	TITUS 24X24 LAY-IN MODULE	PAR 1
R-2	140-240	8	PERFORATED RETURN GRILLE	0.19	25	TITUS 24X24 LAY-IN MODULE	PAR 1
R-3	241-390	10	PERFORATED RETURN GRILLE	0.18	30	TITUS 24X24 LAY-IN MODULE	PAR 1
R-4	391-650	14	PERFORATED RETURN GRILLE	0.18	31	TITUS 24X24 LAY-IN MODULE	PAR 1
R-5	651-950	16	PERFORATED RETURN GRILLE	0.17	32	TITUS 24X24 LAY-IN MODULE	PAR 1
R-6	959-2000	22X22	PERFORATED RETURN GRILLE	0.12	27	TITUS 24X24 LAY-IN MODULE	PAR 1
R-7	651-1200	18X18	SIDEWALL RETURN GRILLE	0.05	10	TITUS SURFACE MOUNT 355R	PAR 1
E-1	<80	6X6	LOUVERED EXHAUST GRILLE	0.05	20	TITUS SURFACE MOUNT 355R	1,3
E-2	80-150	8X8	LOUVERED EXHAUST GRILLE	0.06	20	TITUS SURFACE MOUNT 355R	1,3
E-3	150-240	10X10	LOUVERED EXHAUST GRILLE	0.15	25	TITUS SURFACE MOUNT 355R	1,3
E-4	241-500	12X12	LOUVERED EXHAUST GRILLE	0.15	25	TITUS SURFACE MOUNT 355R	1,3
E-5	401-880	16	PERFORATED EXHAUST GRILLE	0.16	28	TITUS LAY-IN MODULE	PAR 1

KEYED NOTES:  
 1. ALUMINUM CONSTRUCTION.  
 2. 4-WAY PATTERN TYPICAL.  
 3. ΔP DEFLECTION.

### TERMINAL BOX (TB) SCHEDULE

TAG	OUTLET SIZE (IN)	CFM MAX.	HOT WATER HEATING COIL			INLET STATIC PRESSURE MIN.	CFM MIN.	CFM MAX.	MBH	EAT °F	LAT °F	180°F EWT	GPM @ 180°F EWT	ROWS	TYPICAL UNIT MFG & MODEL NO.	NOTES:
			INLET SIZE (IN)	# OF SLOTS	# OF INLETS											
TB-13	10	14X12-1/2	1000	500	0.06	0.5	33.0	55	85	83.3	2	ENVIROTEC SDR-SA-WC-12	*			
TB-15	14	20X17-1/2	2500	2500	0.06	0.5	82.5	55	85	83.3	2	ENVIROTEC SDR-SA-WC-14	*			
TB-32	8	12X10	500	150	0.01	0.22	16.5	55	85	1.7	2	ENVIROTEC SDR-SA-WC-8	*			
TB-34	8	12X10	400	100	0.01	0.15	13.2	55	85	1.3	2	ENVIROTEC SDR-SA-WC-8	*			

### HUMIDIFIER DISPERSION PANEL SCHEDULE

TAG	SERVICE	OR #21	DUCT DIMENSIONS		CFM	ABSORPTION DIST. (IN)	TUBE O.C.	MAX VEL FPM	TYPICAL UNIT MFG & MODEL NO.	NOTES:
			W (IN)	H (IN)						
H-3	OR #21	54	5	20	2500	25	3"	2000	DRISTEEM ULTRASORB LH	*

### EXISTING TERMINAL BOX (TB) SCHEDULE

TAG	INLET SIZE (IN)	OUTLET SIZE (IN)	CFM MAX.	CFM MIN.	MBH	EAT °F	LAT °F	GPM @ 180°F EWT	WPD FT. HD	TYPICAL UNIT MFG & MODEL NO.	NOTES:
TB-14	6	10X6	230	7.5	65	85	0.8	0.3	N/A	N/A	1
TB-17	12	16X15	1520	61.6	65	85	5.2	10.6	N/A	N/A	1
TB-18	6	10X6	340	9.7	65	85	0.4	0.4	N/A	N/A	1
TB-19	12	16X15	1685	54.6	65	85	5.5	8.4	N/A	N/A	1
TB-33	6	10X6	285	8.2	65	75	0.6	0.3	N/A	N/A	1
TB-35	4	10X6	155	4.0	65	75	0.1	0.1	N/A	N/A	1
TB-36	10	22X10	630	20.4	65	85	2.0	1.2	N/A	N/A	1
TB-37	4	10X6	150	3.2	65	75	0.3	0.2	N/A	N/A	1
TB-39	8	14X10	625	13.5	65	75	1.4	1.3	N/A	N/A	1
TB-40	6	10X6	190	4.1	65	75	0.4	0.1	N/A	N/A	1
TB-42	8	14X10	525	13.0	65	75	0.3	0.2	N/A	N/A	1
TB-43	10	14X12-1/2	1000	25.0	8.1	85	0.8	0.8	N/A	N/A	1
TB-44	10	14X12-1/2	1000	25.0	8.1	85	0.8	0.8	N/A	N/A	1
TB-45	10	14X12-1/2	1000	25.0	8.1	85	0.8	0.8	N/A	N/A	1
TB-46	10	22X10	910	23.0	5.0	75	0.5	0.05	N/A	N/A	1
TB-47	8	14X10	460	11.5	2.5	75	0.3	0.2	N/A	N/A	1
TB-52	6	10X6	265	265	5.7	75	0.6	0.17	N/A	N/A	1

NOTES: 1. EXISTING TERMINAL BOX TO REMAIN. CONTRACTOR SHALL PROVIDE ALL NEW CONTROL HARDWARE. CALIBRATE AND BALANCE TO PERFORMANCE INDICATED. TIE IN TO EXISTING HONEYWELL FRONT END SYSTEM.

### AUTOMATIC TEMPERATURE CONTROLS

GENERAL SCOPE OF THE CONTROL WORK

- THE TEMPERATURE CONTROL WORK ON THE PROJECT SHALL BE AN EXTENSION OF THE EXISTING HONEYWELL DDC SYSTEM.
- PROVIDE NEW CONTROLS INCLUDING CONTROL VALVES, DAMPER ACTUATORS, AND SPACE TEMPERATURE SENSORS ON ALL NEW AND EXISTING VAV (TB) TERMINAL BOXES ON AHU-64 AIR HANDLING SYSTEM ON BEAN BUILDING, SECOND FLOOR.
- PROVIDE NEW CONTROLS INCLUDING CONTROL VALVES, DAMPER ACTUATORS, SPACE TEMPERATURE SENSORS, HUMIDITY, AND PRESSURE INDICATING SENSORS ON ALL OPERATING ROOMS (OR'S) #21-23.
- PROVIDE TEMPERATURE SENSORS, HUMIDITY SENSORS, AND PRESSURE SENSORS WHERE INDICATED OR AS REQUIRED TO MEET THE SEQUENCES.

GENERAL SYSTEM STARTUP:

- THE MECHANICAL AND PLUMBING SYSTEMS, INCLUDING THE HUMIDIFIERS, VAV TERMINALS, AND TERMINAL EQUIPMENT, SHALL BE CYCLED THROUGH THE ACTION OF THE DDC SYSTEM AS DESCRIBED HEREIN. SUBMIT PROPOSED SEQUENCE OF OPERATION, POINTS LIST AND SCHEMATIC DIAGRAM FOR EQUIPMENT NOT INCLUDED IN THOSE SEQUENCES OF OPERATIONS.

### SEQUENCES OF OPERATION

VAV BOX W/ HOT WATER REHEAT AND/OR HOT WATER RADIATION:

- WHEN THE RESPECTIVE SINGLE SENSOR ZONES SHALL BE CONTROLLED FROM SENSORS AS SHOWN ON THE "M" DRAWINGS. ZONE SENSORS SHALL HAVE THE CAPABILITY OF EITHER AN AVERAGE SENSOR INPUT OR ANY ONE INDIVIDUAL SENSOR INPUT. PROGRAMMING SHALL BE FULL AVERAGED INPUT. THE VARIABLE VOLUME TERMINAL BOX (TB) IS CONTROLLED INDEPENDENT OF SYSTEM PRESSURE FLUCTUATIONS.
- OCCUPIED ZONE CONTROL: THE VAV IS CONTROLLED BETWEEN MAXIMUM AND MINIMUM SUPPLY AIR VOLUME SETTINGS. THE CONTROLLER MONITORS THE ROOM TEMPERATURE SENSOR AND AIR VELOCITY SENSOR AND MODULATES THE SUPPLY AIR DAMPER IN SEQUENCE WITH THE REHEAT VALVE AND RADIATION VALVE TO MAINTAIN THE ROOM TEMPERATURE AT SETPOINT.
- HEATING MODE: ON THE ZONE HEATING MODE IS DEFINED AS ANY SENSED TEMPERATURE LESS THAN 1 DEGREE BELOW SETPOINT. IN HEATING MODE, THE FINNED TUBE RADIATION WILL MODULE BASED ON THE OUTSIDE AIR REHEAT SCHEDULE. THE VAV TERMINAL SHALL MODULATE TO MINIMUM ABOVE THE REHEAT VALVES SHALL MODULATE TO MAINTAIN SPACE SETPOINT.
- COOLING MODE: THE ZONE COOLING MODE IS DEFINED AS ANY SENSED TEMPERATURE GREATER THAN 1 DEGREE ABOVE SETPOINT. IN COOLING MODE, THE RADIATION SHALL BE UNOCCUPIED ZONE CONTROL. THE VAV TERMINAL AND REHEAT VALVE SHALL MODULATE TO MAINTAIN SPACE SETPOINT.
- UNOCCUPIED ZONE CONTROL: THE TERMINAL UNITS SHALL BE CONTROLLED SAME AS OCCUPIED MODE USING THE NIGHT SETPOINT. THE UNOCCUPIED TIMES IN THESE ZONES SHALL BE SCHEDULED THROUGH THE BUILDING AUTOMATION SYSTEM. THE ZONE MAY RESET TO THE OCCUPIED MODE FOR A PREDETERMINED TIME PERIOD UPON A SIGNAL FROM THE CONTROL SYSTEM.


HUMIDITY CONTROL (H-3, OR#21, H-4(E), OR#22, AND H-5(E), OR#23):

- WHEN THE RESPECTIVE AIR HANDLING UNIT IS OPERATING, THE ZONE HUMIDIFIER VALVES MODULATE TO MAINTAIN THE SPACE HUMIDITY SETPOINT.
  - HUMIDIFIER VALVE MODULATES CLOSED IF SUPPLY AIR HUMIDITY LEVELS EXCEED SETPOINT.
  - A DUCT MOUNTED HIGH LIMIT HUMIDISTAT LOCATED 15 FT DOWNSTREAM OF THE HUMIDIFIER PANEL SHALL CLOSE THE VALVE.
  - AN AIRFLOW PROVING SWITCH SHALL PREVENT THE HUMIDIFIER STEAM VALVE FROM OPENING IF AIR IS NOT MOVING IN THE DUCT.
- OPERATING ROOM SPACE PRESSURE CONTROL:
- THE OPERATING ROOMS REQUIRE A SPECIFIC AIR PRESSURE RELATIONSHIP RELATIVE TO ADJACENT SPACES OF 0.01 INCH W.C. POSITIVE PRESSURE. THESE SPACES HAVE BEEN PROVIDED WITH RETURN AIR AIRFLOW MONITORING AND CONTROL DAMPER STATIONS. THESE ROOMS SHALL HAVE PRESSURE SENSORS LOCATED APPROPRIATELY TO MONITOR AIR PRESSURE IN RELATION TO GENERAL PATIENT SPACES. THESE SENSORS SHALL HAVE AIR PRESSURE READOUTS AND ALARM THROUGH THE BAS WHEN RELATIONSHIPS ARE INCORRECT. SENSORS SHALL ALSO BE PROVIDED WITH DOOR INTERLOCKS ON ALL DOORS TO DELAY ALARM CONDITION WHEN DOOR IS OPENED (ADJ.).
  - THE SUPPLY AIR TERMINAL BOXES IN THE OPERATING ROOMS (OR'S) #21-23, SHALL SUPPLY A CONSTANT VOLUME OF AIR INDEPENDENT OF SYSTEM PRESSURE.
  - THE RETURN AIR DAMPERS IN THE OPERATING ROOMS (OR'S) #21-23 SHOULD POSITIVELY PRESSURIZE THE OR'S. THE RETURN AIR DAMPER SHALL MODULATE TO MAINTAIN A SPACE PRESSURE OF 0.02 INCH W.C. POSITIVE PRESSURE (ADJUSTABLE).

ISSUED FOR CONSTRUCTION  
9-12-08

CURRENT ISSUE STATUS:

REV.	DESCRIPTION	DATE
0	ISSUED FOR CONSTRUCTION	9-12-08



144 Fort Street, 3rd Floor  
Portland, Maine 04108  
Tel: (207) 772-8000  
www.smrtinc.com

**SMRT**

ARCHITECTURE  
ENGINEERING  
PLANNING  
INTERIOR DESIGN  
COMMISSIONING

MAINE MEDICAL CENTER - L.L. BEAN WING 2ND FLOOR  
SURGICAL SERVICES

SCHEDULES AND  
SEQUENCE OF OPERATIONS

SHEET TITLE	NOT TO SCALE	DATE
SEQUENCE OF OPERATIONS	GP	9-12-08

PROJECT MANAGER	DATE
GP	07

JOB CAPTAIN	SCALE
BGG	1"

DATE OF RECORD	KNE	SHEET No.
11-01-08098		M-601

PROJECT No. 08098