

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK CITY OF PORTLAND

BUILDING DEPARTMENT PERMIT

Permit Number: 081538

Please Read Application And Notes, If Any, Attached

This is to certify that MAINE MEDICAL CENTER Clean & All
has permission to Installation of Fire Protection (Sprinklers)
AT 22 BRAMHALL ST 053 D007001

provided that the person or persons, firm or corporation accounting this permit shall comply with all of the provisions of the Statutes of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of buildings and structures, and of the application on file in this department.



Apply to Public Works for street line and grade if nature of work requires such information.

Notification of inspection must be given and written permission procured before this building or part thereof is lathed or otherwise red-in. 24 HOUR NOTICE IS REQUIRED.

A certificate of occupancy must be procured by owner before this building or part thereof is occupied.

OTHER REQUIRED APPROVALS

Fire Dept.	<i>Caro Cisz</i>
Health Dept.	
Appeal Board	
Other	
Department Name	

12/16/08 *Chity J. RA*
Director - Building & Inspection Services

PENALTY FOR REMOVING THIS CARD

City of Portland, Maine - Building or Use Permit Application

389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716

Permit No: 08-1538	Issue Date: 12/14/08	CBL: 053 D007001
-----------------------	-------------------------	---------------------

Location of Construction: 22 BRAMHALL ST	Owner Name: MAINE MEDICAL CENTER	Owner Address: 22 BRAMHALL ST	Phone: 207-657-5646
Business Name:	Contractor Name: Dean & Allyn Inc.	Contractor Address: P.O. Box 709 Gray	Phone: 2076575646
Lessee/Buyer's Name	Phone:	Permit Type: Additions - Commercial	Zone: C-4

Past Use: Maine Medical Ctr/2nd Floor, Richard Bldg	Proposed Use: Maine Medical Ctr/2nd Floor, Richard Bldg - Installation of Fire Protection (Sprinklers)	Permit Fee: \$450.00	Cost of Work: \$42,800.00	CEO District: 2
---	---	-------------------------	------------------------------	--------------------

Proposed Project Description:
Installation of Fire Protection (Sprinklers)

FIRE DEPT: Approved Denied
See conditions

INSPECTION:
Use Group: I-2 Type: 2B
 IMC-2003
 IBC-2003


Signature: *[Signature]* Date: 12/14/08

PEDESTRIAN ACTIVITIES DISTRICT (P.A.D.)
 Action: Approved Approved w/Conditions Denied
 Signature: _____ Date: _____

Permit Taken By: lmd	Date Applied For: 12/10/2008	Zoning Approval
-------------------------	---------------------------------	------------------------

- This permit application does not preclude the Applicant(s) from meeting applicable State and Federal Rules.
- Building permits do not include plumbing, septic or electrical work.
- Building permits are void if work is not started within six (6) months of the date of issuance. False information may invalidate a building permit and stop all work..

Special Zone or Reviews	Zoning Appeal	Historic Preservation
<input type="checkbox"/> Shoreland	<input type="checkbox"/> Variance	<input checked="" type="checkbox"/> Not in District or Landmark
<input type="checkbox"/> Wetland	<input type="checkbox"/> Miscellaneous	<input type="checkbox"/> Does Not Require Review
<input type="checkbox"/> Flood Zone	<input type="checkbox"/> Conditional Use	<input type="checkbox"/> Requires Review
<input type="checkbox"/> Subdivision	<input type="checkbox"/> Interpretation	<input type="checkbox"/> Approved
<input type="checkbox"/> Site Plan	<input type="checkbox"/> Approved	<input type="checkbox"/> Approved w/Conditions
Maj <input checked="" type="checkbox"/> Minor <input type="checkbox"/> MM <input type="checkbox"/>	<input type="checkbox"/> Denied	<input type="checkbox"/> Denied
Date: <i>12/11/08</i>	Date: _____	Date: <i>[Signature]</i>



CERTIFICATION

I hereby certify that I am the owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his authorized agent and I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in the application is issued, I certify that the code official's authorized representative shall have the authority to enter all areas covered by such permit at any reasonable hour to enforce the provision of the code(s) applicable to such permit.

SIGNATURE OF APPLICANT	ADDRESS	DATE	PHONE
RESPONSIBLE PERSON IN CHARGE OF WORK, TITLE		DATE	PHONE

City of Portland, Maine - Building or Use Permit

389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716

Permit No: 08-1538	Date Applied For: 12/10/2008	CBL: 053 D007001
------------------------------	--	----------------------------

Location of Construction: 22 BRAMHALL ST	Owner Name: MAINE MEDICAL CENTER	Owner Address: 22 BRAMHALL ST	Phone: 207-657-5646
Business Name:	Contractor Name: Dean & Allyn Inc.	Contractor Address: P.O. Box 709 Gray	Phone: (207) 657-5646
Lessee/Buyer's Name	Phone:	Permit Type: Additions - Commercial	

Proposed Use: Maine Medical Ctr/2nd Floor, Richard Bldg - Installation of Fire Protection (Sprinklers)	Proposed Project Description: Installation of Fire Protection (Sprinklers)
--	--

Dept: Zoning	Status: Approved	Reviewer: Marge Schmuckal	Approval Date: 12/11/2008
Note:	Ok to Issue: <input checked="" type="checkbox"/>		
Dept: Building	Status: Approved with Conditions	Reviewer: Chris Hanson	Approval Date: 12/16/2008
Note:	Ok to Issue: <input checked="" type="checkbox"/>		
1) Equipment must be installed in compliance with the manufacturer's specifications			
2) All penetrations through rated assemblies must be protected by an approved firestop system installed in accordance with ASTM 814 or UL 1479, per IBC 2003 Section 712.			
Dept: Fire	Status: Approved with Conditions	Reviewer: Capt Greg Cass	Approval Date: 12/11/2008
Note:	Ok to Issue: <input checked="" type="checkbox"/>		
1) Complete "As built drawings " shall be provided to the fire dept at job completion.			
2) The Fire alarm and Sprinkler systems shall be reviewed by a licensed contractor[s] for code compliance. Compliance letters are required.			
3) A single source supplier should be used for all through penetrations.			
4) The sprinkler system shall be installed in accordance with NFPA 13.			
5) Application requires State Fire Marshal approval.			

BUILDING PERMIT INSPECTION PROCEDURES

Please call 874-8703 or 874-8693 (ONLY)

to schedule your inspections as agreed upon

Permits expire in 6 months, if the project is not started or ceases for 6 months.

The Owner or their designee is required to notify the inspections office for the following inspections and provide adequate notice. Notice must be called in 48-72 hours in advance in order to schedule an inspection:

By initializing at each inspection time, you are agreeing that you understand the inspection procedure and additional fees from a "Stop Work Order" and "Stop Work Order Release" will be incurred if the procedure is not followed as stated below.

A Pre-construction Meeting will take place upon receipt of your building permit.

 X **Final inspection required at completion of work.**

Certificate of Occupancy is not required for certain projects. Your inspector can advise you if your project requires a Certificate of Occupancy. All projects DO require a final inspection.

If any of the inspections do not occur, the project cannot go on to the next phase, REGARDLESS OF THE NOTICE OR CIRCUMSTANCES.

CERIFICATE OF OCCUPANICES MUST BE ISSUED AND PAID FOR, BEFORE THE SPACE MAY BE OCCUPIED.

Signature of Applicant/Designee

Date

Signature of Inspections Official

Date

P
D



General Building Permit Application

If you or the property owner owes real estate or personal property taxes or user charges on any property within the City, payment arrangements must be made before permits of any kind are accepted.

Location/Address of Construction: 22 BRAMHALL STREET PORTLAND, ME		
Total Square Footage of Proposed Structure		Square Footage of Lot
Tax Assessor's Chart, Block & Lot Chart# Block# Lot# 053 D 001	Owner: MAINE MEDICAL CENTER	Telephone:
Lessee/Buyer's Name (If Applicable)	Applicant name, address & telephone: 207-657-5646 DEAN F ALLYN INC P.O. BOX 709 GRAY, ME 04039	Cost Of Work: \$ 42,800.00 Fee: \$ 450.00 C of O Fee: \$
Current legal use (i.e. single family) HOSPITAL		
If vacant, what was the previous use? _____		
Proposed Specific use: PATIENT CARE		
Is property part of a subdivision? _____ If yes, please name _____		
Project description: INSTALLATION OF FIRE PROTECTION (SPRINKLERS) IN THE 2ND FLOOR OF THE RICHARDS BLDG AT THE MMC HOSPITAL		
Contractor's name, address & telephone:		
Who should we contact when the permit is ready: JAMES WHITE		
Mailing address: _____ Phone: 207-657-5646		
@ DEAN F ALLYN, INC P.O. BOX 709 GRAY, ME 04039		

Please submit all of the information outlined in the Commercial Application Checklist. Failure to do so will result in the automatic denial of your permit.

In order to be sure the City fully understands the full scope of the project, the Planning and Development Department may request additional information prior to the issuance of a permit. For further information or to download copies of this form and other applications visit the Inspections Division on-line at www.portlandmaine.gov, or stop by the Inspections Division office, room 315 City Hall or call 874-8703.

I hereby certify that I am the Owner of record of the named property, or that the owner of record authorizes the proposed work and that I have been authorized by the owner to make this application as his/her authorized agent. I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in this application is issued, I certify that the Code Official's authorized representative shall have the authority to enter all areas covered by this permit at any reasonable hour to enforce the provisions of the codes applicable to this permit.

Signature of applicant: James White	Date: 12/9/08
--	----------------------

This is not a permit; you may not commence ANY work until the permit is issued.

DEAN & ALLYN, INC.

FIRE PROTECTION · SPECIAL HAZARD

P.O. Box 709 • 32 Lewiston Road • Bldg. 1C
 Gray, ME 04039-0709
 207/657-5646 • fax 657-5647

LETTER OF TRANSMITTAL

TO PORTLAND CITY HALL (PLAN REVIEW)
380 CONGRESS ST. ROOM 315 3RD FLOOR
PORTLAND, ME 04101

DATE	12/9/08	JOB NO.	C818
ATTENTION	DONNA (PORTLAND BLDG DEPT)		
RE:	SPRINKLER SYSTEM PERMIT		
	PLEASE FIND ENCLOSED:		
	SPRINKLER LAYOUT		
	HYDRAULIC CALCS		
	CD / W/ PDF COPIES & PERMIT		
	APPLICATION W/CHECK FOR FEE		

WE ARE SENDING YOU Attached Under separate cover via _____ the following items:

- Shop drawings Prints Plans Samples Specifications
 Copy of letter Change order HYDRAULIC CALCS
 CD W/ PDF VERSION OF PLANS & CALCS

COPIES	DATE	NO.	DESCRIPTION
1	12/9	1 OF 1	SPRINKLER LAYOUT - 2ND FLOOR RICHARDS BLDG
1	12/9	WX1	HYDRAULIC CALCULATIONS
1	12/9	WX2	" "
1	12/9	WX3	" "
1	12/9	WX4	" "
1	12/9	1	PERMIT APPLICATION
1	12/9	1	CHECK # 18902 FOR \$1 450.00 (PERMIT FEE)
1	12/9	1	CD WITH PDF VERSION OF PLANS & CALCS

THESE ARE TRANSMITTED as checked below:

- For approval Approved as submitted Resubmit _____ copies for approval
 For your use Approved as noted Submit _____ copies for distribution
 As requested Returned for corrections Return _____ corrected prints
 For review and comment _____
 FOR BIDS DUE _____ PRINTS RETURNED AFTER LOAN TO US

REMARKS PLEASE FIND ENCLOSED DRAWING (SPRINKLER LAYOUT), CALCS,
CD, PERMIT APPLICATION, AND CHECK FOR \$1 450.00 - PERMIT FEE.


PLEASE CALL WITH ANY QUESTIONS OR CONCERNS.

THANK YOU

COPY TO FILE

SIGNED: James W. [Signature]

If enclosures are not as noted, kindly notify us at once.



... Fire Protection by Computer Design

DEAN & ALLYN, INC.
32 LEWISTON ROAD BUILDING 1C
P.O. BOX 709
GRAY, ME 04039
207-657-5646

Job Name : MMC 2CND FLOOR RICHARDS
Building : Richards Building
Location : Maine Medical Center-22 Bramhall St-Portland, Me
System : WX1
Contract : C0810818
Data File : MMC---2C.WX1

Hydraulic Design Information Sheet

Name - Second Floor Fire Protection Upgrade Date - 11/7/08
 Location - Maine Medical Center-22 Bramhall St-Portland, Me
 Building - Richards Building System No. - WX1
 Contractor - Dean & Allyn, Inc Contract No. - C0810818
 Calculated By - James R White Drawing No. - 1 of 1
 Construction: () Combustible (X) Non-Combustible Ceiling Height - 8'-0"
 Occupancy - Hospital- PATIENT HOLDING ROOM

S (X) NFPA 13 (X) Lt. Haz. Ord.Haz.Gp. () 1 () 2 () 3 () Ex.Haz.
 Y () NFPA 231 () NFPA 231C () Figure Curve

S Other

T Specific Ruling Made By Date

E				
M	Area of Sprinkler Operation	- 12 HEADS	System Type	Sprinkler/Nozzle
	Density	- .1	(X) Wet	Make VIKING
D	Area Per Sprinkler	- 138	() Dry	Model VK462
E	Elevation at Highest Outlet	- 8'-0"	() Deluge	Size 1/2"
S	Hose Allowance - Inside	- 100	() Preaction	K-Factor 5.6
I	Rack Sprinkler Allowance	- 0	() Other	Temp.Rat.155 deg
G	Hose Allowance - Outside	- 0		

N Note SAFETY MARGIN = 78.04 PSI - LARGEST ROOM +2 (12 HEADS)

Calculation Flow Required - 347.20 Press Required - 81.76
 Summary C-Factor Used: 120 Overhead 120 Underground

W	Water Flow Test:	Pump Data:	Tank or Reservoir:
A	Date of Test - 10/11/07	Rated Cap. -	Cap. -
T	Time of Test -	@ Press -	Elev.-
E	Static Press - 170	Elev. -	Well
R	Residual Press - 75		Proof Flow
	Flow - 1160		
S	Elevation - 0		

U Location - RICHARDS FIRE PUMP
 P Source of Information - ANNUAL PUMP TEST
 L
 Y

C	Commodity N/A	Class	Location
O	Storage Ht. N/A	Area	Aisle W.
M	Storage Method: Solid Piled	% Palletized	% Rack
M	() Single Row () Conven. Pallet	() Auto. Storage	() Encap.
S	R () Double Row () Slave Pallet	() Solid Shelf	() Non
T	A () Mult. Row	() Open Shelf	
O	C		
R	K Flue Spacing N/A	Clearance:Storage to Ceiling	
A	Longitudinal N/A	Transverse N/A	
G			
E	Horizontal Barriers Provided: N/A		

Fittings Used Summary

DEAN & ALLYN, INC.
MMC 2CND FLOOR RICHARDS

Page 2
Date 110308

Fitting Legend		1/2	3/4	1	1 1/4	1 1/2	2	2 1/2	3	3 1/2	4	5	6	8	10	12	14	16	18	20	24	
Abbrev.	Name																					
B	Generic Butterfly Valve	0	0	0	0	0	0	7	10	0	12	9	10	12	19	21	0	0	0	0	0	0
E	90' Standard Elbow	2	2	2	3	4	5	6	7	8	10	12	14	18	22	27	35	40	45	50	61	
Fsp	Flow Switch Potter VSR	Fitting generates a Fixed Loss Based on Flow																				
G	Generic Gate Valve	0	0	0	0	1	1	1	1	1	2	2	3	4	5	6	7	8	10	11	13	
Mbb	B Ball Milw BB-SC100			2.25	2	2.5	2.25	10														
N	CPVC 90'Ell Harvel-Spears	7	7	7	8	9	11	12	13	0	0	0	0	0	0	0	0	0	0	0	0	0
O	CPVC Tee - Branch	3	3	5	6	8	10	12	15	0	0	0	0	0	0	0	0	0	0	0	0	0
S	Generic Swing Check Valve	4	5	5	7	9	11	14	16	19	22	27	32	45	55	65	76	87	98	109	130	
T	90' Flow thru Tee	3	4	5	6	8	10	12	15	17	20	25	30	35	50	60	71	81	91	101	121	

Pressure / Flow Summary - STANDARD

DEAN & ALLYN, INC.
 MMC 2CND FLOOR RICHARDS

Page 3
 Date 110308

Node No.	Elevation	K-Fact	Pt Actual	Pn	Flow Actual	Density	Area	Press Req.
D001	16.0	5.6	7.0	na	14.82	0.1	115	7.0
D002	16.0	5.6	7.0	na	14.82	0.1	115	7.0
D003	30.083	5.6	8.03	na	15.87	0.1	80	7.0
D004	30.083	5.6	8.28	na	16.11	0.1	80	7.0
D005	30.083	5.6	12.94	na	20.15	0.1	96	7.0
D006	30.083	5.6	12.68	na	19.94	0.1	94	7.0
D007	30.083	5.6	13.33	na	20.45	0.1	94	7.0
D008	30.083	5.6	15.81	na	22.26	0.1	120	7.0
D009	30.083	5.6	23.31	na	27.04	0.1	80	7.0
D010	30.083	5.6	23.22	na	26.99	0.1	80	7.0
D011	30.083	5.6	18.21	na	23.9	0.1	138	7.0
D012	30.083	5.6	19.36	na	24.64	0.1	138	7.0
27	31.083		12.78	na				
28	31.083		13.32	na				
29	31.083		15.87	na				
26	31.083		7.11	na				
25	31.083		8.21	na				
24	31.083		7.95	na				
22	31.083		18.54	na				
23	31.083		19.52	na				
5	31.083		23.37	na				
17	31.083		23.42	na				
18	31.083		23.59	na				
19	31.083		24.03	na				
20	31.083		43.22	na				
21	31.083		43.31	na				
8	31.083		49.81	na				
15	31.083		63.14	na				
16	31.083		68.78	na				
14B	11.5		77.31	na				
1	31.083		6.88	na				
2	31.083		7.39	na				
3	31.083		8.53	na				
4	31.083		12.92	na				
6	31.083		23.5	na				
7	31.083		24.81	na				
9	31.083		49.4	na				
10	31.083		47.58	na				
11	31.083		51.58	na				
12	31.083		54.73	na	100.0			
13	31.083		68.35	na				
14	11.5		76.91	na				
14A	3.0		81.24	na				
TEST	3.0		81.76	na				

The maximum velocity is 27.63 and it occurs in the pipe between nodes 4 and 5

Final Calculations - Hazen-Williams

DEAN & ALLYN, INC.
MMC 2CND FLOOR RICHARDS

Page 4
Date 110308

Hyd. Ref. Point	Qa Qt	Dia. "C" Pf/Ft	Fitting or Eqv.	Ln.	Pipe Ftng's Total	Pt Pe Pf	Pt Pv Pn	*****	Notes	*****
D001 to EQ01	29.63 29.63	1.049 120 0.2693	1T	5.0 0.0 0.0	1.000 5.000 6.000	7.000 6.099 1.616			K Factor = 5.60 Vel = 11.00	
	0.0 29.63						14.715		K Factor = 7.72	
D002 to EQ02	29.63 29.63	1.049 120 0.2693	1E	2.0 0.0 0.0	1.000 2.000 3.000	7.000 6.099 0.808			K Factor = 5.60 Vel = 11.00	
	0.0 29.63						13.907		K Factor = 7.95	
D001 to 1	14.82 14.82	1.101 150 0.0390	1N	7.0 0.0 0.0	1.000 7.000 8.000	7.000 -0.433 0.312			K Factor = 5.60 Vel = 4.99	
	0.0 14.82						6.879		K Factor = 5.65	
D002 to 26	15.04 15.04	1.101 150 0.0674	1N	7.0 0.0 0.0	1.000 7.000 8.000	7.000 -0.433 0.539			K Factor = 5.60 Vel = 5.07	
	0.0 15.04						7.106		K Factor = 5.64	
D003 to 24	15.87 15.87	1.101 150 0.0444	1N	7.0 0.0 0.0	1.000 7.000 8.000	8.031 -0.433 0.355			K Factor = 5.60 Vel = 5.35	
	0.0 15.87						7.953		K Factor = 5.63	
D004 to 25	16.11 16.11	1.101 150 0.0455	1N	7.0 0.0 0.0	1.000 7.000 8.000	8.279 -0.433 0.364			K Factor = 5.60 Vel = 5.43	
	0.0 16.11						8.210		K Factor = 5.62	
D005 to 4	20.15 20.15	1.101 150 0.0690	1O	5.0 0.0 0.0	1.000 5.000 6.000	12.943 -0.433 0.414			K Factor = 5.60 Vel = 6.79	
	0.0 20.15						12.924		K Factor = 5.61	
D006 to 27	19.94 19.94	1.101 150 0.0676	1N	7.0 0.0 0.0	1.000 7.000 8.000	12.675 -0.433 0.541			K Factor = 5.60 Vel = 6.72	
	0.0 19.94						12.783		K Factor = 5.58	
D007 to 28	20.45 20.45	1.101 150 0.0708	1O	5.0 0.0 0.0	1.000 5.000 6.000	13.332 -0.433 0.425			K Factor = 5.60 Vel = 6.89	
	0.0 20.45						13.324		K Factor = 5.60	
D008 to 29	22.26 22.26	1.101 150 0.0830	1O	5.0 0.0 0.0	1.000 5.000 6.000	15.806 -0.433 0.498			K Factor = 5.60 Vel = 7.50	

Final Calculations - Standard

DEAN & ALLYN, INC.
MMC 2CND FLOOR RICHARDS

Page 5
Date 110308

Hyd. Ref. Point	Qa Qt	Dia. "C" Pf/Ft	Fitting or Eqv.	Ln.	Pipe Ftng's Total	Pt Pe Pf	Pt Pv Pn	*****	Notes	*****
	0.0 22.26					15.871			K Factor = 5.59	
D009 to 18	27.04 27.04	1.101 150 0.1188	1O	5.0 0.0 0.0	1.000 5.000 6.000	23.307 -0.433 0.713			K Factor = 5.60 Vel = 9.11	
	0.0 27.04					23.587			K Factor = 5.57	
D010 to 6	26.99 26.99	1.101 150 0.1185	1O	5.0 0.0 0.0	1.000 5.000 6.000	23.224 -0.433 0.711			K Factor = 5.60 Vel = 9.10	
	0.0 26.99					23.502			K Factor = 5.57	
D011 to 22	23.90 23.9	1.101 150 0.0946	1N	7.0 0.0 0.0	1.000 7.000 8.000	18.214 -0.433 0.757			K Factor = 5.60 Vel = 8.05	
	0.0 23.90					18.538			K Factor = 5.55	
D012 to 23	24.64 24.64	1.101 150 0.1000	1O	5.0 0.0 0.0	1.000 5.000 6.000	19.355 -0.433 0.600			K Factor = 5.60 Vel = 8.30	
	0.0 24.64					19.522			K Factor = 5.58	
27 to 28	19.94 19.94	1.101 150 0.0676		0.0 0.0 0.0	8.000 0.0 8.000	12.783 0.0 0.541			Vel = 6.72	
28 to 29	20.44 40.38	1.101 150 0.2497	1O	5.0 0.0 0.0	5.200 5.000 10.200	13.324 0.0 2.547			Vel = 13.61	
29 to 19	22.27 62.65	1.101 150 0.5626	1O	5.0 0.0 0.0	9.500 5.000 14.500	15.871 0.0 8.157			Vel = 21.11	
	0.0 62.65					24.028			K Factor = 12.78	
26 to 2	15.04 15.04	1.101 150 0.0401	1O	5.0 0.0 0.0	2.000 5.000 7.000	7.106 0.0 0.281			Vel = 5.07	
	0.0 15.04					7.387			K Factor = 5.53	
25 to 3	16.11 16.11	1.101 150 0.0457	1O	5.0 0.0 0.0	2.000 5.000 7.000	8.210 0.0 0.320			Vel = 5.43	
	0.0 16.11					8.530			K Factor = 5.52	
24 to 3	15.87 15.87	1.101 150 0.0444	1O	5.0 0.0 0.0	8.000 5.000 13.000	7.953 0.0 0.577			Vel = 5.35	
	0.0									

Final Calculations - Standard

DEAN & ALLYN, INC.
MMC 2CND FLOOR RICHARDS

Page 6
Date 110308

Hyd. Ref. Point	Qa Qt	Dia. "C" Pf/Ft	Fitting or Eqv. Ln.	Pipe Ftg's Total	Pt Pe Pf	Pt Pv Pn	*****	Notes	*****
	15.87				8.530		K Factor =	5.43	
22 to 23	23.90 23.9	1.101 150 0.0945	0.0 0.0 0.0	10.410 0.0 10.410	18.538 0.0 0.984		Vel =	8.05	
23 to 7	24.64 48.54	1.101 150 0.3509	1O 5.0 0.0 0.0	10.080 5.000 15.080	19.522 0.0 5.291		Vel =	16.36	
	0.0 48.54				24.813		K Factor =	9.74	
5 to 17	28.51 28.51	1.598 150 0.0214	0.0 0.0 0.0	2.100 0.0 2.100	23.371 0.0 0.045		Vel =	4.56	
17 to 18	0.0 28.51	1.598 150 0.0214	0.0 0.0 0.0	8.000 0.0 8.000	23.416 0.0 0.171		Vel =	4.56	
18 to 19	27.04 55.55	1.598 150 0.0735	0.0 0.0 0.0	6.000 0.0 6.000	23.587 0.0 0.441		Vel =	8.89	
19 to 20	62.65 118.2	1.598 150 0.2966	1O 8.0 0.0 0.0	56.700 8.000 64.700	24.028 0.0 19.193		Vel =	18.91	
20 to 21	0.0 118.2	1.598 150 0.2968	0.0 0.0 0.0	0.310 0.0 0.310	43.221 0.0 0.092		Vel =	18.91	
21 to 10	0.0 118.2	1.598 150 0.2967	1O 8.0 0.0 0.0	6.370 8.000 14.370	43.313 0.0 4.263		Vel =	18.91	
	0.0 118.20				47.576		K Factor =	17.14	
8 to 15	150.24 150.24	1.598 150 0.4624	2O 16.0 0.0 0.0	12.830 16.000 28.830	49.807 0.0 13.331		Vel =	24.03	
15 to 16	0.0 150.24	2.469 120 0.0840	3E 18.0 1B 7.0 1Fsp 0.0	6.450 25.000 31.450	63.138 3.000 2.641		* Fixed loss = 3 Vel =	10.07	
16 to 14B	0.0 150.24	6.065 120 0.0011	1E 14.0 0.0 0.0	31.100 14.000 45.100	68.779 8.481 0.048		Vel =	1.67	
14B to 14A	0.0 150.24	6.065 120 0.0011	6E 84.0 2T 60.0 1G 3.0	91.000 147.000 238.000	77.308 3.681 0.252		Vel =	1.67	
	0.0 150.24				81.241		K Factor =	16.67	
1 to 2	14.82 14.82	1.101 150 0.0391	1O 5.0 0.0 0.0	8.000 5.000 13.000	6.879 0.0 0.508		Vel =	4.99	
2 to 3	15.04 29.86	1.101 150 0.1429	0.0 0.0 0.0	8.000 0.0 8.000	7.387 0.0 1.143		Vel =	10.06	

Final Calculations - Standard

DEAN & ALLYN, INC.
MMC 2CND FLOOR RICHARDS

Page 7
Date 110308

Hyd. Ref. Point	Qa Qt	Dia. "C" Pf/Ft	Fitting or Eqv.	Ln.	Pipe Ftng's Total	Pt Pe Pf	Pt Pv Pn	*****	Notes	*****
3	31.98	1.101		0.0	8.000	8.530				
to		150		0.0	0.0	0.0				
4	61.84	0.5492		0.0	8.000	4.394		Vel = 20.84		
4	20.15	1.101	1O	5.0	6.290	12.924				
to		150		0.0	5.000	0.0				
5	81.99	0.9253		0.0	11.290	10.447		Vel = 27.63		
5	-28.51	1.598		0.0	1.910	23.371				
to		150		0.0	0.0	0.0				
6	53.48	0.0686		0.0	1.910	0.131		Vel = 8.56		
6	26.99	1.598		0.0	9.000	23.502				
to		150		0.0	0.0	0.0				
7	80.47	0.1457		0.0	9.000	1.311		Vel = 12.87		
7	48.53	1.598	1O	8.0	63.660	24.813				
to		150		0.0	8.000	0.0				
8	129.0	0.3488		0.0	71.660	24.994		Vel = 20.64		
8	-150.24	1.598	1O	8.0	24.910	49.807				
to		150		0.0	8.000	0.0				
9	-21.24	-0.0124		0.0	32.910	-0.408		Vel = 3.40		
9	0.0	1.598	2N	18.0	129.120	49.399				
to		150		0.0	18.000	0.0				
10	-21.24	-0.0124		0.0	147.120	-1.823		Vel = 3.40		
10	118.20	1.598	1O	8.0	11.450	47.576				
to		150		0.0	8.000	0.0				
11	96.96	0.2057		0.0	19.450	4.000		Vel = 15.51		
11	0.0	1.598	1N	9.0	6.330	51.576				
to		150		0.0	9.000	0.0				
12	96.96	0.2056		0.0	15.330	3.152		Vel = 15.51		
12	100.00	2.067	3E	15.0	4.020	54.728		Qa = 100		
to		120	1Mbb	2.25	28.250	3.000		* Fixed loss = 3		
13	196.96	0.3293	1S	11.0	32.270	10.625		Vel = 18.83		
			1Fsp	0.0						
13	0.0	6.065	1E	14.0	31.100	68.353				
to		120		0.0	14.000	8.481				
14	196.96	0.0018		0.0	45.100	0.079		Vel = 2.19		
14	0.0	6.065	7E	98.0	207.000	76.913				
to		120	2T	60.0	164.000	3.681				
14A	196.96	0.0017	2G	6.0	371.000	0.647		Vel = 2.19		
14A	150.24	6.065	2E	28.0	12.000	81.241				
to		120	1T	30.0	93.000	0.0				
TEST	347.2	0.0050	1G	3.0	105.000	0.521		Vel = 3.86		
			1S	32.0						
	0.0									
	347.20					81.762		K Factor = 38.40		