

SECTION 23 34 23

HVAC POWER VENTILATORS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:

- 1. In-line centrifugal fans.

1.3 PERFORMANCE REQUIREMENTS

- A. Project Altitude: Base fan-performance ratings on sea level.
- B. Operating Limits: Classify according to AMCA 99.

1.4 SUBMITTALS

- A. Product Data: Include rated capacities, furnished specialties, and accessories for each type of product indicated and include the following:
  - 1. Certified fan performance curves with system operating conditions indicated.
  - 2. Submit the family of rpm curves indicating operating point relative to fan class.
  - 3. Drive construction and rating.
  - 4. Catalog cuts and dimension drawings.
  - 5. Submit all selected sheave (fan and motor) calculations.
  - 6. Correction chart for fans equipped with variable inlet vanes indicating performance at various percentage of opening.
  - 7. VFD application: Submit fan selection with system curve indication, operating point, family of all rpm curves in fan class and the "DO NOT SELECT TO THE LEFT OF THIS CURVE". The minimum rpm shall be indicated.

8. Certified fan sound-power ratings.
  9. Motor ratings and electrical characteristics, plus motor and electrical accessories.
  10. Material thickness and finishes, including color charts.
  11. Dampers, including housings, linkages, and operators.
  12. Roof curbs.
  13. Fan speed controllers.
- B. Shop Drawings: Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
1. Wiring Diagrams: Power, signal, and control wiring.
  2. Design Calculations: Calculate requirements for selecting vibration isolators and seismic restraints and for designing vibration isolation bases.
  3. Vibration Isolation Base Details: Detail fabrication, including anchorages and attachments to structure and to supported equipment. Include auxiliary motor slides and rails, and base weights.
- C. Coordination Drawings: Reflected ceiling plans and other details, drawn to scale, on which the following items are shown and coordinated with each other, based on input from installers of the items involved:
1. Roof framing and support members relative to duct penetrations.
  2. Ceiling suspension assembly members.
  3. Size and location of initial access modules for acoustical tile.
  4. Ceiling-mounted items including light fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings.
- D. Field quality-control test reports.
- E. Operation and Maintenance Data: For power ventilators to include in emergency, operation, and maintenance manuals.
- 1.5 QUALITY ASSURANCE
- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. AMCA Compliance: Products shall comply with performance requirements and shall be licensed to use the AMCA-Certified Ratings Seal.
1. Test and rate all fans in accordance with the standards of AMCA. All fans shall bear the AMCA rating and seal.
- C. NEMA Compliance: Motors and electrical accessories shall comply with NEMA standards.
- D. UL Standard: Power ventilators shall comply with UL 705.

#### 1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver fans as factory-assembled unit, to the extent allowable by shipping limitations, with protective crating and covering.
- B. Disassemble and reassemble units, as required for moving to final location, according to manufacturer's written instructions.
- C. Lift and support units with manufacturer's designated lifting or supporting points.

#### 1.7 COORDINATION

- A. Coordinate size and location of structural-steel support members.
- B. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified in Division 03.
- C. Coordinate installation of roof curbs, equipment supports, and roof penetrations. These items are specified in Division 07 Section "Roof Accessories."

#### 1.8 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Belts: One set(s) for each belt-driven unit.
  - 2. Sheaves : One set(s) for each unit

### PART 2 - PRODUCTS

#### 2.1 GENERAL

- A. Make appropriate allowances for the effects on fan performance of all installation conditions including plenum enclosures and inlet and discharge arrangements so that actual installed fan performance equals that specified.
- B. Fans shall be non-overloading and operate stably without surging at design conditions.
- C. Fan characteristic curves provided by manufacturer must be such that that the fan operating point:
  - 1. Is to the right of peak efficiency.
  - 2. Is on the steep part of the fan curve such that an increase in static pressure over the specified duty results in not more than the same percent decrease in volume (CFM) and does not affect the stability of fan operation.

3. Is no greater than 60 to 70 percent of the peak static pressure.
  4. Has the ability to provide an allowable increase in fan speed of 15 percent above the design point without surging or increasing the class of fan.
- D. Provide non-overloading design, except as noted with minimum capacities as noted and with certified ratings by AMCA. Where variable inlet vanes are used, complete assembly shall be factory installed by the fan manufacturer. The fan horsepower performance characteristics shall be within 5 percent of published catalog rating data of the standard fan without the variable inlet vanes, where no data is available for the fan with inlet vanes. Inlet vanes shall be capable of reducing flow to 20 percent of design cfm at 1-1/2 inch w.g. static pressure and maintain stable performance. Inlet vanes and all operating linkages shall be provided and assembled by fan manufacturer prior to shipment to job site.
- E. Wheel shall be factory balanced statically and dynamically. Brake horsepower ratings shall be 5 percent maximum above those noted and published for a minimum of two (2) years.
- F. Motor pulley shall be variable pitch diameter, for fans up to 25 hp and 1000 rpm, except fans with variable inlet vanes and VFD's use fixed pitch, and fixed pitch diameter, over 25 hp or 1000 rpm. Supply and install one fixed pitch pulley change, as required, per fan to balance systems. Companion sheaves shall maintain belts parallel. Belt guards shall be in compliance with OSHA regulations and with tachometer opening for fan speed measurements. Manufacturer shall provide replacement fixed pitched sheaves where needed to balance system.
- G. Provide removable flanged screens at inlets or outlets where no connecting ductwork is indicated, including inlets to fans in field erected casings.
- H. Bearings shall be ball, roller or taper. Provide pressure type lubricating fittings with pressure relief fittings extended to accessible locations. Lubricating fittings shall be similar to Alemite. Pressure relief fittings shall be similar to Keystone. For fans 27 inch and larger, provide housings horizontally split, roller bearings.
- I. The drive end of the fan shaft shall be countersunk for tachometer readings.
- J. For all fans located outdoors, except roof ventilators exposed to the weather, provide custom fitted weather guards completely enclosing the fan motor, drive and bearings. Provide weatherproof louvers in the enclosure to permit circulation of air but to exclude rain and snow. Arrange one side of the enclosure to be completely removable for access to motors, drives, bearings and other equipment located within requiring maintenance. Construct the enclosure of 16 gauge aluminum, braced with aluminum angles. Paint the fan exterior with two coats of weatherproof aluminum paint.

## 2.2 IN-LINE CENTRIFUGAL FANS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Greenheck.

2. Loren Cook Company.

- B. Description: In-line, direct driven centrifugal fans consisting of housing, wheel, outlet guide vanes, fan shaft, bearings, motor and disconnect switch, drive assembly, mounting brackets, and accessories.
- C. Housing: Split, spun aluminum with aluminum straightening vanes, inlet and outlet flanges, and support bracket adaptable to floor, side wall, or ceiling mounting.
- D. Fan Wheels: Aluminum, airfoil blades welded to aluminum hub.
- E. Accessories:
  - 1. Volume-Control Damper: Manually operated with quadrant lock, located in fan outlet.
  - 2. Companion Flanges: For inlet and outlet duct connections.

2.3 MOTORS

- A. Comply with requirements in Division 23 Section "Common Motor Requirements for HVAC Equipment."
- B. Enclosure Type: Totally enclosed, fan cooled.

2.4 SOURCE QUALITY CONTROL

- A. Sound-Power Level Ratings: Comply with AMCA 301, "Methods for Calculating Fan Sound Ratings from Laboratory Test Data." Factory test fans according to AMCA 300, "Reverberant Room Method for Sound Testing of Fans." Label fans with the AMCA-Certified Ratings Seal.
- B. Fan Performance Ratings: Establish flow rate, pressure, power, air density, speed of rotation, and efficiency by factory tests and ratings according to AMCA 210, "Laboratory Methods of Testing Fans for Rating."

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install power ventilators level and plumb.
- B. Support units using spring isolators having a static deflection of 1 inch (25 mm). Vibration- and seismic-control devices are specified in Division 23 Section "Vibration and Seismic Controls for HVAC Piping and Equipment."
  - 1. Secure vibration and seismic controls to concrete bases using anchor bolts cast in concrete base.

- C. Support suspended units from structure using threaded steel rods and spring hangers having a static deflection of 1 inch (25 mm). Vibration-control devices are specified in Division 23 Section "Vibration and Seismic Controls for HVAC Piping and Equipment."
- D. Install units with clearances for service and maintenance.
- E. Label units according to requirements specified in Division 23 Section "Identification for HVAC Piping and Equipment."

### 3.2 CONNECTIONS

- A. Duct installation and connection requirements are specified in other Division 23 Sections. Drawings indicate general arrangement of ducts and duct accessories. Make final duct connections with flexible connectors. Flexible connectors are specified in Division 23 Section "Air Duct Accessories."
- B. Install ducts adjacent to power ventilators to allow service and maintenance.
- C. Ground equipment according to Division 26 Section "Grounding and Bonding for Electrical Systems."
- D. Connect wiring according to Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."

### 3.3 FIELD QUALITY CONTROL

- A. Perform the following field tests and inspections and prepare test reports:
  - 1. Verify that shipping, blocking, and bracing are removed.
  - 2. Verify that unit is secure on mountings and supporting devices and that connections to ducts and electrical components are complete. Verify that proper thermal-overload protection is installed in motors, starters, and disconnect switches.
  - 3. Verify that cleaning and adjusting are complete.
  - 4. Disconnect fan drive from motor, verify proper motor rotation direction, and verify fan wheel free rotation and smooth bearing operation. Reconnect fan drive system, align and adjust belts, and install belt guards.
  - 5. Adjust belt tension.
  - 6. Adjust damper linkages for proper damper operation.
  - 7. Verify lubrication for bearings and other moving parts.
  - 8. Balance all fan wheels and all other moving components statically and dynamically. Where a coating is specified and it affects the balance of the fan wheel, perform the balancing after the coating has been applied.
  - 9. Verify that manual and automatic volume control and fire and smoke dampers in connected ductwork systems are in fully open position.
  - 10. Refer to Division 23 Section "Testing, Adjusting, and Balancing for HVAC" for testing, adjusting, and balancing procedures.

11. Disable automatic temperature-control operators, energize motor and confirm proper motor rotation and unit operation, adjust fan to indicated rpm, and measure and record motor voltage and amperage.
  12. For units with variable frequency drives lock out critical frequencies before initial start.
  13. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
  14. Replace fan and motor pulleys as required to achieve design airflow.
  15. Shut unit down and reconnect automatic temperature-control operators.
  16. Remove and replace malfunctioning units and retest as specified above.
- B. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

### 3.4 ADJUSTING

- A. Adjust damper linkages for proper damper operation.
- B. Adjust belt tension.
- C. Refer to Division 23 Section "Testing, Adjusting, and Balancing for HVAC" for testing, adjusting, and balancing procedures.
- D. Replace fan and motor pulleys as required to achieve design airflow.
- E. Lubricate bearings.

### 3.5 DEMONSTRATION

- A. Train Owner's maintenance personnel to adjust, operate, and maintain centrifugal fans. Refer to Division 01 Section "Demonstration and Training."

END OF SECTION