General Notes:

LEGEND:

EXISTING MANHOLE

EXISTING CONDUIT/DUCTBANK LOCATED UNDERGROUND

EXISTING CONDUIT TO BE DEMOLISHED

GENERAL NOTES:

1. ALL EXISTING AND NEW CONDUITS INDICATED ON THIS PLAN ARE ROUTED IN CONCRETE ENCASEMENTS UNLESS NOTED OTHERWISE.
2. ALL EXISTING CONDUITS INDICATED ON THIS PLAN ARE TO REMAIN UNLESS NOTED OTHERWISE.
3. COORDINATE DEMOLITION WITH PACKAGE F CONTRACTOR.
4. SEE CIVIL PLANS FOR OTHER ELECTRICAL DEMOLITION.

DEMOLITION NOTES:

D1. GENERALLY, IN AREAS SCHEDULED FOR DEMOLITION AND REMODELING, WHEN ELECTRICAL DEVICES ARE REMOVED, REMOVE EXPOSED PORTIONS OF THE BRANCH CIRCUIT WIRING AND BE RESPONSIBLE FOR MAINTAINING THE INTEGRITY OF EXISTING CIRCUITS FEEDING DEVICES THAT ARE TO REMAIN.

D2. UTILIZE, WHEREVER POSSIBLE, PRACTICAL, AND APPROVED BY THE ARCHITECT, EXISTING LIGHT POLES, CONDUIT, FEEDERS, ETC. COMPATIBLE WITH THE MATERIAL SPECIFIED FOR INSTALLATION IN THE NEW CONSTRUCTION AREAS. WHEREVER EXISTING RACEWAY SYSTEMS ARE UTILIZED, REMOVE EXISTING WIRING. IN SUCH CASES, ASSOCIATED CONDUITS AND WIRING SHALL BE ARRANGED TO ACCOMMODATE THE WIRING SHOWN ON THE DRAWING.

D3. ELECTRICAL EQUIPMENT REMOVED SHALL BE STOCKPILED FOR FUTURE REUSE. IN THE EVENT THE EXISTING DEVICES ARE NOT REUSED, THEY SHALL BE RETURNED TO THE OWNER OR DISCARDED PER OWNER DIRECTIVE.

D4. ELECTRICAL CONTRACTOR SHALL MAINTAIN THE INTEGRITY OF EXISTING SYSTEMS AND CIRCUITS, SCHEDULED TO REMAIN, DURING DEMOLITION.

DRAWING NOTES:

1. MAINTAIN POWER TO GARAGE DURING CONSTRUCTION.
2. MAINTAIN TELEPHONE SERVICE AND SECURITY CAMERA TO PUMPHOUSE DURING CONSTRUCTION.

MARK	ISSUE DATE	DESCRIPTION
A1	09/27/04	ADDENDUM NO.1
PERMIT	09/16/04	PERMIT SET
BID	08/31/04	BID SET

Issue Log



Key Plan

TRO
Architecture
Planning
Engineering
Interior Design
The Fitchie Organization
60 Bridge Street
Newton, MA 02465-1334
617-969-9400

Maine Medical Center
Pkg C - Site Utitlities
Portland, Maine MMC Project No. 21846

Drawing Title
ELECTRICAL SITE DEMOLITION PLAN

0' 15' 30' 60' 120'

Commission No.	4677	Date Issued	08/31/04
Scale	1"=30'-0"	Sheet Number	PKG-C
Drawn By	G.S.		E010
Approved By	T.S.		
Filename	4677E010		

Copyright © 2004 The Fitchie Organization