FLOORCOVERING FINISH NOTES

FLOORCOVERING MATERIALS ARE IDENTIFIED ON BOTH THE ROOM FINISH SCHEDULE AND ON THE ATTACHED FLOORCOVERING DISTRIBUTION PLAN. THE COMPLEXITY OF FINISHES/MATERIALS ARE CLARIFIED ON THE DISTRIBUTION PLANS BY ONE OF THE SYMBOLS NOTED BELOW:

FLOORCOVERING SYMBOL LEGEND:

- CARPET DISTRIBUTION SYMBOL — MATERIAL CODE
- RESILIENT TILE FLOORING DISTRIBUTION SYMBOL — MATERIAL CODE
- RESILIENT SHEET FLOORING DISTRIBUTION SYMBOL — MATERIAL CODE
- CERAMIC TILE DISTRIBUTION SYMBOL — MATERIAL CODE
- PORCELAIN TILE DISTRIBUTION SYMBOL — MATERIAL CODE
- WALK OFF MAT DISTRIBUTION SYMBOL — MATERIAL CODE
- REDUCER/TRANSITION STRIP (NOTE: NOT ALL SHOWN)

1. CARPET

CPT
AREAS DESIGNATED AS CPT SHALL RECEIVE COLLINS AND AIKMAN, STYLE: GRIDWORKS,
A COLOR: #22006 SANDALWOOD.

2. RESILIENT TILE FLOORING

VCT – VINYL COMPOSITION TILE
AREAS DESIGNATED AS VCT SHALL RECEIVE ARMSTRONG, "IMPERIAL TEXTURE"
A COLOR: #51858 SANDRIFT WHITE.

UNLESS DESIGNATED ON THE DISTRIBUTION PLANS TO RECEIVE ANOTHER COLOR ILLUSTRATED BY ONE OF THE SYMBOLS BELOW.
B COLOR: #51927 FIELD GRAY.
C COLOR: #51830 COTTAGE TAN.

SPECIAL INSTRUCTIONS: STRIATIONS TO RUN IN THE SAME DIRECTION.

3. PORCELAIN TILE

PORC T – PORCELAIN TILE
AREAS DESIGNATED AS PORC T SHALL RECEIVE: APAVISA PORCELANICO, STYLE STONETECH
A COLOR: SERIE STRATA BEIGE (24X24).

UNLESS DESIGNATED ON THE DISTRIBUTION PLANS TO RECEIVE ANOTHER COLOR ILLUSTRATED BY ONE OF THE SYMBOLS BELOW.
B COLOR: SERIE FOREST GRIS (12X12).
C COLOR: SERIE FOREST SIENA (12X12).

SPECIAL INSTRUCTIONS: GROUT TO MATCH COLOR OF FIELD TILE, SUBMIT SELECTOR TO DESIGNER.

4. WALK OFF MAT

WOM-1 – WALK OFF MAT
AREAS DESIGNATED AS WOM SHALL RECEIVE MATS INC., STYLE: ULTRA ENTRY
A COLOR: #70 GRAY.

WOM-2 – WALK OFF MAT
AREAS DESIGNATED AS WOM SHALL RECEIVE MATS INC., STYLE: SUPREME NOP
B COLOR: #27 BEIGE.

UNLESS DESIGNATED ON THE DISTRIBUTION PLANS TO RECEIVE ANOTHER COLOR ILLUSTRATED BY ONE OF THE SYMBOLS BELOW.
C COLOR: #05 NATURAL.
D COLOR: #07 CHARCOAL.

5. RUBBER BASE

AREAS TO RECEIVE RUB BASE SHALL RECEIVE: JOHNSONITE
COLOR: #32 PEBBLE.
FOR ALL RESILIENT AREAS USE COVE BASE: #32 PEBBLE.
FOR ALL CARPETED AREAS USE STRAIGHT BASE: #32 PEBBLE.

6. TRANSITION STRIPS
TRANSITION STRIPS FROM CARPET TO A DISSIMILAR MATERIAL SHALL BE JOHNSONITE, COLOR: #32 PEBBLE.

7. THE CONTRACTOR SHALL SUBMIT TO THIS OFFICE ACTUAL SAMPLES IN TRIPLICATE, OF EACH COLOR AND MATERIAL SELECTED BY THE DESIGNER FOR DESIGNER'S VERIFICATION AND APPROVAL NOT LATER THAN TWO (2) WEEKS FROM DATE OF CONTRACT. SAMPLES SHALL BE PROPERLY LABELED BY PROJECT AND CODE.

WALL FINISH NOTES

WALL FINISH MATERIALS ARE IDENTIFIED ON BOTH THE ROOM FINISH SCHEDULE AND ON THE ATTACHED WALL FINISH DISTRIBUTION PLAN. THE COMPLEXITY OF FINISHES/MATERIALS ARE CLARIFIED ON THE DISTRIBUTION PLANS BY ONE OF THE SYMBOLS NOTED BELOW:

WALL FINISH SYMBOL LEGEND:

- PAINT DISTRIBUTION SYMBOL — PAINT COLOR CODE
- VINYL WALLCOVERING DISTRIBUTION SYMBOL — VINYL WALLCOVERING COLOR CODE
- ACOUSTICAL WALLCOVERING DISTRIBUTION SYMBOL — ACOUSTICAL WALLCOVERING COLOR CODE
- FABRIC WALLCOVERING DISTRIBUTION SYMBOL — FABRIC WALLCOVERING COLOR CODE
- PLASTIC WALLCOVERING DISTRIBUTION SYMBOL — PLASTIC WALLCOVERING COLOR CODE
- CERAMIC TILE DISTRIBUTION SYMBOL — CERAMIC TILE COLOR CODE
- DENOTES COLOR ON ALL WALLS OF ROOM
- DENOTES EXTENT OF COLOR/MATERIAL
- DENOTES EXTENT OF COLOR/MATERIAL
- DENOTES COLOR/MATERIAL ABOVE
- DENOTES COLOR/MATERIAL BELOW

1. PAINT

AREAS DESIGNATED AS PTD SHALL BE DURON PAINTS AND WALLCOVERINGS
COLOR: #CW055W HONEYWIND.
EXCEPT THOSE WALLS DESIGNATED TO RECEIVE ANOTHER COLOR SO DESIGNATED BY THE SYMBOLS ILLUSTRATED BELOW:
A COLOR: #8704 STRATFORD BROWN.
B COLOR: #8724M MEADOWLARK. (NOT USED)
C COLOR: #8004M BLUE ROOM.

2. VINYL WALLCOVERING

VWC – VINYL WALLCOVERING
AREAS DESIGNATED AS VWC SHALL RECEIVE MAHARAM, STYLE: #396990 TERRAIN
A COLOR: #004 OYSTER. (NOT USED)

3. PLASTIC WALLCOVERING

PWC – PLASTIC WALLCOVERING
AREAS DESIGNATED AS PWC SHALL RECEIVE C/S ACROVYN,
B COLOR: #100 EGGSHELL.

4. CONTRACTOR SHALL SUBMIT TO THIS OFFICE ACTUAL SAMPLES IN TRIPLICATE OF ALL COLORS, MATERIALS AND PATTERNS FOR DESIGNER'S VERIFICATION AND APPROVAL, NOT LATER THAN TWO (2) WEEKS FROM DATE OF CONTRACT. SIZE OF SAMPLES SHALL BE APPROXIMATELY 12"x12". SAMPLES SHALL BE PROPERLY LABELED BY PROJECT AND CODE AND SUBMITTED FOR APPROVAL PRIOR TO CONTRACTOR ORDERING MATERIAL.

CASEWORK FINISH NOTES

CASEWORK FINISHES/MATERIALS ARE IDENTIFIED ON BOTH THE CUSTOM CASEWORK DRAWINGS AND ON THE SCHEDULE BELOW:

1. LP – LAMINATED PLASTIC

CASEWORK DESIGNATED TO RECEIVE LP SHALL BE AS FOLLOWS:
WORK SURFACES: WILSONART #D403-60 WHITE SAND.
VERTICAL SURFACES: WILSONART #D403-60 WHITE SAND.

2. SSM – SOLID SURFACE MATERIALS

SURFACES DESIGNATED TO RECEIVE SSM SHALL BE: CORIAN,
COLOR: SAVANNAH

3. ORN MTL – ORNAMENTAL METALS

VERTICAL SURFACES DESIGNATED TO RECEIVE ORN MTL SHALL BE: CHEMETAL,
COLOR: #414 NOMADIC ALUMINUM.

4. WD – HARDWOOD/VENEER STAIN

CASEWORK DESIGNATED TO RECEIVE WD SHALL BE STAINED TO MATCH:
HDWD-1: WHITE MAPLE, QUARTERED CUT, FINISH: TO MATCH ARCHITECT SAMPLE
HDWD 2: SYCAMORE, QUARTERED STEAMED, FINISH: TO MATCH ARCHITECT SAMPLE

5. SP – SOLID POLYMER PANEL

CASEWORK DESIGNATED TO RECEIVE SP SHALL BE: 3FORM, VARIA COLLECTION, TEXTURA: GENOA
COLOR: AQUA

5. SPECIALTY CASEWORK

CASEWORK NOT FULLY DESCRIBED BY THE ABOVE INFORMATION IS FURTHER CLARIFIED BY THE COLOR CODE AND SCHEDULE WHICH FOLLOWS:

COLOR CODE

CODE	MANUFACTURER	COLOR NUMBER	COLOR NAME
LP-A	WILSONART	#4637-60	MONTEREY HAZE
LP-B	WILSONART	#4639-60	MONTEREY STORM

CASEWORK SCHEDULE

ROOM NAME	ROOM NUMBERS	TRANSACTION SURFACE	WORKSURFACE	VERTICAL SURFACE
RCPT	G007-LO	SSM	SSM	ORN MTL/ LP/ LP-A/ LP-B

MISCELLANEOUS FINISH NOTES

1. KICK PLATES, PUSH PLATES, ARMOR PLATES SHALL BE STAINLESS STEEL.
2. FABRIC TACKBOARDS DESIGNATED AS TKBD-1 SHALL BE: MAHARAM TEKWALL #303601 LUSTRA, COLOR: #039 BRITE WHITE.
3. WINDOW SILLS SHALL BE CORIAN, COLOR: BISQUE.
4. WOOD HANDRAILS SHALL BE WHITE MAPLE, QUARTERED CUT, FINISH: TO MATCH ARCHITECT SAMPLE.
5. CORNER GUARDS SHALL BE C/S ACROVYN, COLOR: #100 EGGSHELL.
6. BUMPER RAILS SHALL BE C/S ACROVYN, COLOR: #100 EGGSHELL.
7. INTERIOR SOFFITS DESIGNATED AS PTD SHALL BE PAINTED CEILING WHITE.
8. INTERIOR FASCIAS DESIGNATED AS PTD SHALL BE PAINTED TO MATCH SOFFIT.
9. INTERIOR CEILINGS DESIGNATED AS PTD SHALL BE: PAINTED CEILING WHITE.
10. INTERIOR DOOR FRAMES DESIGNATED AS PTD SHALL BE PAINTED TO MATCH ADJACENT WALL.
11. INTERIOR DOORS DESIGNATED AS WD SHALL BE STAINED TO MATCH: ARCHITECT SAMPLE.
12. METAL STAIR STRUCTURES DESIGNATED AS PTD SHALL BE: DURON PAINTS AND WALLCOVERINGS, COLOR: #CW055 HONEYWIND.
13. METAL HANDRAILS DESIGNATED AS PTD SHALL BE: DURON PAINTS AND WALLCOVERINGS, COLOR: #CW055 HONEYWIND.
14. HVAC REGISTERS AND GRILLS, ELECTRICAL PANELS, ACCESS PANELS, ELECTRICAL OUTLET STRIPS AND FIRE EXTINGUISHER CABINETS SHALL BE FIELD PAINTED TO MATCH ADJACENT WALL OR ACT.

13. THE CONTRACTOR SHALL SUBMIT TO THIS OFFICE ACTUAL SAMPLES IN TRIPLICATE, OF EACH COLOR AND MATERIAL SELECTED BY THE DESIGNER FOR DESIGNER'S VERIFICATION AND APPROVAL NOT LATER THAN TWO (2) WEEKS FROM DATE OF CONTRACT. SAMPLES SHALL BE PROPERLY LABELED BY PROJECT AND CODE.

General Notes:

1. NOTE: FURTHER INFORMATION IS INCORPORATED IN THE ROOM FINISH SCHEDULE DATED 08/26/04, AND IN THE DISTRIBUTION PLANS I20B.F, I20G.F & I20G.W DATED 08/26/04.

2. THE SOLE INTENT OF THIS DOCUMENT IS TO IDENTIFY THE COLOR AND OR FINISH OF THE MATERIALS SPECIFIED. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO NOTIFY TRO OF ANY DISCREPANCIES BETWEEN ANY/ALL DOCUMENTS.

3. REFER TO THE ARCHITECTURAL SPECIFICATIONS FOR IMPORTANT INFORMATION REGARDING THE SPECIFIED FINISH MATERIALS AND MANUFACTURERS.

4. IT IS THE RESPONSIBILITY OF EACH TRADE TO SUBMIT TO THE ARCHITECT SAMPLES OF ALL MATERIALS, COLORS AND FINISHES SPECIFIED FOR APPROVAL AND VERIFICATION PRIOR TO INSTALLATION.

MARK	ISSUE DATE	DESCRIPTION
PERMIT	09/16/04	PERMIT SET
BID	08/26/04	BID SET

Issue Log



Key Plan

TRO
Architecture
Planning
Engineering
Interior Design
The Ritchie Organization
80 Bridge Street
Newton, MA 02458-1134
617-969-9400

Maine Medical Center
Pkg F - Garage / Vault / Conn / Heliport
Portland, ME MMC Project No. 21845

Drawing Title
CONNECTOR MATERIALS AND FINISHES INDEX SHEET

0' 0 0 0 0

Commission No.	4678	Date Issued	08/26/04
Scale	NTS	Sheet Number	PKG-F
Drawn By	RG		I001
Approved By	RCP		
Filename	4678I001		

Copyright © 2004 The Ritchie Organization