



GENERAL DEMOLITION NOTES:

- CONTACT ARCHITECT THROUGH RFI WITH QUESTIONS OF UNIDENTIFIED OBJECTS THAT WILL BE REQUIRED TO BE REMOVED.
- COORDINATE EXTENT OF DEMOLITION WITH LOCATIONS OF PARTITIONS DESCRIBED ON PLANS AND WITH LOCATIONS OF FINISHES NOTED AS EXISTING TO REMAIN.
- ANY WALL, PARTITION OR SURFACE DISTURBED BECAUSE OF NEW WORK OR DEMOLITION SHALL BE PATCHED AND FINISHED CONTINUOUSLY TO THE NEAREST CORNER UNLESS NOTED OTHERWISE, MATCH EXISTING ADJACENT CONSTRUCTION FINISHES, CONTINUITY AND FIRE RATINGS UNLESS NOTED OTHERWISE.
- PROTECT ALL FINISHES, MATERIALS AND EQUIPMENT NOTED AS EXISTING TO REMAIN. CONTRACTOR SHALL BE RESPONSIBLE TO REPLACE ALL FINISHES, MATERIALS AND EQUIPMENT DAMAGED DURING CONSTRUCTION.
- CLEARLY IDENTIFY & TAG MECHANICAL PLUMBING/ELECTRICAL FIXTURES OR EQUIPMENT THAT ARE STILL IN USE PRIOR TO DEMOLITION TO AVOID ACCIDENTAL REMOVAL.
- SEE M.E.P DRAWINGS FOR THE SCOPE OF DEMOLITION IN THOSE DISCIPLINES.
- FOR EXTENTS OF CEILING GRID REMOVALS AND ADJUSTMENTS REFER TO REFLECTED CEILING PLANS.
- DIMENSIONS INDICATED ± ARE EXISTING CONDITION DIMENSIONS TO BE VERIFIED IN FIELD.

DEMOLITION KEY NOTES:

- REMOVE PARTITION COMPLETE.
- REMOVE EXISTING CASEWORK COMPLETE.
- REMOVE DOOR, FRAME & HARDWARE COMPLETE AND CO-ORDINATE WITH OWNER THOSE ITEMS TO BE SALVAGED PRIOR TO REMOVAL.
- REMOVE PLUMBING FIXTURE, CAP FLUSH WITH EXISTING WALL OR FLOOR, COORDINATE WITH OWNER THOSE ITEMS TO BE SALVAGED PRIOR TO REMOVAL.
- REMOVE FIRE HOSE SYSTEM AND SALVAGE FOR RE-USE/RELOCATION AT LOCATION SHOWN ON PLAN.
- REMOVE PORTION OF PARTITION (INTERIOR OR EXTERIOR) FOR INSTALLATION OF DOOR OR WINDOW. COORDINATE EXTENTS WITH FINISHES TO REMAIN. REFERENCE DOOR SCHEDULE OR WINDOW ELEVATION.
- REMOVE EXISTING FIXTURE. REFERENCE MECHANICAL/ELECTRICAL.
- EXISTING CEILING SYSTEM TO BE REMOVED TO ALLOW MECHANICAL WORK TO BE PERFORMED.
- (NOT USED)
- REMOVE FIRE EXTINGUISHER, SALVAGE FOR RE-USE.
- REMOVE FINISH FLOOR MATERIAL (IF ANY) & BASE. PREPARE SURFACE FOR NEW FINISHES AS REQUIRED BY SCHEDULE & SPECS.
- REMOVE CEILING ASSEMBLY COMPLETE. COORDINATE EXTENTS OF REMOVAL WITH PARTITION LOCATIONS AND EXISTING FINISHES TO REMAIN.
- REMOVE MISC. WALL MOUNTED EQPM, SALVAGE FOR RE-USE. COORDINATE WITH OWNER.
- REMOVE CEILING SYSTEMS COMPLETE I.E. FRAMING MEMBERS, TRACKS WIRES ETC.
- REMOVE EXISTING WINDOWS COMPLETE PREPARE FOR GWB INFILL
- REMOVE EXISTING OR CEILING LIGHTS, DIFFUSERS & ANY OTHER EQUIPMENT. COORDINATE WITH OWNER THOSE ITEMS TO BE SALVAGED.
- REMOVE EXISTING SOFFIT COMPLETE.
- REMOVE EXISTING EXIT SIGN.

NOTES:

- SEE GENERAL NOTES ON G1002.
- FURNITURE DASHED IN BY OTHERS IS INDICATED FOR COORDINATION. PROVIDE BLOCKING FOR ALL WALL MOUNTED CASEWORK, FURNITURE, EQUIPMENT AND ANY OTHER NIC ITEM.
- REFER TO DETAILS FOR ADDITIONAL INFORMATION.

WALL LEGEND

- PARTITION TYPE, SEE G1002
- INDICATES 1-HOUR RATED PARTITION/WALL
- INDICATES 2-HOUR RATED PARTITION/WALL
- CORNER GUARD-1: S.S., 90 DEGREE
- CORNER GUARD-2: S.S., END WALL PROTECTOR
- WALL PROTECTION-UP TO 48" AFF.
- RECESSED FIRE EXTINGUISHER CABINET

144 Fore Street, P.O. Box 618
Portland, Maine 04104
Tel: (207) 772-2846
Fax: (207) 772-1070
www.smrti.com

ARCHITECTURE
ENGINEERING
PLANNING
INTERIOR DESIGN
COMMISSIONING

PROJECT NORTH

LICENSED ARCHITECT
CRAIG DAVID
PIPER
No. 2692
STATE OF MAINE 2-24-09

MAINE MEDICAL CENTER
ENDOSCOPY & VASCULAR DEPT. RENOVATION
PORTLAND, ME

ISSUED FOR CONSTRUCTION
2-24-09

REV	DESCRIPTION	DATE
0	ISSUED FOR CONSTRUCTION	2-24-09

GRAPHIC SCALE:
0" = 1"

SCALE: AS NOTED

PROJECT MANAGER: DIV

JC/DRAWN BY: DIV

A/E OF RECORD: CSP

CAD FILE: A-101-05169

PROJECT NO: 05169

DATE: 2-24-09

SHEET TITLE:
PLANS

SHEET No.
A-101

A1 REMOVALS PLAN
1/4" = 1'-0" *

A7 FLOOR PLAN
1/4" = 1'-0" *