



**Richards Wing
Ninth Floor**

Renovations

Maine Medical Center
Portland, Maine 04102

Architect
Winton Scott Architects
Portland, Maine

Mechanical Engineering
Mechanical Systems Engineers
Yarmouth, Maine

Electrical Engineering
Swiftcurrent Engineering Services
Yarmouth, Maine

Removals Plan

D 1.1

Scale: 1/8" = 1' - 0"

March 16, 2009

REMOVALS KEYED NOTES

- 1 REMOVE EXISTING METAL STUD FRAMED DRYWALL PARTITION
- 2 REMOVE EXISTING DOOR AND FRAME. SAVE HARDWARE FOR REUSE.
- 3 REMOVE HOLLOW METAL BORROWED LITE
- 4 REMOVE BUILT IN COUNTER
- 5 REMOVE WALL CABINETS, COUNTER AND BASE CABINETS
- 6 REMOVE SHELF OR SHELVES
- 7 REMOVE SINK
- 8 REMOVE MOP RECEPTOR
- 9 REMOVE SHOWER
- 10 REMOVE CLINICAL FLUSHING RIM SINK

- 11 REMOVE CLINICAL FLUSHING RIM SINK
- 12 REMOVE TOILET
- 13 REMOVE CLINICAL FLUSHING RIM SINK
- 14 REMOVE VCT FLOORING AND VINYL BASE IN THIS ROOM. GRIND FLOOR SMOOTH. PREPARE FLOOR AND WALLS FOR PROPOSED FLOORING AND BASE.
- 15 REMOVE SUSPENDED ACOUSTIC TILE CEILING AND SPRINKLER HEADS IN THIS ROOM.
- 16 REMOVE SUSPENDED ACOUSTIC TILE CEILING IN THIS ROOM.
- 17 REMOVE PLASTER FINISH TO FACE OF CMU
- 18 REMOVE EXIST 2 X 12 PROJECTED OAK WALL RAIL. SAVE HARDWARE AND RADIUSSED RETURN ENDS FOR REUSE. SEE DWGS 1.3 AND 1.4.
- 19 REMOVE EXIST 2 X 12 SURFACE MOUNTED OAK WALL RAIL. PATCH WALL TO MATCH EXISTING.

NOTES

- 1. PATCH FLOOR OPENINGS TO MATCH EXISTING 6" SLAB
- 2. GRIND SLAB AS SHOWN AT SHOWER ROOM 9128 TO PROVIDE DEPRESSED FLOOR AREA FOR DRAINAGE
- 3. PNEUMATIC TUBE STATION, CONTROLS AND AIR CONDUITS TO BE REMOVED AND REINSTALLED BY OWNER UNDER SEPARATE CONTRACT. PROVIDE POWER CONNECTION AT PROPOSED LOCATION.

- 20 REMOVE PVC WALL PROTECTION OVERLAY AND PATCH WALL TO MATCH EXISTING.
- 21 REMOVE CERAMIC TILE FLOORING IN THIS ROOM. GRIND FLOOR SMOOTH. PREPARE FLOOR AND WALLS FOR PROPOSED FLOORING AND BASE.
- 22 REMOVE CARPETING AND VINYL BASE IN THIS ROOM. GRIND FLOOR SMOOTH. PREPARE FLOOR AND WALLS FOR PROPOSED FLOORING AND BASE.
- 23 NO WORK IN THIS ROOM
- 24 REMOVE EXISTING METAL CHART CABINET AND TEMPORARILY RELOCATE DURING PHASE. REINSTALL FOLLOWING PHASE COMPLETION.
- 25 REMOVE EXISTING SPRINKLER SYSTEM DRAIN PIPING. PROVIDE REPLACEMENT PIPING TO PROPOSED MOP SINK IN ROOM 9163.