



REFLECTED CEILING NOTES

1. FIRE SPRINKLERS SHALL BE LOCATED IN ALIGNMENT WITH OTHER CEILING ITEMS, TYPICALLY.
2. FIRE SPRINKLERS SHALL BE CENTERED IN CEILING TILES.
3. LIGHT FIXTURE POSITIONS INDICATED.
4. FIRE SPRINKLERS ARE SHOWN FOR COORDINATION ONLY. ADDITIONAL SPRINKLERS MAY BE REQUIRED FOR CODE COMPLIANCE, AS DETERMINED BY THE FIRE PROTECTION ENGINEER. FIRE PROTECTION CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING A COMPLETE CODE COMPLIANT SYSTEM, INCLUDING HEADS NOT INDICATED IN THIS DRAWING. SEE MECHANICAL DRAWINGS.
5. ALIGN CEILING ITEMS AS SHOWN, WITH COMMON CENTERLINES, TYPICALLY. CENTER ITEMS IN CEILINGS, OR IN AREAS UNLESS INDICATED OTHERWISE.
6. REFER TO ROOM FINISH SCHEDULE FOR CEILING HEIGHTS AND CEILING FINISHES TO BE PROVIDED.
7. USE HALF TILES OR GREATER @ PERIMETERS AS POSSIBLE.
8. CEILING HEIGHT IS AS SCHEDULED ON A201.

SYMBOL LEGEND

- SPRINKLER HEAD.
- ⊠ EXHAUST AIR GRILLE.
- ⊞ SUPPLY AIR GRILLE.
- ⊞ RETURN AIR GRILLE.
- DOWN LIGHT.
- FLUORESCENT STRIP FIXTURE.
- 1x4 LIGHT FIXTURE.
- 2x4 LAY-IN LIGHT FIXTURE.
- 2x2 LAY-IN LIGHT FIXTURE.
- ▨ GWB CEILING.
- ▨ 2x4 SUSPENDED CEILING PANEL AND GRID ASSEMBLY.

GENERAL NOTES:

1. DO NOT SCALE THE DRAWINGS.
2. EACH TRADE TO PROVIDE SMOKE OR FIRE SEALANT AT FIRE STOPPING AND SMOKE STOPPING ASSEMBLIES SHALL BE PROVIDED BY OWNER OR WHERE CASEWORK OR WALL PENETRATIONS WHERE SEALING OR WALL HOOKS ARE TO BE PROVIDED BY CONTRACTOR FURNISHED/CONTRACTOR INSTALLED.
3. DIMENSIONS ARE FACE OF CONCRETE, FACE OF MASONRY AND OTHERS AS NOTED.
4. REFER TO ALL CONSTRUCTION DOCUMENTS FOR REQUIREMENTS WHICH MAY AFFECT THE WORK ON ANOTHER AND COORDINATE WORK.
5. REFER TO DETAILS FOR ADDITIONAL DIMENSIONAL INFORMATION.
6. CONTRACTOR TO PROVIDE BLOCKING, TYPICAL FOR ALL LOCATIONS WHERE SEALING OR WALL HOOKS ARE TO BE PROVIDED BY OWNER OR WHERE CASEWORK OR WALL PENETRATIONS WHERE SEALING OR WALL HOOKS ARE TO BE PROVIDED BY CONTRACTOR FURNISHED/CONTRACTOR INSTALLED.

ACCESSORY SCHEDULE

TAG	DESCRIPTION	QTY
(A)	SOAP DISPENSER	O/C
(B)	PAPER TOWEL DISPENSER	O/C
(C)	CONTRACTOR FURNISHED/CONTRACTOR INSTALLED	
(D)	OWNER FURNISHED/OWNER INSTALLED	

(CONTRACTOR SHALL PROVIDE BLOCKING IN WALL)

GENERAL NOTES:

1. REFER TO THIS SHEET FOR LAYOUT OF FLOORING MATERIALS. ACTUAL MATERIALS USED.
2. EACH SQUARE IN THE VCT FLOOR TILE REPRESENTS A 12"x12" TILE.
3. METAL STUDS @ 12" O.C. (1) LAYER 3/8" GWB ON TAGGED SIDE, WALL ASSEMBLY TO CEILING.
3. METAL STUDS @ 16" O.C. (1) LAYER 3/8" GWB EACH SIDE, FULL THICKNESS BATT INSULATION, WALL ASSEMBLY TO DECK.
3. METAL STUDS @ 16" O.C. (1) LAYER 3/8" GWB EACH SIDE, FULL THICKNESS BATT INSULATION, WALL ASSEMBLY TO CEILING.
- U.L. DESIGN U465, 1 HOUR RATED 3/8" METAL STUDS, 3/8" TYPE-X GWB OVER 3/8" FIRE TREATED PLYWOOD ON TAGGED SIDE TO 8'-0" A.F.F., 3/8" TYPE-X GWB ABOVE TO STRUCTURE AND ON OPPOSITE SIDE.
- 3/8" METAL STUDS @ 16" O.C. (1) LAYER 3/8" GWB EACH SIDE, FULL THICKNESS BATT INSULATION, WALL ASSEMBLY TO CEILING.
- REVERSE EXISTING PARTITION TO MATCH S4 AS REQUIRED FOR INSTALLATION OF HVAC EQUIPMENT ABOVE.
- APPLY 3/8" PLYWOOD, PAINTED, TO TAGGED SIDE OF EXISTING WALL TO 8'-0" A.F.F.
- MATCH EXISTING ADJACENT WALL TYPE, PROVIDE NECESSARY RATING IF APPLICABLE.

FLOOR FINISH LEGEND:

- RB-1 NONAPLAN MEGA #1581, MOTHER OF PEARL
- RB-2 NONAPLAN MEGA #2665, MIWI
- VCT-1 ARMSTRONG #1810 WASHED LINEN
- VCT-2 ARMSTRONG #1875 MID GRAYED BLUE
- VCT-3 ARMSTRONG #1906 TEAL

WALL LEGEND

- EXISTING PARTITION
- 1 HOUR RATED SMOKE BARRIER
- 1 HOUR RATED BARRIER
- NEW PARTITION

PROJECT INFORMATION

PROJECT: MAINE MEDICAL CENTER O.R. RENOVATION
Portland, Maine

ARCHITECTURE ENGINEERING PLANNING: SMART
144 Fore Street/P.O. Box 618
Portland, Maine 04104
Tel: (207) 772-3846
Fax: (207) 772-1070

PROJECT: FLOOR PLAN, REFLECTED CEILING PLAN AND FLOOR FINISH PLAN

DATE: 7-29-04
SCALE: 1/4" = 1'-0"

PROJECT MANAGER: CFG
JOB CAP/DRAWN: SDL/SDL
A/E OF RECORD: CFG
SMART CAD FILE: AE101-03122
PROJECT NO.: 03122

AE101