



PROJECT TITLE:  
SYSTEMS  
FLOOR PLAN

DATE: 7-27-04  
SCALE: 1/4" = 1'-0"  
GRAPHIC SCALE: 0' 1'

PROJECT MANAGER: CFG  
JOB CAP/PRMWR: SOL/LAM  
A/E OF RECORD: CFG  
SMART CAD FILE: EY101-03122  
PROJECT NO.: 03122

PROJECT: EY101

PROJECT:  
MAINE MEDICAL CENTER  
O.R. RENOVATION  
Portland, Maine

ARCHITECTURE ENGINEERING PLANNING  
SMART  
144 Fore Street/P.O. Box 618  
Portland, Maine 04104  
tel. (207) 773-3846  
fax. (207) 773-1070

PROJECT NORTH

CURRENT ISSUE STATUS:  
ISSUED FOR CONSTRUCTION  
7-27-04

REV.	DESCRIPTION	DATE
0	ISSUED FOR CONSTRUCTION	7-27-04

NOTES:

- SEE SHEET E-001 FOR LEGEND AND GENERAL NOTES.
- REFER TO MNC TELECOMMUNICATION SPECIFICATION 16600 FOR COMPONENTS, MATERIALS AND INSTALLATION REQUIREMENTS. ALL WIRING TO BE PLENUM RATED.
- ALL FIRE ALARM DEVICES SHALL BE COMPATIBLE WITH EXISTING HONEYWELL SYSTEM AND INSTALLED ON EXISTING LOOPS. CONTRACTOR TO PROVIDE ALL NECESSARY COMPONENTS, WIRING, CONDUIT AND PROGRAMMING FOR A COMPLETE AND OPERABLE SYSTEM.
- RUN ALL VOICE/DATA WIRING BACK TO NETWORK CLOSET B032 APPROXIMATELY 160' AWAY FROM AREA OF WORK. COORDINATE EXACT LOCATION WITH OWNER.
- COORDINATE ALL CONDUIT RUNS FROM DOCUMENTATION STATION WITH STRIKER COMMUNICATIONS. (619)401-8444.

KEYED NOTES:

- DUCT SMOKE DETECTOR SHALL CLOSE SMOKE DAMPER UPON SENSING OF SMOKE.
- MOUNT 18" BELOW FINISHED CEILING FOR CONNECTION TO PAR-X MACHINE.
- CONTRACTOR TO PROVIDE 2 EMPTY 2" CONDUITS WITH PULL STRINGS FROM EQUIPMENT ROOM TO WITHIN 12" OF THE FLOOR AT THE SWITCHBOARD INFINITY SIDE OF DOCUMENTATION STATION.
- CONTRACTOR TO PROVIDE 2 EMPTY 1-1/2" CONDUITS WITH PULL STRINGS FROM SKATRON BOOM TO WITHIN 12" OF FLOOR AT THE SWITCHBOARD INFINITY SIDE OF DOCUMENTATION STATION.
- CONTRACTOR TO PROVIDE 2 GANG BOX AND MOUNT IN SOFTT ABOVE DOCUMENTATION STATION APPROXIMATELY 84" AFF FOR PIZ CAMERA & SPEAKER. CONTRACTOR TO PROVIDE 1 EMPTY 1-1/2" CONDUIT WITH PULL STRING FROM BOX TO WITHIN 12" OF FLOOR AT THE SWITCHBOARD INFINITY SIDE OF DOCUMENTATION STATION.
- CONTRACTOR TO PROVIDE 1 EMPTY 2" CONDUIT FROM WITHIN DOCUMENTATION STATION TO NETWORK CLOSET B032 APPROXIMATELY 160' AWAY. COORDINATE EXACT LOCATION WITH OWNER.
- CONTRACTOR TO PROVIDE 1 EMPTY 1-1/2" CONDUIT WITH PULL STRING FROM WITHIN 12" OF FLOOR AT THE SWITCHBOARD INFINITY SIDE OF DOCUMENTATION STATION TO NETWORK CLOSET B032 APPROXIMATELY 160' AWAY. COORDINATE EXACT LOCATION WITH OWNER.
- MOUNT INSIDE DOCUMENTATION STATION CABINET ON FUTURE PLASMA MONITOR.
- MOUNT INSIDE DOCUMENTATION STATION CABINET ON SWITCHBOARD INFINITY SIDE.