



PROJECT NO. 03122	PROJECT: MAINE MEDICAL CENTER O.R. RENOVATION
SMART CAD FILE: P-101-03122	ARCHITECTURE ENGINEERING PLANNING
A/E OF RECORD: LPA	144 Fore Street/P.O. Box 618 Portland, Maine 04104 Tel. (207) 773-3846 Fax. (207) 773-1070
JOB CAP/DRWN: SOL/BGG	SM RT
PROJECT MANAGER: CFG	PROJECT NORTH
DATE: 7-29-04	ISSUED FOR CONSTRUCTION 7-29-04
SCALE: AS NOTED	ISSUED FOR CONSTRUCTION 7-29-04
SHEET TITLE: DEMOLITION AND PLUMBING PLANS	ISSUED FOR CONSTRUCTION 7-29-04
CURRENT ISSUE STATUS:	
REV. 0	DESCRIPTION
DATE 7-29-04	ISSUED FOR CONSTRUCTION

NOTE:
1. SEE M-001 FOR LEGEND AND ABBREVIATIONS.

KEYED NOTES:

- RELOCATE HW, CW, & VENT BRANCH PIPING SERVING MOP SINK TO ACCOMMODATE NEW DUCTWORK.
- CONNECT TO SCRUB SINK. SEE DETAIL M13/M-601.
- 1" HW & CW. CONNECT TO (3) AT SCRUB SINK.
- CEILING MOUNTED MEDICAL GAS SERVICE COLUMN (TRP, 2) FURNISHED BY OWNER. BASED ON SKYTRON. EACH COLUMN SHALL HAVE A RISER PLATE WITH 3/8" DIAMETER TUBE STUBS FOR THE FOLLOWING: (2) O2, (1) N2, (1) MA, (1) N2O, (2) MV. COORDINATE CONNECTION TO TUBE STUBS WITH APPROVED SUBMITTAL DRAWINGS.
- ORIO EQUIPMENT ROOM (TAG 10) FURNISHED BY OWNER. BASED ON SKYTRON. W/ (2) MV CONNECTIONS & (1) N2 CONNECTION. POINT OF CONNECTION SHALL BE TO MEDICAL GAS RISER PLATE (FURNISHED WITH EQUIPMENT) 1/2" TUBE STUBS. COORDINATE WITH FINAL APPROVED EQUIPMENT ROOM SUBMITTAL.
- ORIO MEDICAL GAS RECESSED VALVE BOX.
- MATCH SIZE OF EXISTING CW PIPING.
- INSTALL SHUT-OFF VALVES AND LOCK OPEN.