
CITY OF PORTLAND
HOUSING SAFETY OFFICE

389 Congress Street
Portland, Maine 04101

Inspection Violations

Owner/Manager KONTOS GREGORY C & CAROL A KONTOS		Inspector David Petruccelli	Inspection Date 2/10/2017
Location 879 CONGRESS ST	CBL 053 I016001	Status Follow up Required	Inspection Type Legalize Nonconforming units

Code	Int/Ext	Floor	Unit No.	Area	Compliance Date
-------------	----------------	--------------	-----------------	-------------	------------------------

1) 69.25

Violation: PORTLAND FIRE DEPARTMENT CHAPTER 10 4.6.1, 4.6.2 UNIT/SUITE NUMBERS NOT MARKED;
4.6.1 RESIDENTIAL UNITS SHALL BE DESIGNATED USING NUMERALS.

4.6.2 THE FIRST NUMERAL OF EACH RESIDENTIAL UNIT SHALL BE THE FLOOR DESIGNATION.

Notes: Basement rear

2) 80.46

Violation: NFPA 101- 7.2.1.8.1 FIRE DOORS MUST BE SELF- OR AUTO-CLOSING; A door leaf normally required to be kept closed shall not be secured in the open position at any time and shall be self-closing or automatic-closing in accordance with 7.2.1.8.2, unless otherwise permitted by 7.2.1.8.3.

Notes: Apartment doors need hinges adjusted.

3) 80.56

Violation: NFPA 101- 7.2.8.5.1 HANDRAILS REQUIRED ON STAIRS; ALL FIRE ESCAPE STAIRS SHALL HAVE WALLS OR GUARDS AND HANDRAILS ON BOTH SIDES IN ACCORDANCE WITH 7.2.8.4.1 (B).

Notes: Rear exterior stair needs graspable handrail.

4) 91.15

Violation: NFPA 70- ARTICLE 110.12 B EXPOSED WIRING CONNECTIONS; Internal parts of electrical equipment, including busbars, wiring terminals, insulators, and other surfaces, shall not be damaged or contaminated by foreign materials such as paint, plaster, cleaners, abrasives, or corrosive residues. There shall be no damaged parts that may adversely affect safe operation or mechanical strength of the equipment such as parts that are broken; bent; cut; or deteriorated by corrosion, chemical reaction, or overheating.

Notes: Several locations in basement crawl space

5) 3.011

Violation: NFPA 101- 31.3.2.1.1 BOILER PROTECTION REQUIRED; THE AREAS DESCRIBED IN TABLE 31.3.2.1.1 SHALL BE PROTECTED AS INDICATED:
BOILER AND FUEL-FIRED HEATER ROOMS SERVING MORE THAN A SINGLE DWELLING UNIT (MINIMUM SEPARATION/PROTECTION IS 1 HOUR OR SPRINKLERS)

Notes: Gas unit is basement crawl space

Comments: