

SECTION 07720

ROOF ACCESSORIES

PART 1 - GENERAL

1.01 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.02 SUMMARY

- A. This Section includes the following:
 - 1. Roof hatches.
 - 2. Ladder extension device.
- B. Related Sections include the following:
 - 1. Division 5 Section "Metal Fabrications" for ladders and miscellaneous metal framing and supports.
 - 2. Division 6 Section "Rough Carpentry" for wood nailers.
 - 3. Division 7 Section "Flashing and Sheet Metal" for shop- and field-fabricated metal siding, flashing and counterflashing, fasciae, and miscellaneous sheet metal trim and accessories.
 - 4. Division 8 Section "Unit Skylights" for individual skylights.

1.03 SUBMITTALS

- A. General: Submit in accordance with Section 01300.
- B. Product Data: For each type of product indicated. Include manufacturer's detailed technical product data; installation instructions and recommendations; construction details, materials, dimensions of individual components and profiles, and finishes.
- C. Shop Drawings: Show fabrication and installation details. Include plans, rough-in requirements, elevations, sections, details, and attachments to other Work.

1.04 QUALITY ASSURANCE

- A. Standards: Comply with the following:
 - 1. SMACNA's "Architectural Sheet Metal Manual" details for fabrication of units, including flanges and cap flashing to coordinate with type of roofing indicated.
 - 2. NRCA's "Roofing and Waterproofing Manual" details for installing units.

PART 2 - PRODUCTS

2.01 MATERIALS, GENERAL

- A. Aluminum Sheet: ASTM B 209 for alclad alloy 3005H25 or alloy and temper required to suit forming operations, with mill finish, unless otherwise indicated.
- B. Extruded Aluminum: ASTM B 221 alloy 6063-T52 or alloy and temper required to suit structural and finish requirements, with mill finish, unless otherwise indicated.
- C. Insulation: Manufacturer's standard rigid or semirigid glass-fiber board of thickness indicated.

- D. Wood Nailers: Softwood lumber, pressure treated with waterborne preservatives for aboveground use, complying with AWWPA C2; not less than 1-1/2 inches thick.
- E. Fasteners: Same metal as metals being fastened, or nonmagnetic stainless steel or other noncorrosive metal as recommended by manufacturer. Match finish of exposed fasteners with finish of material being fastened.
 - 1. Where removing exterior exposed fasteners affords access to building, provide nonremovable fastener heads.
- F. Gaskets: Manufacturer's standard tubular or fingered design of neoprene, EPDM, or PVC; or flat design of foam rubber, sponge neoprene, or cork.
- G. Bituminous Coating: SSPC-Paint 12, solvent-type bituminous mastic, nominally free of sulfur and containing no asbestos fibers, compounded for 15-mil dry film thickness per coating.
- H. Mastic Sealant: Polyisobutylene; nonhardening, nonskinning, nondrying, nonmigrating sealant.
- I. Elastomeric Sealant: Generic type recommended by unit manufacturer that is compatible with joint surfaces; ASTM C 920, Type S, Grade NS, Class 25, and Uses NT, G, A, and, as applicable to joint substrates indicated, O.

2.02 ROOF HATCHES

- A. General: Fabricate units to withstand 40-lbf/sq. ft. external and 20-lbf/sq. ft. internal loading pressure. Frame with minimum 9-inch- high, integral-curb, double-wall construction with 1-1/2-inch insulation, formed cants and cap flashing (roofing counterflashing), with welded or sealed mechanical corner joints. Provide double-wall cover (lid) construction with 1- inch- thick insulation core. Provide gasketing and equip with corrosion-resistant or hot-dip galvanized hardware including pintle hinges, hold-open devices, interior padlock hasps, and both interior and exterior latch handles.
 - 1. Manufacturer: Bilco Company.
- B. Type: Single-leaf personnel access.
 - 1. For Ladder Access: 30 by 36 inches.
- C. Material: Aluminum, sheets and extrusions; mill finish.
- D. Ladder Extension Post: Telescoping tubular section fabricated from steel that attaches to fixed ladder below hatch and that locks automatically when fully extended. Upward and downward movement shall be controlled by a stainless steel balancing mechanism.

2.03 FINISHES, GENERAL

- A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
- B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- C. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in the same piece are not acceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 - EXECUTION

3.01 INSTALLATION

- A. General: Comply with manufacturer's written instructions and recommendations. Coordinate installation of roof accessories with installation of roof deck, roof insulation, flashing, roofing membranes, penetrations, equipment, and other construction involving roof accessories to ensure that each element of the Work performs properly and that combined elements are waterproof and weathertight. Anchor roof accessories securely to supporting structural substrates so they are capable of withstanding lateral and thermal stresses, and inward and outward loading pressures.
- B. Install roof accessory items according to construction details of NRCA's "Roofing and Waterproofing Manual," unless otherwise indicated.
- C. Separation: Separate metal from incompatible metal or corrosive substrates, including wood, by coating concealed surfaces, at locations of contact, with bituminous coating or providing other permanent separation.
- D. Flange Seals: Unless otherwise indicated, set flanges of accessory units in a thick bed of roofing cement to form a seal.
- E. Cap Flashing: Where required as component of accessory, install cap flashing to provide waterproof overlap with roofing or roof flashing (as counterflashing). Seal overlap with thick bead of mastic sealant, except where overlap is indicated to be left open for ventilation.

3.02 CLEANING AND PROTECTION

- A. Clean exposed surfaces according to manufacturer's written instructions. Touch up damaged metal coatings.

END OF SECTION