


Your Store:
Scarborough, ME

Your Store: Scarborough, ME



**JELD-WEN Tradition 1-Lite
Aluminum-Clad Double Pane
Annealed New Construction Egress
Casement Window (Rough Opening:
28.75-in x 48.75-in Actual: 28-in x
48-in)**

Item #: 109969 | Model #: LOWOLTCCW2848LERH

Be the first to

\$330.61

Get 5%* Off Every Day or Special Financing**
Minimum Purchase Required

Tweet 0 8+1 0 email

FREE
Store Pickup
Your order will be ready for pickup from
Lowe's Of Scarborough, ME by
08/07/2015.

Lowe's Truck Delivery
Your order will be ready for delivery to
you from Lowe's Of Scarborough, ME
by 08/07/2015.

Parcel Shipping
Unavailable for This Order
Sent by carriers like UPS,
FedEx, USPS, etc.

**JELD-WEN Tradition 1-Lite
Aluminum-Clad
Double Pane
Annealed New
Construction Egress
Casement Window
(Rough Opening:
28.75-in x 48.75-in
Actual: 28-in x 48-in)** **\$330.61**

Description

Tradition 1-Lite Aluminum-Clad Double Pane Annealed New Construction Egress Casement Window (Rough Opening: 28.75-in x 48.75-in Actual: 28-in x 48-in)

- Tradition aluminum-clad wood casement windows are built from Auralast wood - pine for superior protection against decay and termites, and backed by our industry-leading 20-year warranty
- Durable metal cladding surrounds the exterior wood of our windows for steadfast protection from the elements
- This product features Low-E 366 insulating glass that lowers energy costs and helps homes stay cooler in the summer and warmer in the winter
- Natural unfinished wood interior that can be painted or stained to match your decor
- The integrated nailing fin adds strength and stability, and also allows for faster, easier installations

Specifications

Actual Height (Inches)	48	Warranty	20-year
Actual Width (Inches)	28	Lowe's Exclusive	No
Rough Opening Width (Inches)	28.75	Project Type	New construction
Rough Opening Height (Inches)	48.75	Meets Egress Requirement	Yes
Jamb Depth (Inches)	4.5625	Lock Type	Multi-point
Hinge Location (Exterior View)	Right	Handle Type	Folding
Venting	1-lite	Nail Fin	Integrated
Series	Tradition	J Channel	N/A
Interior Color/Finish	Wood unfinished	Mulling	Field applied
Exterior Color/Finish	Brilliant white	Wood Jamb Extension	4-9/16-in
Hardware Color/Finish	Desert sand	High Altitude Rated	No
Paintable	Yes	Hurricane Approved	No
Color/Finish Family	Silver	Miami Dade Approved	No
Includes Grid	No	Florida Product Approved	No
Grid Type	N/A	Texas Department of Insurance Approved	No
		Sound Transmission Control (STC) Rated	Yes
		Design Pressure (DP) Rating	35

Grid Width	N/A	U Value	0.32
Grid Profile	N/A	Solar Heat Gain Coefficient (SHGC)	0.21
Grid Pattern	N/A	ENERGY STAR Qualified Northern Zone	Yes
Glazing Type	Double pane	ENERGY STAR Qualified North/Central Zone	Yes
Argon Gas Insulated	Yes	ENERGY STAR Qualified South/Central Zone	Yes
Glass Strength	Annealed	ENERGY STAR Qualified Southern Zone	Yes
Frame Profile	Flat	Frame Material	Aluminum-clad
Screen Included	Full		
Screen Type	Fiberglass mesh		
Screen Frame Type	Extruded		

© 2015 Lowe's. All rights reserved. Lowe's and the gable design are registered trademarks of LF, LLC