

City of Portland, Maine – Building or Use Permit Application 389 Congress Street, 04101, Tel: (207) 874-8703, FAX: 874-8716

| | | | | | | |
|---|--|---|--|---|--|---|
| Location of Construction: 260 Vaughn Street | | Owner: Dick Stevens | | Phone: | | Permit No: 001025 |
| Owner Address: AAA | | Lessee/Buyer's Name: | | BusinessName: | | |
| Contractor Name: Taggart Construction | | Address: 4000 PG Box 255 Freeport ME 04032 | | Phone: 865-2281 | | Permit Issued: SEP 14 2000 |
| Past Use: misc | | Proposed Use: same | | COST OF WORK: \$ 96,000 | | |
| Proposed Project Description: interior renovations upgrades kitchen and bathrooms | | FIRE DEPT. <input type="checkbox"/> Approved <input type="checkbox"/> Denied Signature: | | PERMIT FEE: \$ 194.00 | | INSPECTION: Use Group: 93 Types 53 Signature: <i>[Signature]</i> Zoning Approval: 034-E-004 |
| | | | | PEDESTRIAN ACTIVITIES DISTRICT (P.A.D.) Action: Approved <input type="checkbox"/> Approved with Conditions: <input type="checkbox"/> Denied <input type="checkbox"/> Signature: _____ Date: _____ | | |
| Permit Taken By: K | | Date Applied For: Sept 1 2000 K | | | | Special Zone or Reviews: <input type="checkbox"/> Shoreland <input type="checkbox"/> Wetland <input type="checkbox"/> Flood Zone <input type="checkbox"/> Subdivision <input type="checkbox"/> Site Plan maj <input type="checkbox"/> minor <input type="checkbox"/> mm <input type="checkbox"/> |

1. This permit application does not preclude the Applicant(s) from meeting applicable State and Federal rules.
2. Building permits do not include plumbing, septic or electrical work.
3. Building permits are void if work is not started within six (6) months of the date of issuance. False information may invalidate a building permit and stop all work..

CERTIFICATION

I hereby certify that I am the owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his authorized agent and I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in the application is issued, I certify that the code official's authorized representative shall have the authority to enter all areas covered by such permit at any reasonable hour to enforce the provisions of the code(s) applicable to such permit

| | | | |
|---|----------|--------------------------|--------|
| SIGNATURE OF APPLICANT | ADDRESS: | DATE: Sept 1 2000 | PHONE: |
| RESPONSIBLE PERSON IN CHARGE OF WORK, TITLE | | | PHONE: |

White-Permit Desk Green-Assessor's Canary-D.P.W. Pink-Public File Ivory Card-Inspector

PERMIT ISSUED WITH REQUIREMENTS

PERMIT ISSUED WITH REQUIREMENTS 3

COMMENTS

9/2/00. Out site - construction run

10/23/00. Checked framing & interior plumbing test on
water OK / exterior partitions OK to close in
checked Mike Collins did electrical same time
OK to close framing ✓

1-29-01 Final Insp - some other issues - need to relocate 2 smoke
det.

Inspection Record

Type

Date

Foundation: _____

Framing: _____

Plumbing: _____

Final: _____

Other: _____

BUILDING PERMIT REPORT

DATE: 1 Sept 2000 ADDRESS: 260 Vaughn St. CBL: 03 *8

REASON FOR PERMIT: Renovations To Kitchen & Bathroom

BUILDING OWNER: Dick Stevens

PERMIT APPLICANT: _____ CONTRACTOR Taggart Const.

USE GROUP: R-2 CONSTRUCTION TYPE: 50 CONSTRUCTION COST: 95,000 PERMIT FEES: 594.00

The City's Adopted Building Code (The BOCA National Building code/1999 with City Amendments)
The City's Adopted Mechanical Code (The BOCA National Mechanical Code/1993)

CONDITION(S) OF APPROVAL


This permit is being issued with the understanding that the following conditions shall be met: *1, *11, *15, *19, *27
*29, *30, *34, *31

- *1. This permit does not excuse the applicant from meeting applicable State and Federal rules and laws.
- 2. Before concrete for foundation is placed, approvals from the Development Review Coordinator and Inspection Services must be obtained. (A 24 hour notice is required prior to inspection) "ALL LOT LINES SHALL BE CLEARLY MARKED BEFORE CALLING."
- 3. Foundation drain shall be placed around the perimeter of a foundation that consists of gravel or crushed stone containing not more than 10 percent material that passes through a No. 4 sieve. The drain shall extend a minimum of 12 inches beyond the outside edge of the footing. The thickness shall be such that the bottom of the drain is not higher than the bottom of the base under the floor, and that the top of the drain is not less than 6 inches above the top of the footing. The top of the drain shall be covered with an approved filter membrane material. Where a drain tile or perforated pipe is used, the invert of the pipe or tile shall not be higher than the floor elevation. The top of joints or top of perforations shall be protected with an approved filter membrane material. The pipe or tile shall be placed on not less than 2" of gravel or crushed stone, and shall be covered with not less than 6" of the same material. Section 1813.5.2
- 4. Foundations anchors shall be a minimum of 1/2" in diameter, 7" into the foundation wall, minimum of 12" from corners of foundation and a maximum 6' O.C. between bolts. Section 2305.17
- 5. Waterproofing and dampproofing shall be done in accordance with Section 1813.0 of the building code.
- 6. Precaution must be taken to protect concrete from freezing. Section 1908.0
- 7. It is strongly recommended that a registered land surveyor check all foundation forms before concrete is placed. This is done to verify that the proper setbacks are maintained.
- 8. Private garages located beneath habitable rooms in occupancies in Use Group R-1, R-2, R-3 or I-1 shall be separated from adjacent interior spaces by fire partitions and floor/ceiling assembly which are constructed with not less than 1-hour fire resisting rating. Private garages attached side-by-side to rooms in the above occupancies shall be completely separated from the interior spaces and the attic area by means of 1/2 inch gypsum board or the equivalent applied to the garage side. (Chapter 4, Section 407.0 of the BOCA/1999)
- 9. All chimneys and vents shall be installed and maintained as per Chapter 12 of the City's Mechanical Code. (The BOCA National Mechanical Code/1993). Chapter 12 & NFPA 211
- 10. Sound transmission control in residential building shall be done in accordance with Chapter 12, Section 1214.0 of the City's Building Code.
- *11. Guardrails & Handrails: A guardrail system is a system of building components located near the open sides of elevated walking surfaces for the purpose of minimizing the possibility of an accidental fall from the walking surface to the lower level. Minimum height all Use Groups 42". In occupancies in Use Group A,B,H-4, I-1, I-2, M and R and public garages and open parking structures, open guards shall have balusters or be of solid material such that a sphere with a diameter of 4" cannot pass through any opening. Guards shall not have an ornamental pattern that would provide a ladder effect. (Handrails shall be a minimum of 34" but not more than 38". Use Group R-3 shall not be less than 30", but not more than 38"). Handrail grip size shall have a circular cross section with an outside diameter of at least 1 1/2" and not greater than 2". (Sections 1021 & 1022.0). Handrails shall be on both sides of stairway. (Section 1014.7)
- 12. Headroom in habitable space is a minimum of 7'6". (Section 1204.0)
- 13. Stair construction in Use Group R-3 & R-4 is a minimum of 10" (read and 7 1/2" maximum rise. All other Use Group minimum 11" tread, 7" maximum rise. (Section 1014.0)
- 14. The minimum headroom in all parts of a stairway shall not be less than 80 inches. (6'8") 1014.4
- *15. Every sleeping room below the fourth story in buildings of Use Groups R and I-1 shall have at least one operable window or exterior door approved for emergency egress or rescue. The units must be operable from the inside without the use of special knowledge or separate tools. Where windows are provided as means of egress or rescue they shall have a sill height not more than 44 inches (1118mm) above the floor. All egress or rescue windows from sleeping rooms shall have a minimum net clear opening height dimension of 24 inches (610mm). The minimum net clear opening width dimension shall be 20 inches (508mm), and a minimum net clear opening of 5.7 sq. ft. (Section 1010.4)
- 16. Each apartment shall have access to two (2) separate, remote and approved means of egress. A single exit is acceptable when it exits directly from the apartment to the building exterior with no communications to other apartment units. (Section 1010.1)
- 17. All vertical openings shall be enclosed with construction having a fire rating of at least one (1) hour, including fire doors with self closer's. (Over 3 stories in height requirements for fire rating is two (2) hours. (Section 710.0)
- 18. The boiler shall be protected by enclosing with (1) hour fire rated construction including fire doors and ceiling, or by providing automatic extinguishment. (Table 302.1.1)

mlh

All single and multiple station smoke detectors shall be of an approved type and shall be installed in accordance with the provisions of the City's Building Code Chapter 9, Section 920.3.2 (BOCA National Building Code/1999), and NFPA 101 Chapter 18 & 19. (Smoke detectors shall be installed and maintained at the following locations):

- In the immediate vicinity of bedrooms
 - In all bedrooms
 - In each story within a dwelling unit, including basements
20. A portable fire extinguisher shall be located as per NFPA #10. They shall bear the label of an approved agency and be of an approved type. (Section 921.0)
 21. The Fire Alarm System shall maintained to NFPA #72 Standard.
 22. The Sprinkler System shall installed and maintained to NFPA #13 Standard.
 23. All exit signs, lights and means of egress lighting shall be done in accordance with Chapter 10 Section & Subsections 1023.0 & 1024.0 of the City's Building Code. (The BOCA National Building Code/1999)
 24. Section 25 - 135 of the Municipal Code for the City of Portland states, "No person or utility shall be granted a permit to excavate or open any street or sidewalk from the time of November 15 of each year to April 15 of the following year".
 25. The builder of a facility to which Section 4594-C of the Maine State Human Rights Act Title 5 MRSA refers, shall obtain a certification from a design professional that the plans commencing construction of the facility, the builder shall submit the certification the Division of Inspection Services.
 26. Ventilation shall meet the requirements of Chapter 12 Sections 1210.0 of the City's Building Code. (Crawl spaces & attics).
 - X 27. All electrical, plumbing and HVAC permits must be obtained by a Master Licensed holders of their trade. No closing in of walls until all electrical (min. 72 hours notice) and plumbing inspections have been done.
 28. All requirements must be met before a final Certificate of Occupancy is issued.
 - X 29. All building elements shall meet the fastening schedule as per Table 2305.2 of the City's Building Code (The BOCA National Building Code/1999).
 - X 30. Ventilation of spaces within a building shall be done in accordance with the City's Mechanical code (The BOCA National Mechanical Code/1993). (Chapter M-16)
 - (31) Please read and implement the attached Land Use Zoning report requirements. *The use of this structure is a single family only*
 32. Boring, cutting and notching shall be done in accordance with Sections 2305.3, 2305.3.1, 2305.4.4 and 2305.5.1 of the City's Building Code.
 33. Bridging shall comply with Section 2305.16.
 - X 34. Glass and glazing shall meet the requirements of Chapter 24 of the building code. (Safety Glazing Section 2405.0)
 35. All signage, shall be done in accordance with Section 3102.0 signs of the City's Building Code, (The BOCA National Building Code/1999).


J. Samuel Hobbs, Building Inspector
cc: M. McDougall, PFD
Marge Schmuckal, Zoning Administrator

PSH 11/25/99

****This Permit is herewith issued, on the basis of plans submitted and conditions placed the plans, any deviations shall require a separate approval.**

*****THIS PERMIT HAS BEEN ISSUED WITH THE UNDERSTANDING THAT ALL THE CONDITIONS OF THE APPROVAL SHALL BE COMPLETED. THEREFORE, BEFORE THE WORK IS COMPLETED A REVISED PLAN OR STATEMENT FROM THE PERMIT HOLDER SHALL BE SUBMITTED TO THIS OFFICE SHOWING OR EXPLAINING THAT THE CONDITIONS HAVE BEEN MET. IF THIS REQUIREMENT IS NOT RECEIVED YOUR CERTIFICATE OF OCCUPANCY SHALL BE WITHHELD.**

****** Certificate of Occupancy Fees: \$50.00 each**

******* All PLANS THAT REQUIRE A PROFESSIONAL DESIGN'S SEAL, (AS PER SECTION 114.0 OF THE BUILDING CODE) SHALL ALSO BE PRESENTED TO THIS DIVISION ON AUTO CAD LT. 2000 OR REQUIVALENT.**

THIS IS NOT A PERMIT/CONSTRUCTION CANNOT COMMENCE UNTIL THE PERMIT IS ISSUED

**Building or Use Permit Pre-Application
Attached Single Family Dwellings/Two-Family Dwelling
Multi-Family or Commercial Structures and Additions Thereto**

In the interest of processing your application in the quickest possible manner, please complete the Information below for a Building or Use Permit.

NOTEIf you or the property owner owes real estate or personal property taxes or user charges on ANY PROPERTY within the City, payment arrangements must be made before permits of any kind are accepted.**

| | | | |
|---|--|-------------------------------------|--|
| Location/Address of Construction (include Portion of Building): <i>260 Vaughn St. Portland, ME</i> | | | |
| Total Square Footage of Proposed Structure <i>Existing</i> | | Square Footage of Lot | |
| Tax Assessor's Chart, Block & Lot Number Chart# <i>054</i> Block# <i>E</i> Lot# <i>004</i> | | Owner: <i>Dick + Penny Stevens</i> | Telephone#: <i>temp.</i> |
| Owner's Address: <i>260 Vaughn St. Portland, ME 04101</i> | | Lessee/Buyer's Name (If Applicable) | Cost Of Work: <i>\$95,000</i> Fee <i>\$594</i> |
| Proposed Project Description: (Please be as specific as possible) <i>Interior Renovations: New Kitchen, New Bathroom, Interior Wall Changes, Electrical Upgrades.</i> | | | |
| Contractor's Name, Address & Telephone: <i>Taggart Construction, Inc. 207-865-2281 P.O. Box 255, Freeport, ME 04032</i> | | | Rec'd By: <i>[Signature]</i> |
| Current Use: <i>Residence</i> | | Proposed Use: <i>Residence</i> | |

Separate permits are required for Internal & External Plumbing, HVAC and Electrical installation.

- All construction must be conducted in compliance with the 1996 B.O.C.A. Building Code as amended by Section 6-Art II.
- All plumbing must be conducted in compliance with the State of Maine Plumbing Code.
- All Electrical Installation must comply with the 1996 National Electrical Code as amended by Section 6-Art III.
- HVAC (Heating, Ventilation and Air Conditioning) installation must comply with the 1993 BOCA Mechanical Code.

You must include the following with you application:

- 1) A Copy of Your Deed or Purchase and Sale Agreement
- 2) A Copy of your Construction Contract, if available
- 3) A Plot Plan/Site Plan

Minor or Major site plan review will be required for the above proposed projects. The attached checklist outlines the minimum standards for a site plan.

4) Building Plans

Unless exempted by State Law, construction documents must be designed by a registered design professional.

A complete set of construction drawings showing all of the following elements of construction:

- Cross Sections w/Framing details (including porches, decks w/ railings, and accessory structures)
- Floor Plans & Elevations
- Window and door schedules
- Foundation plans with required drainage and dampproofing
- Electrical and plumbing layout. Mechanical drawings for any specialized equipment such as furnaces, chimneys, gas equipment, HVAC equipment (air handling) or other types of work that may require special review must be included.

Certification

I hereby certify that I am the Owner of record of the named property, or that the proposed work is authorized by the owner of record and that I have been authorized by the owner to make this application as his/her authorized agent. I agree to conform to all applicable laws of this jurisdiction. In addition, if a permit for work described in this application is issued, I certify that the Code Official's authorized representative shall have the authority to enter all areas covered by this permit at any reasonable hour to enforce the provisions of the codes applicable to this permit.

| | |
|--|----------------------|
| Signature of applicant: <i>Peter W Taggart</i> | Date: <i>8-20-00</i> |
|--|----------------------|

Building Permit Fee: \$30.00 for the 1st \$1000. cost plus \$6.00 per \$1,000.00 construction cost thereafter.

Additional Site review and related fees are attached on a separate addendum

CITY OF PORTLAND, MAINE
HISTORIC PRESERVATION COMMITTEE

Edward Hobler, Chair
Rick Romano, Vice Chair
Susan Wroth
Camillo Breggia
Robert Parker
Steve Sewall
Cordelia Pitman

August 1, 2000

Kathleen and Richard Stevens
260 Vaughan
Portland, ME 04102

Re: 260 Vaughan Street, Certificate of Appropriateness for Chimney Removal, Window Repair/Replacement

Dear Mr. And Mrs. Stevens:

On July 24, 2000, the City of Portland's Historic Preservation Authority granted approval to your application for a Certificate of Appropriateness. Approval is for the removal of two chimneys and the restoration of existing sash readily visible from Vaughan Street, as described in the application. (Two windows at the rear of the north elevation may be replaced.)

All improvements shall be carried out as shown on the submitted plans and specifications. Changes to the approved plans and specifications and any additional work which may be undertaken must be reviewed and approved by this office prior to construction, alteration, or demolition. If, during the course of completing the approved work, conditions are encountered which prevent completing the approved work, or which require additional or alternative work, you must apply for and receive a Certificate of Appropriateness or Non-Applicability PRIOR to undertaking additional or alternative work.

This Certificate is granted upon condition that the work authorized herein is commenced within twelve (12) months after the date of issuance. If the work authorized by this Certificate is not commenced within twelve (12) months after the date of issuance or if such work is suspended in significant part for a period of one year after the time the work is commenced, such Certificate shall expire and be of no further effect; provided that, for cause, one or more extensions of time for periods not exceeding ninety (90) days each may be allowed in writing by the Department.

Sincerely,


Deborah G. Andrews
Historic Preservation Program Manager

cc: Lance Fletcher
Peter Taggart
Building Inspections


**WARRANTY DEED
MAINE STATUTORY SHORT FORM**


KNOW ALL MEN BY THESE PRESENTS, that I, JOYCE H. SELIGMAN of Portland, Maine, for consideration paid, GRANT to RICHARD S. STEVENS and KATHLEEN R. STEVENS of Annandale, Virginia, Maine, as joint tenants and not as tenants in common, with WARRANTY COVENANTS, the real property in Portland, County of Cumberland, State of Maine, as follows:

See Exhibit A attached hereto and made a part hereof.

**IN WITNESS WHEREOF, the said JOYCE H. SELIGMAN has set her hand and seal
this 03 day of April, 2000.**

Witness:





JOYCE H. SELIGMAN

State of Maine
Cumberland, ss

April 3, 2000

Then personally appeared the above-named JOYCE H. SELIGMAN and acknowledged the foregoing instrument to be her free act and deed.

Before me,



Notary Public/Attorney at Law

Charles R. Bean

(Print Name)

EXHIBIT A

A certain lot or parcel of land, with the buildings thereon, situated on the westerly side of Vaughan Street, in the City of Portland, County of Cumberland, State of Maine, being lot numbered 3 on a Plan of lots near the corner of Vaughan and Bramhall Streets, recorded in Cumberland County Registry of Deeds, in Plan Book 3, Page 34, described as follows: Beginning at a stake on said westerly side of Vaughan Street, distant one hundred thirty-four (134) feet and four and one-half ($4\frac{1}{2}$) inches southerly from the monument at the intersection of Vaughan and Bramhall Streets; thence westerly at an angle of Ninety (90) degrees, sixty-eight (68) feet, more or less, to the rear line of lot numbered One (1) on said Plan; thence northeasterly twenty-eight and one-half ($28\frac{1}{2}$) feet, more or less, by the rear line of lot numbered One (1) to the southerly corner of lot formerly of Rev. S. H., Merrill; thence northeasterly twenty-five (25) feet, more or less, by the rear line of said Merrill lot to lot numbered Four (4) on said Plan; thence easterly by the rear of said Lot numbered Four (4), thirty- three (33) feet, more or less, to the westerly line of Vaughan Street; thence southerly on the westerly line of said Vaughan Street to the point of beginning; reserving the right to pass through and across the yard of lot numbered Three (3) to and from the rear of the buildings situated on lot numbered Two (2) on said Plan.

Being the same premises conveyed to Joyce H. Seligman by Quitclaim Deed of Ira H. Hymoff dated May 27, 1977 and recorded in Cumberland County Registry of Deeds in Book 4022, Page 320. Reference is also made to the Warranty Deed of Margaret Tolman to Ira H. Hymoff and Joyce S. Hymoff dated November 12, 1970 and recorded in Cumberland County Registry of Deeds in Book 3150, Page 632.