BELOW AS APPLICABLE

2. ALL RECEPTACLES SHALL BE INSTALLED 18" AFF TO CENTERLINE OF BOX UNLESS NOTED OTHERWISE.

3. MOUNT PANELS IN RESIDENTIAL SPACES SO NO CIRCUIT BREAKER HANDLE IS HIGHER THAN 48" AFF.

4. ALL WIRING SHALL BE COPPER UNLESS DESIGNATED AS "AL". UNLESS OTHERWISE NOTED ALL WIRING SHALL BE 2*12 AWG AND 1*12 EQUIPMENT GROUNDING CONDUCTOR. HOMERUNS FED FROM A 20A-1P, 120V CIRCUIT IN EXCESS OF 70' SHALL BE *10 AWG.

5. CONNECT BATTERY BACKED EMERGENCY AND EXIT LIGHTING TO NEAREST LIGHTING CIRCUIT AHEAD OF ANY SWITCHING. CONNECT REMOTE HEADS WITH *10 AWG COPPER CONDUCTORS. AC EXIT FIXTURES SHALL BE CONNECTED TO NEAREST EMERGENCY CIRCUIT OR AS INDICATED

6. TEST ALL EMERGENCY LIGHTING UNITS FOR PROPER OPERATION OF LAMPS AND BATTERIES.

7. SEE MECHANICAL PLAN FOR HVAC UNITS, PUMPS AND FANS CONTROLLED BY THERMOSTATS (PROVIDED BY ATC CONTRACTOR).

8. FUSES AND OVERLOAD UNITS FOR MOTORS SHALL BE SIZED BASED ON ACTUAL MOTOR NAMEPLATE DATA AND IN ACCORDANCE WITH NEC. CIRCUIT BREAKERS FOR MOTORS ARE SUPPLIED AT MAX VALUE PER NEC (2.5 x FLA). SIZE IN THE FIELD IN ACCORDANCE WITH MFGR RECOMMENDATION.

9. ALL WORK SHALL COMPLY WITH NFPA70, NFPA72, NFPA101 & ALL FEDERAL, STATE & LOCAL REGULATIONS.

10. ALL PENETRATIONS THROUGH FLOORS, RATED WALLS AND PARTITIONS SHALL BE SEALED WITH UL APPROVED FIRE SEALANT MATERIAL TO MAINTAIN FIRE RATING FOR THE SEPARATION.

11. ALL ENCLOSURES, CONDUIT BODIES AND THEIR COVERS CONTAINING FIRE ALARM SYSTEM CONDUCTORS SHALL BE PAINTED RED.

12. AN EQUIPMENT GROUNDING CONDUCTOR SHALL BE INSTALLED WITH ALL FEEDERS AND BRANCH CIRCUITS. SIZE IN ACCORDANCE WITH NFPA 70 ARTICLE 250.

13. COORDINATE INSTALLATION OF VOICE/DATA OUTLETS WITH OWNER, MIS OR COMMUNICATIONS CONTRACTOR.

14. LOCATE DISCONNECTS AT EQUIPMENT AS REQUIRED BY MANUFACTURER. LOCATIONS ON DRAWINGS ARE APPROXIMATE

15. PROVIDE RISER OR PLENUM RATED CABLES ABOVE SUSPENDED CEILINGS. 16. THE CONTRACTOR SHALL SET ALL ELECTRONIC BREAKERS TO SPECIFIED TRIP SETTINGS BEFORE ENERGIZING EQUIPMENT.

17. PROVIDE EXPANSION FITTINGS FOR ALL UNDERGROUND RACEWAYS ENTERING ENCLOSURES ATTACHED TO FIXED STRUCTURES.

18. OUTDOOR RECEPTACLE COVERS SHALL COMPLY WITH NFPA 70 ARTICLE 406.9.

19. ALL CONDUCTOR INSULATION FOR BUILDING WIRE SHALL BE THWN/THHN UNLESS NOTED OTHERWISE.

20. PROVIDE ARC FAULT LABELS PER NFPA 70-ARTICLE 110.24

21. OUTLETS INSTALLED IN FIRE RATED WALLS BACK TO BACK SHALL BE SEPARATED BY 24" MINIMUM OR BE PROTECTED WITH "PUTTY PADS" PER 2009 INTERNATIONAL BUILDING CODE SECTION 713.3.2

22. PROVIDE AIR VAPOR BARRIER BOXES FOR WIRING DEVICES IN EXTERIOR WALLS AND INTERIOR SOUND CONTROL WALLS BETWEEN RESIDENT ROOMS. INSTALL PER MANUFACTURER'S INSTRUCTIONS. PROVIDE LESSCO MODEL

23. MINIMUM WIRE SIZE ON ALL BRANCH CIRCUITS SHALL BE *12.

(1)4"C -WITH 4. 500KCMIL+#2 GND-

(1) 1 1/2"C, (3) 1/0

GND

(FIRST FLOOR)

175AF

ELEVATOR (CONFIRM

MOTOR RATING)

FIRST FLOOR

SECOND FLOOR

ABBREVIATIONS

AFF

CB

CS

EC

ERL

FWU

ALTERNATING CURRENT, ABOVE COUNTER LTG LIGHTING AMERICANS WITH DISABILITIES ACT LSIG LONG TIME, SHORT TIME, INSTANTANEOUS, GROUND FAULT CIRCUIT BREAKER TRIP FUNCTIONS AS INDICATED AMP FRAME

LP LIGHTING PANELBOARD

ARC FAULT CIRCUIT INTERRUPTER MOTOR CONTROL CENTER ABOVE FINISHED FLOOR MOLDED CASE CIRCUIT BREAKER ABOVE FINISHED GRADE MAIN CIRCUIT BREAKER MAIN DISTRUBITION PANEL

AMPERES INTERRUPTING CAPACITY MANHOLE MAIN LUGS ONLY

AUTOMATIC TEMPERATURE CONTROL MANUAL TRANSFER SWITCH AUTOMATIC TRANSFER SWITCH ATS NORMALLY CLOSED OF NURSE CALL AMERICAN WIRE GAUGE NATIONAL ELECTRICAL CODE BLDG BUILDING

NFPA NATIONAL FIRE PROTECTION ASSOCIATION CONDUI1 NIGHT LIGHT CIRCUIT BREAKER NO NORMALLY OPEN CAST IRON NUMBER CIRCUIT

CKT OVERLOAD CENTERLINE POLE CENTRAL MAINE POWER (ELECTRIC UTILITY) PUBLIC ADDRES CONCRETE MASONRY UNIT PUSH BUTTON CT CURRENT TRANSFORMER POWER FACTOR

CONC PH CONCRETE PHASE CARBON STEE COPPER

TELE-POWER POLE - POLE AND CIRCUIT NUMBER AS INDICATED CABINET UNIT HEATER PUBLIC SERVICE OF NEW HAMPSHIRE (ELECTRIC UTILITY) DAMP LOCATION POTENTIAL TRANSFORMER

ELECTRICAL CONTRACTOR PVC POLYVINYL CHLORIDE EXHAUST FAN ELECTRICAL EQUIPMENT TO BE RELOCATED

EXISTING REMAINS IN PLACE ELECTRICAL EQUIPMENT TO REMAIN EXISTING RELOCATE RIGID STEEL CONDUIT EXISTING REMOVE ROOF TOP UNIT ELECTRIC UNIT HEATER ELECTRICAL EQUIPMENT TO REMOVE

ELECTRICAL WATER COOLER RVNR REDUCED VOLTAGE, NON-REVESING FIRE ALARM CONTROL PANEL SB SMART BOARD FAPS FIRE ALARM PULL STATION SUPPLY FAN SF SINGLE LINE DIAGRAM FIBER REINFORCED PLASTIC

MANUAL MOTOR STARTER SWITCH WITH THERMAL SM FULL VOLTAGE, NON-REVERSING OVERLOAD DEVICE, MOUNTED AT UNIT FURNISHED WITH UNIT SS SOLID STATE DIRECT CURRENT

3W

THIRD FLOOR

THREE WIRE

SWBD-1 SWITCHBOARD NUMBER AS DESIGNATED GFI GROUND FAULT INTERRUPTER TIME CLOCK GND TRANSFER SWITCH HID HIGH INTENSITY DISCHARGE

TOP AND BOTTOM HAND-OFF-AUTOMATIC TYPICAL TYP HORSEPOWER UNDERGROUND HIGH PRESSURE SODIUM VOLT VOLT-AMPERE INSULATED CASE CIRCUIT BREAKER VFD VARIABLE FREQUENCY DRIVE

THOUSAND AMP INTERRUPTING CAPACITY WITH THOUSAND CIRCULAR MIL WEATHERPROOF THOUSAND VOLTS XFMR TRANSFORMER THOUSAND VOLT-AMPS THOUSAND WATTS (KILOWATT) THREE PHASE LIGHTING CONTACTORS 4W FOUR WIRE LATERAL CONTROL PIT

LIGHT EMITTING DIODE

ONE-LINE DIAGRAM

SCALE: NONE

SYMBOL LEGEND

SURFACE MOUNTED POWER PANEL, SEE PANEL SCHEDULES FOR RATING RECESSED MOUNTED POWER PANEL, SEE PANEL SCHEDULES FOR RATING

(1/4) ELECTRIC MOTOR DRIVEN EQUIPMENT, HP SHOWN

H, DS, DW JUNCTION BOX, "H" DENOTES RANGE HOOD, "DS" DENOTES DISPOSAL, "DW" DENOTES DISHWASHER

SM MANUAL MOTOR STARTER SWITCH WITH THERMAL OVERLOAD DEVICE MOUNTED AT UNIT

DISCONNECT SWITCH, SIZE AND NUMBER OF POLES AS INDICATED ON DRAWING. PROVIDED BY EC UNLESS NOTED OTHERWISE. PROVIDE FUSES WHERE RECOMMENDED BY MANUFACTURER.

COMBINATION MOTOR STARTER/ DISCONNECT SWITCH WITH AUXILARY CONTACTS AND HAND-OFF-AUTO SWITCH AND RED RUN LIGHT. PROVIDED AND INSTALLED BY EC UNLESS NOTED OTHERWISE

VFD VARIABLE FREQUENCY DRIVE, PROVIDED BY MC, INSTALLED AND WIRED BY EC

DUPLEX RECEPTACLE, 20A, 125V SPEC GRADE GROUNDING TYPE, TAMPER PROOF AND MATCHING PLATE. MOUNT 18" AFF UNLESS NOTED OTHERWISE

QUAD RECEPTACLE, 20A, 125V SPEC GRADE GROUNDING TYPE, TAMPER PROOF AND MATCHING PLATE. MOUNT 18" AFF UNLESS NOTED OTHERWISE

DUPLEX RECEPTACLE, 20A, 125V SPEC GRADE GROUNDING TYPE, TAMPER PROOF AND MATCHING PLATE. MOUNT 18" AFF, BOTTOM RECEPTACLE SWITCHED.

GROUND FAULT DUPLEX RECEPTACLE 20A, 125V, TAMPER PROOF WITH MATCHING

PLATE FURNISHED W/ OUTLET. FLUSH MOUNTED 45" AFF UNLESS OTHERWISE NOTED. REFRIGERATOR DUPLEX RECEPTACLE, 20A, 125V SPEC GRADE GROUNDING TYPE

AMPER PROOF AND MATCHING PLATE. MOUNT RECEPTACLE AT 48" AFF

CL FLUSH FLOOR MOUNTED DUPLEX RECEPTACLE- 20A, 125V SPEC GRADE GROUNDING TYPE. "CL" DENOTES CEILING MONTED

-♥ RANGE OUTLET 50 AMP, 250 VOLT, GROUNDING TYPE FLUSH MOUNTED 18" AFF → DRYER OUTLET 30 AMP, 250 VOLT, GROUNDING TYPE FLUSH MOUNTED 18" AFF

----- RACEWAY & WIRING OR MC CABLE RUN CONCEALED IN WALLS/CEILINGS

---- RACEWAY & WIRING RUN EXPOSED ____ RACEWAY & WIRING RUN CONCEALED UNDER FLOOR OR BURIED 30" BELOW FINISH GRADE HOME RUN TO PANEL. WITH PANEL AND CIRCUIT NUMBER

BRANCH CIRCUIT WIRING SHALL CONSIST OF (1)1/2"C-2*12AWG+1*12GND UNLESS OTHER WISE NOTED. (*)ASTERISK DENOTED *10AWG FOR ALL CIRCUITS CONTAINED IN HOME RUN. (**)DOUBLE ASTERISK DENOTES (1)3/4"C-2*8AWG+1*10GND PROVIDE EQUIPMENT GROUNDS IN ACCORDANCE

WITH NFPA 70, ARTICLE 250.

CABLE TV JUNCTION BOX "CTV", SIZE AS REQUIRED BY CABLE UTILITY

☑ TV OUTLET LOCATION, CABLE AND JACKS BY EC

TEMPERATURE CONTROL PANEL, PROVIDED BY MC WIRED BY EC

PUSHBUTTON FOR ELECTRICALLY OPERATED DOOR, FURN W/ DOOR OPERATOR,

DOOR PUSHBUTTON-DOORBELL

□ DOOR ELECTRIC STRIKE

|오| S DOOR CHIME WITH STROBE-ADA COMMUNICATIONS REQUIREMENT

LIGHTING FIXTURES, CAPITAL LETTERS DENOTE TYPE PER

LIGHTING FIXTURE SCHEDULE. LOWER CASE LETTERS INDICATE SWITCH CONTROL. "ab" INDICATES INBOARD LAMPS CONTROLLED BY OUTBOARD SWITCHED "a" AND "b". DIAGONAL INDICATED NIGHT LIGHT (UNSWITCHED)

SELF CONTAINED EMERGENCY LIGHT W/2 HEADS DUAL-LITE (LED) MODEL LZ25NI-03L, 25 WATTS FOR 90 MINUTES, COLOR BY ARCHITECT

BATT EMERGENCY LIGHTING BATTERY PACK DUAL-LITE No LM130-12VI-0 SELF-DIAGNOSTIC

9 INTERIOR REMOTE HEAD DUAL-LITE (LED) MODEL No CPRD 1203L, COLOR BY ARCHITECT

EXTERIOR REMOTE HEAD DUAL-LITE (LED) MODEL No OCRD 1203L COLOR BY ARCHITECT

EXIT LIGHT FIXTURE, UNSWITCHED, DUAL-LITE LX-U-R-W-E OR APPROVED EQUAL

₹ EXIT/ EMERGENCY LIGHT COMBO, DUAL-LITE No EVCU-R-D4-IOR APPROVED EQUAL COLOR BY ARCHITECT

-3*1/0 & 1*8 GND IN

(TYP ALL UNIT FEEDERS)

TYPE SE CABLE

405 406 407 408 409 410

SECURITY CAMERA LOCATION, COORDINATE AND PROVIDE DUPLEX RECEPTACLE, DATA AND CONDUIT PER MANUFACTURERS RECOMMENDATIONS

CEILING MOUNTED MOTION SENSOR (WATTSTOPPER OR EQUAL) CORRIDORS: WT-2255 SENSOR & B120E-P POWER PACK. OTHER COMMON SPACES: WT-605 SENSOR & B120E-P POWER PACK. SENSORS AND RELAYS TO CONTROL CIRCUITS IN SPACES INDICATED. DEVICES SHALL PROVIDE FULL COVERAGE IN AREAS INSTALLED. DT INDICATES DUAL TECHNOLOGY

PIR INDICATED PASSIVE INFRARED TECHNOLOGY S_{MS} WALL MOUNTED SWITCH MOTION SENSOR. MOUNT AT 48" AFF UNLESS OTHER WISE NOTED SINGLE POLE SWITCH, 120V, 20A, SPEC GRADE, GROUNDING TYPE, MOUNT 48" AFF, 3=3-WAY,

S₄ S₃ 4=4-WAY, LOWER CASE LETTER INDICATES FIXTURE OR CONTROLLED LOAD. SWITCH WITH PILOT LIGHT, SWITCH SHALL BE PROVIDED W/ ENGRAVED NAMEPLATE

SRF REMOTE RANGE HOOD FAN SWITCH, CONNECT TO HOOD FAN THRU HOOD JUNCTION BOX. SRL REMOTE RANGE HOOD LIGHT SWITCH, CONNECT TO HOOD LIGHT THRU JUNCTION BOX.

SB BURNER SAFETY SWITCH, PROVIDE WITH RED PLATE, MOUNTED 72" AFF SINGLE POLE DIMMER SWITCH, 120V, 20A, SPEC GRADE, GROUNDING TYPE, MOUNT 48" AFF,

D. D SINGLE POLE DIMMER SWITCH, 12UV, ZUA, SPEC GRADE, GROUNDING THE, MICHAEL DAD. D. 3=3-WAY, 4=4-WAY, LOWER CASE LETTER INDICATES FIXTURE OR CONTROLLED LOAD.

PC PHOTOCELL

LC LIGHTING CONTACTOR

TIMECLOCK

▼ TELEPHONE/DATA DUAL JACK, MOUNT 18"AFF, RUN TWO CAT 5E CABLES BACK TO TBB ∇ DATA JACK, RUN TWO CAT 5E CABLES BACK TO TBB.

CL TO FLUSH FLOOR MOUNTED TELEPHONE/DATA DUAL JACK, RUN TWO CAT 5E CABLES

BACK TO TBB. "CL" DENOTES CEILING MOUNTED ▼ TELEPHONE JACK, MOUNT 18"AFF UNLESS NOTED OTHERWISE, RUN ONE CAT 5E CABLE

TELEPHONE BACK BOARD

WIFIROUTER, OCE CAT 5E CABLE BACK TO TBB OR IT ROOM. MOUNT ABOVE CEILING, "W" DENOTES WALL MOUNTED AT 72" AFF

IP INTERCOM PANEL IN UNIT

INTERCOM PANEL AT RECEPTION

CARD READER LOCATION: PROVIDE BOX AND 3/4" CONDUIT TO NEAREST LOCATION ABOVE SUSPENDED CEILING. PROVIDE 120V DOOR STRIKE POWER FROM NEAREST RECEPTACLE CIRCUIT.

FACE FIRE ALARM CONTROL PANEL WITH DEDICATED TELEPHONE JACK

FIRE ALARM ANNUNCIATOR PANEL

FIRE EXTINGUISHER ELECTRONIC MONITOR-SHALL BE ACCOMPLISHED THROUGH USE OF AN ADDRESSABLE INTERFACE DEVICE AND SHALL PROVIDE INPUT TO THE FACP

FIRE ALARM AUDIO/VISUAL, MOUNT 6'-8"AFF, NUMBER DENOTES CANDELA RATING. "MH" DENOTES MINIHORN, "CL" DENOTES CEILING MOUNTED. NO DESIGNATION EQUALS 15cd

F FIRE ALARM PULL STATION, MOUNT 48"AFF

りまり FIRE ALARM VISUAL STROBE ONLY, FLUSH MOUNT 6'-8" AFF, NUMBER DENOTES CANDELA RATINGS. "CL" DENOTES CEILING MOUNTED

SYSTEM CONNECTED SMOKE / CARBON MONOXIDE DETECTOR, PHOTOELECTRIC TYPE

135° SYSTEM CONNECTED FIXED TEMPERATURE HEAT DETECTOR

SMOKE DETECTOR, PHOTOELECTRIC TYPE, SYSTEM CONNECTED.

SMOKE DETECTOR, PHOTOELECTRIC TYPE, SYSTEM CONNECTED. "ER" DENOTES ELEV RECALL

SB SYSTEM CONNECTED SMOKE DETECTOR, PHOTOELECTRIC TYPE, WITH SOUNDER BASE


© CARBON MONOXIDE DETECTOR

SD DUCT SMOKE DETECTOR & TEST STATION FIRE/SMOKE DAMPER, SUPPLIED AND INSTALLED BY MECHANICAL CONTRACTOR. ELECTRICAL CONTRACTOR TO PROVIDE ALL WIRING CONNECTIONS AND FIRE

ALARM DUCT SMOKE DETECTORS, ADDRESSABLE MODULES AND PROGRAMMING

SPRINKLER SYSTEM FLOW SWITCH SUPPLIED BY SPRINKLER CONTRACTOR WIRED BY EC, VERIFY LOCATIONS WITH SPRINKLER SYSTEM TAMPER SWITCH SPRINKLER CONTRACTOR.

MAGNETIC DOOR HOLD



THIRD FLOOR

CARLETON STE SENIOR HOUS

ABBREVIATIONS DETAILS 8 **SYMBOLS** 08/08/2016 NOTES,