DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK





This is to certify that

AVESTA CARLETON LP

Located at

17 CARLETON ST

PERMIT ID: 2017-01040 **ISSUE DATE:** 08/08/2017 **CBL:** 055 A004001

has permission to **Install NFPA 13 R sprinkler system.**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise closed-in. 48 hour notice is required.

A final inspection must be completed before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

/s/ David Petruccelli /s/ Michael Russell, MS, Director

Fire Official Building Official

THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY THERE IS A PENALTY FOR REMOVING THIS CARD

Approved Property Use - Zoning

Building Inspections

Fire Department

PERMIT ID: 2017-01040 **Located at:** 17 CARLETON ST **CBL:** 055 A004001

BUILDING PERMIT INSPECTION PROCEDURES Please call 874-8703

or email: buildinginspections@portlandmaine.gov

Check the Status of Permit or Schedule an Inspection at http://www.portlandmaine.gov/planning/permitstatus.asp

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the City of Portland Inspections Division for the inspections listed below. Appointments must be requested 48 to 72 hours in advance. The inspection date will need to be confirmed by this office.

- Please read the conditions of approval that are attached to this permit.
- Permits expire in 6 months if the project is not started or ceases for 6 months.
- If the inspection requirements below are not followed, then additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.
- Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC), one set of printed approved stamped construction documents will be kept at the site of work and open to inspection by building officials.

REQUIRED INSPECTIONS:

Final - Fire

The project cannot move to the next phase prior to the required inspection and approval to continue.

If the permit requires a certificate of occupancy, it must be paid and issued to the owner or designee before the space may be occupied.

City of Portland, Maine - Building or Use Permit					refint No:	Date Applied For:	CBL:		
389 Co	ngress Street, 0	4101 Tel	: (207) 874-8703, Fax: (207	7) 874-871	6 2017-01040	06/27/2017	055	A004	001
Proposed Use:				Propos	Proposed Project Description:				
Same. Multi-family (37 units).				Insta	Install NFPA 13 R sprinkler system.				
Dept:	Historic	Status:	Approved	Reviewer	: Deborah Andrew	/s Approval Da	ate:	08/08/	2017
Note:							Ok to	Issue:	✓
Condi	tions:								
Dept:	Fire	Status:	Approved w/Conditions	Reviewei	: David Petruccell	i Approval D a		07/12/	/2017
Note:	1110	Status	ripproved we conditions	110,10,00	. David I chaccon	. Topiovai Di		Issue:	
11010.							OKIU	ibbut.	

Conditions:

- 1) The approved plans with the Building Department Approved stamp shall be maintained on site for inspection.
- 2) Notice: The first scheduled final inspection fee is at no charge. Additional inspections shall be billed at \$150 for each inspector.
- 3) Through-penetrations and membrane penetrations in fire walls, fire barrier walls, and fire resistance rated horizontal assemblies shall be protected by firestop systems or devices in conformance with NFPA 101:8.3.5 (ASTM E 814 or ANSI/UL 1479). Providing firestop labels at each firestop system or device and an onsite manual containing the detail for each firestop system or device used for the project will streamline final inspection approvals.
- 4) A Knox Box is required.
- 5) The entire sprinkler system shall be maintained in accordance with NFPA 25, Standard for Inspection, Testing and Maintenance of Water-Based Fire Protection Systems, 2008 edition.
- 6) System acceptance and commissioning must be coordinated with a fire alarm technician and suppression system contractors and the Fire Department. Call 874-8400 to schedule.
- 7) Fire department connection shall be one 5" inlet
- 8) A sprinkler supervisory system shall be provided in accordance with NFPA 101, Life Safety Code, and NFPA 72, National Fire Alarm and Signaling Code. Sprinkler supervisory systems shall monitor for water flow and sprinkler supervisory signals via an approved fire alarm panel to central station. One smoke detector shall be located over the panel, a manual pull station located at the front door, and an audible water flow alarm provided. A separate fire alarm permit is required from a certified fire alarm company.
- 9) Sprinkler supervision shall be provided in accordance with NFPA 101, Life Safety Code, and NFPA 72, National Fire Alarm and Signaling Code.
- 10 Installation shall be in accordance with the City of Portland Fire Department Regulations and NFPA 13R as published. A copy of the State Sprinkler permit with RMS date and signature and the Contractor's Material and Test Certificate for Aboveground Piping (NFPA 13R figure 10.1.2) shall be provided prior to scheduling of the final inspection.
- 11 Shall meet the requirements of NFPA 101 (2009) Chapter 30 New Apartment Buildings
- 12 Shall meet the requirements of 2009 NFPA 1 Fire Code.
- 13 NFPA 1 Fire Code Per 1.14.4 Review and approval by the AHJ shall not relieve the applicant of the responsibility of compliance with this Code.

PERMIT ID: 2017-01040 **Located at:** 17 CARLETON ST **CBL:** 055 A004001