



**Item#: 2 Location: Basement Awnings Qty: 2 Unit Price: \$790.96 Total: \$1,581.92**



Manufacturer: Marvin; clad ultimate awning – roto operating; call number: custom; frame size: 38 5/8" x 29 1/4"; masonry opening: 39 1/8" x 29 1/2"; rough opening: 39 5/8" x 29 3/4"; 4 9/16" jamb depth; 3/4" insulated glass; low E1 with argon; ogee interior glazing profile; 7/8" simulated divided lite – with spacer bar – stainless – rectangular grille – special lite cut 2 wide x 1 high: ebony clad exterior – painted interior finish – white pine interior; satin taupe folding handle; satin taupe multi – point lock; painted interior finish – white – pine interior; back prime; ebony clad exterior; screen: aluminum screen: screen wire: charcoal fiberglass mesh, screen: satin taupe frame; nailing fin; ebony clad sash exterior; painted interior finish – white pine sash interior; stainless perimeter and spacer bar; standard bottom rail; black weather strip; promotional discount.


**Item#: 3 Location: Integrity Casement Windows Qty: 4 Unit Price: \$799.52 Total: \$3,198.08**



Manufacturer: Marvin; Integrity casement – left hand; call number: custom; rough opening: 34 1/2" x 54 1/2"; 4 9/16" jamb depth; insulated glass; low E1 with argon; 2 11/32" simulated rail rectangular: standard 1.0:2.0, 7/8" simulated divided lite – with spacer bar – top lite cut 2 wide x 1 high – bottom lite cut 2 wide x 1 high: 4 rectangular lites, ebony exterior – white interior; oil rubbed bronze folding handle; white interior; ebony exterior; wood interior – ultrex exterior; screen: interior aluminum screen: screen wire: charcoal fiberglass mesh, screen: white frame; nailing fin.

\*\*\*Note: Divided lite cut alignment may not be accurately represented in the OMS drawing. Please consult your local representative for exact specifications.

**Item#: 4 Location: ~~3rd Floor Bathroom~~ Qty: ~~1~~ 2ND FLOOR BATH & STAIR Qty 3 Total: \$831.44**



Manufacturer: Marvin; Integrity traditional double hung; call number: 34 (standard width); rough opening: 34 1/2" x 55"; 4 9/16" jamb depth; oil rubbed bronze sash lock; white interior; ebony exterior; wood interior – ultrex exterior; screen: exterior aluminum screen: ebony surround, screen wire: charcoal fiberglass mesh; nailing fin; glass add for all sash/panels.

**Top & Bottom Sashes**

Insulated glass, tempered low E1 with argon, 7/8" rectangular simulated divided lite – with spacer bar – special lite cut 2 wide x 1 high: ebony exterior – white interior.

\*\*\*Note: Divided lite cut alignment may not be accurately represented in the OMS drawing. Please consult your local representative for exact specifications.

	<u>Total Material</u>	<u>\$6,758.12</u>
	Sub Total	\$6,758.12
	<u>Sales Tax (5.5%)</u>	<u>\$371.70</u>
<b>Grand Total</b>		<b>\$7,129.82</b>