

DENNIS MARTIN
 217 BRACKETT ST
 PORTLAND, ME 04102
 207-415-3877
 207-415-3877

SOUTH PORTLAND
 300 CLARKS POND PKWY
 SOUTH PORTLAND, ME 04106

Store # 2406
 Customer Account # 252315
 Associate WALTER



Line #	Description	Qty	Unit Price	Total Price
--------	-------------	-----	------------	-------------

100-1

31.5x81.75 Fire Rated Steel Single Door Unit Right Inswing

1


\$530.14

\$530.14



Call Width = 30
 Call Height = 80
 Frame Width = 31.5
 Frame Height = 81.75
 Room Location = Foyer/Entry
 Reorder = No
 Jamb Width = Adjustable 4 1/2" - 5 1/2"
 Jamb Type = 90 Minute Fire Rated
 Jamb Specie = Steel Adjustable
 Weather-Strip Type = 90 Minute Category G White
 Sill / Threshold Type = 90 Minute Adjustable
 Sill Width = 5 5/8"
 Sill Finish = Aluminum
 Protective Sill Cover = No
 SKU = 639016
 Vendor Name = S/O JELD-WEN DOOR SYSTEMS
 Vendor Number = 60075920
 Manufacturer = JELD-WEN, North Springfield (UP)
 Customer Service = 1.800.246.9131
 Catalog Version Date = 12/04/2014
 Building Code = Non-Certified
 Unit Type = Pre-Hung
 Handing & Swing = Right Inswing
 Unit Spec = All Products
 Door Bore = Double Bore
 Bore Backset = 2 3/8"
 Lockset Bore Position = 44"
 Dead Bolt Bore Position = 5 1/2"
 Bore Diameter = 2 1/8"
 Hinge Prep = 3-Hinge Prep
 Hinge Type = Spring
 Hinge Finish = Brasstone
 Hinge Size = 4" x 4"
 Hinge Radius = 5/8" Radius / Square
 First Hinge Position = 6 3/4"
 Second Hinge Position = 36"
 Third Hinge Position = 65 1/4"
 Door Finish Type = None
 Door Type = 90 Minute Fire Rated
 Door Thickness = 1 3/4"
 Door Style = 6-Panel
 Door Order Method = Store Delivery
 Brickmould Specie = None

238



Fire Door
 Schedule

238-242 Brackett St

CBL 055-B-020-001