



### FINISH SCHEDULE

ROOM NO.	ROOM NAME	FLOOR	BASE	WALLS				CEILING		REMARKS
				NORTH	EAST	SOUTH	WEST	FINISH	HEIGHT	
001	ENTRY	FL1	B1	WL1	WL1	WL1	WL1	CL1	9'-0"	
002	COOLER	FL2	B2	WL4	WL4	WL4	WL4	CL1	7'-6"	
003	STORAGE	FL1	B1	WL1	WL1	WL1	WL1	CL1	9'-0"	
004	KITCHEN	FL1	B1	WL1/WL2	WL2/WL3	WL1	WL1	CL1	9'-0"	
005	OFFICE	FL1	B1	WL1	WL1	WL1	WL1	CL1	9'-0"	
006	RESTROOM	FL1	B1	WL2	WL1	WL1	WL1	CL1	9'-0"	

### FINISH LEGEND

MARK	DESCRIPTION
FL1	RESILIENT FLOORING - ALTRO WALKWAY (PLUS) 20 OR APPROVED EQUAL
FL2	CONC SLAB - UNFINISHED
B1	RESILIENT FLOORING - ALTRO WALKWAY (PLUS) 20 OR APPROVED EQUAL
B2	1X4 WOOD
WL1	GYPSUM BOARD - PTD
WL2	3X6 CERAMIC SUBWAY TILE
WL3	S.S. METAL PANELING
WL4	PLYWOOD
CL1	GYPSUM BOARD - PTD



CONSULTANT

STATUS: PERMIT SET  
NOT FOR CONSTRUCTION

ISSUE DATE: 7.11.14

ISSUE DATE: 7.28.14

ISSUE DATE: 7.31.14

ISSUE DATE: 8.27.14

ISSUE DATE: 9.17.14

PROJECT NO: 2014-100